



HAMEL RECREATION CENTER - VIEW FROM MEMORIAL FIELD



HAMEL RECREATION CENTER - VIEW FROM EDGEWOOD ROAD

UNIVERSITY OF NEW HAMPSHIRE

HAMEL RECREATION CENTER RENOVATION AND EXPANSION

60% DESIGN DEVELOPMENT PROGRESS

JANUARY 16, 2014



UNIVERSITY ARCHITECT

UNIVERSITY OF NEW HAMPSHIRE 105 MAIN STREET DURHAM, NEW HAMPSHIRE 03824 TEL: 603-862-5052 CONTACT: DANA PETERSON, AIA

OWNER REPRESENTATIVE

HAMEL STUDENT RECREATION CENTER 128 MAIN STREET DURHAM, NEW HAMPSHIRE 03824 TEL: 603-862-2073 CONTACT: STACEY HALL

ARCHITECT

HUGHES GROUP ARCHITECTS 22630 DAVIS DRIVE, SUITE 175 STERLING, VIRGINIA 20164 TEL: 703-437-6600 CONTACT: J. LYNN REDA, AIA

3

STRUCTURAL - MEP - CIVIL - LANDSCAPE

OAK POINT ASSOCIATES
85 MIDDLE STREET
PORTSMOUTH, NEW HAMPSHIRE 03801
TEL: 603-431-1870
CONTACT: KENNETH WESTON

2

<u>AQUATICS</u>

WATER TECHNOLOGIES, INC. 100 PARK AVENUE BEAVER DAM, WISCONSIN 53916 TEL: 920-887-7375 CONTACT: SCOTT LeMONDS

Copyright 2014 © Hughes Group Architects



RHAM, NEW HAMPSHIRE 0382,

s: 105 MAIN STREET, DURHAM, I

SEAL

INTERIM REVIEW ONLY

THESE DOCUMENTS ARE INCOMPLETE
AND ARE RELEASED FOR INTERIM
REVIEW ONLY AND ARE NOT INTENDED
FOR REGULATORY APPROVAL, PERMIT,
BIDDING OR CONSTRUCTION PURPOSES

3		ITTEMORE IOVATION		HAMEL RENOV.	HAME ADDITIO
	O	TRUE NORTH		PROJECT NORTH	+
		RE\	/ISI	ONS	
	MARK	DATE		SSUE	
	ISSUANCES				
	DATE	i IS	SSUA	NCE	
	01/16/1	15 60%	6 DD	PROGRE	SS

COVER SHEET

CS-001

CIVIL NOTES:

- 1. PLAN REFERENCE: TOPOGRAPHIC PLAN OF HAMEL RECREATION CENTER, BY DOUCET SURVEY INC., MAY 10, 2013.
- 2. JURISDICTIONAL WETLANDS DELINEATED BY S.W. COLE ENGINEERING, INC. DURING APRIL 2013 IN ACCORDANCE WITH 1987 CORPS OF ENGINEERS WETLANDS DELINEATIONS MANUAL. TECHNICAL REPORT Y-87-1.
- 3. HORIZONTAL DATUM BASED ON NAD83(CORS96) NEW HAMPSHIRE STATE PLANE 2800 DERIVED FROM STATIC GPS OBSERVATION PROCESSED BY THE NATIONAL GEODETIC SURVEY ON-LINE POSITIONING USER SERVICE (OPUS).
- 4. VERTICAL DATUM BASED ON NGVD29 PER NHDOT DISK "UNH 3 133-0290", ELEV.=77.44'
- 5. UNDERGROUND UTILITY INFORMATION BASED ON SURFACE EVIDENCE AND MARKINGS BY DIG SMART OF MAINE AND UNH GIS DATA COMPILED THROUGH A COMBINATION OF HISTORICAL AND GPS COLLECTED DATA SETS.
- VERIFY EXISTING CONDITIONS AND DIMENSIONS, AND REPORT ANY DISCREPANCIES TO THE UNH PROJECT MANAGER. PROCEED WITH THE WORK ONLY AFTER THE DISCREPANCY(IES) HAS(HAVE) BEEN RESOLVED.
- 7. WORK SHALL CONFORM WITH LOCAL, STATE AND FEDERAL CODES AND ORDINANCES WHICH APPLY TO THIS PROJECT.
- 8. COMPONENTS ARE NEW WITHIN THE LIMIT(S) OF WORK AND SHALL BE PROVIDED, UNLESS NOTED OTHERWISE.
- 9. EXISTING UNDERGROUND UTILITIES ARE SHOWN IN THEIR APPROXIMATE LOCATIONS ONLY. DETERMINE THE EXACT LOCATION OF APPLICABLE UNDERGROUND UTILITIES PRIOR TO BEGINNING WORK. COORDINATE WITH THE UNH PROJECT MANAGER AND OBTAIN A "DIG SAFE" PERMIT PRIOR TO COMMENCING EXCAVATION OPERATIONS ON THE SITE. PREMARK THE AREA OF EXCAVATION IN ACCORDANCE WITH THE UNH DIGSAFE POLICY AND PRACTICES.
- 10. AT THE END OF EACH WORKING DAY, THE CONSTRUCTION SITE SHALL BE LEFT IN A SAFE, SECURE, NEAT, AND CLEAN MANNER AS APPROVED BY UNH PROJECT MANAGER.
- 11. WORK SHALL BE PROVIDED IN COMPLIANCE WITH INDUSTRIES' STANDARDS AND PERFORMED IN A WORKMANLIKE PROFESSIONAL MANNER.
- 12. PROTECT EXISTING SYSTEMS AND SURFACES TO REMAIN. DAMAGE RESULTING FROM THE CONTRACTORS OPERATIONS SHALL BE REPAIRED OR REPLACED AS APPROVED BY UNH PROJECT MANAGER.
- 13. COORDINATE THE SEQUENCE OF WORK, PROJECT SCHEDULE. TEMPORARY BARRICADES FOR PEDESTRIAN AND TRAFFIC CONTROL, STAGING AREAS, AND SITE UTILIZATION WITH THE UNH PROJECT MANAGER. COORDINATE WORK WITH UNH OUTDOOR POOL ADVANCED SITEWORK PROJECT AND VOLUME 2: OUTDOOR POOL, BATH HOUSE, PUMP HOUSE.
- 14. MATERIALS SCHEDULED TO BE REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS OTHERWISE SPECIFIED OR CLAIMED BY THE UNIVERSITY PRIOR TO REMOVAL. DISPOSE OF MATERIALS OFF-SITE IN ACCORDANCE WITH FEDERAL, STATE AND LOCAL REGULATIONS, ORDINANCES AND CODES, THERE ARE NO PROVISIONS FOR WASTE MATERIALS ON UNH PROPERTY.
- 15. GIVEN DIMENSIONS ARE FROM FACE OF CURB, FACE OF WALL, FACE OF BUILDING AND CENTERLINE OF PAVEMENT MARKING UNLESS OTHERWISE NOTED.
- 16. COORDINATE UTILITY WORK WITH THE RESPECTIVE UTILITY COMPANY. UTILITY WORK SHALL BE IN ACCORDANCE WITH UTILITY COMPANY STANDARDS AND SPECIFICATIONS.
- 17. KNOWN PERMITS REQUIRED FOR CONSTRUCTION OF THIS PROJECT INCLUDE BUT ARE NOT LIMITED TO: A. UNH DIGSAFE AND TRENCH PERMITS. B. NHDES ALTERATION OF TERRAIN COMPLIANCE WITH ENV-WQ 1503.03 GENERAL PERMIT BY RULE REQUIREMENTS. SPECIAL ATTENTION SHALL BE GIVEN TO COLD WEATHER SITE STABILIZATION REQUIREMENTS THEREIN. C. USEPA NPDES STORMWATER PERMIT NOI AND NOT. D. NHDES SEWER EXTENSION PERMIT.
- 18. UPDATE AND COMPLY WITH THE EXISTING STORMWATER POLLUTION PREVENTION PLAN (SWPPP) OR OR PREPARE A SWPPP. OBTAIN OPERATOR COVERAGE UNDER THE NHDES NOTICE OF INTENT (NOI) FOR STORMWATER DISCHARGES FROM CONSTRUCTION ACTIVITIES AND COMPLY WITH THE REQUIREMENTS AND CONDITIONS OF THE PERMIT.

SPECIAL WINTER CONDITIONS FOR **BACKFILL AND EMBANKMENT:**

- 1. FILL SHALL BE PLACED ON UNFROZEN SUBGRADE WHICH IS STABLE AND FIRM DURING PROOFROLLING/COMPACTION.
- EXPOSED STRUCTURAL FILL SHALL BE COMPACTED AT THE END OF EACH DAY IN ANTICIPATION OF FREEZING OVERNIGHT TEMPERATURES. WHEN THE PREVAILING TEMPERATURES ARE BELOW 30°F, FILL SHALL HAVE A MOISTURE CONTENT, AT THE TIME OF COMPACTION, EQUAL TO OR LESS THAN THE OPTIMUM MOISTURE CONTENT.
- FROZEN FILL WHICH IS FRIABLE MAY REMAIN IN-PLACE AFTER BREAKING UP THE SURFACE WITH A BULLDOZER. FROZEN FILL MORE THAN 1/4" THICK SHALL BE REMOVED PRIOR TO PLACING ADDITIONAL FILL. FROZEN FILL LESS THAN 1/4" THICK SHALL BE BROKEN UP WITH A BULLDOZER OR OTHER COMPACTOR WITH A PAD DRUM AND RE-COMPACTED PRIOR TO PLACEMENT OF ADDITIONAL FILL. TEMPORARY FILL MATERIAL MAY REMAIN IN-PLACE AFTER BEING EXPOSED TO OVERNIGHT FREEZING TEMPERATURES. TESTING AGENCY SHALL VERIFY THAT EXPOSED SURFACES MEET THE ABOVE CONDITIONS PRIOR TO ADDITIONAL FILL PLACEMENT.
- SNOW SHALL BE REMOVED FROM EXPOSED SURFACES PRIOR TO PLACING ADDITIONAL PERMANENT FILL MATERIAL. SNOW LESS THAN 1 INCH THICK MAY REMAIN IN FILL AREAS PRIOR TO ADDITIONAL FILL PLACEMENT.
- MEASURES TO REDUCE FROST PENETRATION DURING OVERNIGHT EXPOSURE TO FREEZING TEMPERATURES SHALL INCLUDE COVERING EXPOSED SURFACES WITH DARK COLORED TARPS, CONCRETE BLANKETS, AND THE USE OF SACRIFICIAL MATERIAL. THE CONTRACTOR IS RESPONSIBLE FOR MEANS AND METHODS AND SHALL CONSIDER SCHEDULE, WEATHER, AND EXPERIENCE IN SELECTING FROST PREVENTIVE MEASURE(S).

CIVIL ABBREVIATIONS:

AASHTO AMERICAN ASSOCIATION OF STATE HIGHWAY TRANSPORTATION OFFICIALS AMERICAN SOCIETY FOR TESTING AND MATERIALS BEST MANAGEMENT PRACTICES CATCH BASIN CONCRETE CAST IN PLACE DIAMETER EASTING EXISTING CATCH BASIN **ELEV ELEVATION** EXISTING SEWER MANHOLE EACH WAY **EXIST** EXISTING FINISH FLOOR ELEVATION FEET GALLON GEOGRAPHIC INFORMATION SYSTEM HIGH DENSITY POLYETHYLENE INVERT LBS POUNDS MAX MAXIMUM MINIMUM OR MINUTE NORTHING NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION NOTICE OF INTENT NOTICE OF TERMINATION NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM ON CENTER OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION OUNCES POUNDS PER SQUARE INCH RADIUS REINFORCED CONCRETE PIPE REINFORCED SLOPED GRANITE CURB SQUARE FOOT SIMILAR SEWER MANHOLE SQUARE SQUARE YARDS TEMPORARY BENCH MARK TYP TYPICAL UNIVERSITY OF NEW HAMPSHIRE VERTICAL GRANITE CURB WITH YARDS

PLAN REFERENCES:

NUMBER

- OUTDOOR SWIMMING POOL GENERAL PLAN, BY WESTON & SAMPSON CONSULTING ENGINEERS, JANUARY 11, 1937.
- 2. UNIVERSITY OF NEW HAMPSHIRE SNIVELY POOL GENERAL PLAN, NOVEMBER 28, 1990.
- 3. TOPOGRAPHIC PLAN OF HAMEL RECREATION CENTER AT THE UNIVERSITY OF NEW HAMPSHIRE, BY DOUCET SURVEY, INC., MAY 10, 2013.
- 4. UNIVERSITY OF NEW HAMPSHIRE RECREATIONAL SPORTS CENTER, BY SASAKI ASSOCIATES, INC., SEPTEMBER 2, 1994.
- 5. UNH OUTDOOR POOL ADVANCED SITEWORK, BY OAK POINT ASSOCIATES, NOVEMBER 13, 2014.
- 6. PRELOAD FILL AS-BUILT TOPOGRAPHIC SURVEY BY NORTHEAST EARTH MECHANICS, INC., DECEMBER 18, 2014.

DRAINAGE STRUCTURES

ECB 1	ECB 5	ECB 13
RIM ELEV=62.7'	RIM ELEV=63.3'	RIM ELEV=66.6'
(A) 8" CIP INV=59.2'	(A) 20" RCP INV=56.7'	(A) 12" RCP INV=58.4"
		(B) 18" RCP INV=58.4"
(C) 8" CIP INV=59.2'	(10" ENCLOSED CIP RUNNING	(C) 18" RCP INV=58.3"
• •	THROUGH STRUCTURE, TOP=58.3')	•
ECB 2	•	EDMH 28
RIM ELEV=62.6'	ECB 6	RIM ELEV=66.9'
(A) 8" CIP INV=58.8'		(A) 8" HDPE INV=62.2'
	(A) 20" CIP INV=56.2'	(B) 8" HDPE INV=62.2'
(C) INV=59.0'(RECESSED)	(B) 20" RCP INV=56.3'	
		ECB 29
ECB 3	ECB 11	RIM ELEV=75.3'
RIM ELEV=63.6'	RIM ELEV=66.5'	(NO VISIBLE INVERTS)
SUMP=57.0'	(NO VISIBLE INVERTS)	SUMP=70.7'
FOD 4	SUMP=60.1'	505 70
ECB 4		ECB 30
RIM ELEV=67.6'	ECB 12	RIM ELEV=71.1'
(A) 8" PVC INV=61.3'	RIM ELEV=66.1'	(A) 12" RCP INV=67.0'
		(B) 2" PVC INV=68.3'
	(B) 12" RCP INV=61.7'	(C) 2" PVC INV=68.6'
	(C) 12" RCP INV=61.6'	

SEWER STRUCTURES

ESMH 1	ESMH 6	ESMH 8
RIM ELEV=67.4'	RIM ELEV=75.9'	RIM ELEV=71.3'
(A) 8" PVC INV=62.3'	(A) 8" CIP INV=67.3'	(A) 6" CIP INV=64.2"
(B) 6" PVC INV=62.5'	(B) 8" CIP INV=67.3'	(B) 6" CIP INV=64.1'
(C) 8" PVC INV=62.2'		
(D) 8" PVC INV=62.4'	ESMH 7	EFM 1
	RIM ELEV=75.5'	RIM ELEV=71.3'
ESMH 5	(A) 10" CIP INV=63.3'	SUMP=60.9'
RIM ELEV=75.7'	(B) 8" PVC INV=67.2'	
(A) 8" CIP INV=67.0'	(C) 8" PVC INV=63.1'	
(B) 8" INV=67.0'	(D) 18" INV=63.1'	
(C) 4" PVC INV=72.9'	(=) · · = · · · · · · · · · · · · · · ·	

COMMUNICATIONS STRUCTURES

ETMH 1	ETMH 2	ETMH 3
RIM ELEV=64.8'±	RIM ELEV=67.1'	RIM ELEV=66.8'
SUMP=58.9'	SUMP=58.6'	SUMP=58.0'

I 3

1 4

____EHW____

CIVIL LEGEND:	
DETAIL NUMBER SHEET WHERE DETAIL IS DRAWN SHEETS WHERE DETAIL IS TAKEN	DETAIL LABEL
\triangle	KEYNOTE INDICATOR
2	REMOVALS KEYNOTE INDICATOR
— — — — — — — — — — — — — — — — — — —	EXISTING GRADE CONTOUR LINE
	EXISTING BUILDING LINE
EEOP	EXISTING EDGE OF PAVEMENT
ESGC	EXISTING SLOPED GRANITE CURB
EVGC	EXISTING VERTICAL GRANITE CURB
EDYL	EXISTING DOUBLE YELLOW PAINTED PAVEMENT MARKING
ESWL	EXISTING SINGLE WHITE PAINTED PAVEMENT MARKING
	EXISTING EDGE OF JURISDICTIONAL WETLANDS
<u> 4117</u>	EXISTING WETLAND AREA
ESD(12")	EXISTING STORM DRAIN LINE (PIPE SIZE AS NOTED)
———ESS(ABAN)———	EXISTING ABANDONED SANITARY SEWER LINE
———ESS(12")———	EXISTING SANITARY SEWER LINE (PIPE SIZE AS NOTED)
EFM	EXISTING SANITARY SEWER FORCE MAIN
———EW(6")———	EXISTING WATER LINE (PIPE SIZE AS NOTED)
EG	EXISTING GAS LINE (PIPE SIZE AS NOTED)
EUC	EXISTING UNDERGROUND COMMUNICATION LINE
EUE	EXISTING UNDERGROUND ELECTRIC LINE
EOHW	EXISTING OVERHEAD ELECTRIC/COMMUNICATIONS LINE
ЕОНС	EXISTING OVERHEAD COMMUNICATIONS LINE
EOHE/C	EXISTING OVERHEAD ELECTRIC AND COMMUNICATIONS LIN

EWER LINE (PIPE SIZE AS NOTED) EWER FORCE MAIN (PIPE SIZE AS NOTED) PIPE SIZE AS NOTED) ND COMMUNICATION LINE ND ELECTRIC LINE LECTRIC/COMMUNICATIONS LINE COMMUNICATIONS LINE EXISTING OVERHEAD ELECTRIC AND COMMUNICATIONS LINE EXISTING UNDERGROUND HOT WATER SUPPLY AND RETURN LINES

EXISTING METAL FENCE EXISTING PICKET FENCE ____v ___v ___v ___v ___ EXISTING CHAIN LINK FENCE EXISTING GUARDRAIL EXISTING STONE WALL EXISTING LIGHT POLE \bigcirc EXISTING LIGHT POLE WITH SINGLE FIXTURE EXISTING LIGHT POLE WITH DOUBLE FIXTURES -0

EXISTING TRAFFIC SIGN EXISTING BOLLARD EXISTING UTILITY POLE EXISTING UTILITY POLE AND SUPPORT POLE EXISTING ELECTRIC BOX EXISTING MONITORING WELL

EXISTING COMMUNICATIONS MANHOLE © ETMH EXISTING CATCH BASIN □ ECB EDMH EXISTING DRAINAGE MANHOLE © ESMH EXISTING SANITARY MANHOLE EXISTING GAS VALVE ₩ *****§° EXISTING WATER VALVE EXISTING FIRE HYDRANT EXISTING SURVEY STATION

EXISTING SOIL BORING OR PROBE LOCATION (REFER TO GEOTECHNICAL REPORT FOR ADDITIONAL INFORMATION) EXISTING EXPOSED LEDGE AREA

EXISTING CONCRETE EXISTING RIPRAP **EXISTING CONIFEROUS TREE**

EXISTING DECIDUOUS TREE EXISTING TREE STUMP EXISTING TREE LINE

63.20 FINISH GRADE SPOT ELEVATION SANITARY SEWER FORCE MAIN (PIPE SIZE AS NOTED) -----FM(4")-----SANITARY SEWER LINE (PIPE SIZE AS NOTED) _____SS(8")_____ _____SD(12")_____ STORM DRAIN LINE (PIPE SIZE AS NOTED) WATER LINE (PIPE SIZE AS NOTED)

FINISH GRADE CONTOUR LINE

PERIMETER FOUNDATION DRAIN LINE (PIPE SIZE AS NOTED) UNDERGROUND ELECTRIC LINE (CONDUIT SIZE AS NOTED) UNDERGROUND COMMUNICATIONS DUCTBANK (CONDUIT SIZE AND NUMBER AS NOTED)

FIRE HYDRANT WATER VALVE JOINT RESTRAINT WATER FITTING (REDUCER) CATCH BASIN

-----FD(4")-----

——UE(2*)——

UC(6-4")

2

COMMUNICATIONS MANHOLE SANITARY SEWER MANHOLE ARCHITECTS 22630 DAVIS DRIVE, SUITE 175 STERLING, VIRGINIA 20164 703.437.6600




KEY PLAN WHITTEMORE /XXXXXEV RENOVATION TO THE REPORT OF THE RENOVATION TO THE RENOVATION THE RENOVATION TO THE RENOVATION THE RENOVATION TO THE RENO REVISIONS MARK DATE ISSUE

ISSŲĄNCES DATE | ISSUANCE

> CIVIL LEGEND NOTES, AND **ABBREVIATIONS**

01/16/2015 60% DD Progress

C001







HAMEL RECREATION CENTER RENOVATICAND EXPANSION RECREATION CENTER

SEAL

KEY PLAN

WHITTEMORE RENOVATION RENOVATION

REVISIONS

MARK DATE ISSUE

REVISIONS

MARK DATE ISSUE


DRAINAGE ISSUANCES

DATE ISSUANCE

01/16/2015 60% DD Progress

> GRADING AND DRAINAGE SITE PLAN

CG101





20164 703.437.6600



REZ

KEY PLAN WHITTEMORE RENOVATION RENOVATION **REVISIONS**


MARK DATE ISSUE


ISSŲANCES

DATE ISSUANCE 01/16/2015 60% DD Progress

SITE PLAN

CS101









REZ

KEY PLAN WHITTEMORE RENOVATION REMOV

REVISIONS MARK DATE ISSUE

DATE ISSUANCE 01/16/2015 60% DD Progress

> UTILITY SITE PLAN

CU101

EROSION AND SEDIMENT CONTROL

A. GENERAL NOTES

DURING CONSTRUCTION AND THEREAFTER, PROVIDE EROSION CONTROL MEASURES AS INDICATED AND SPECIFIED. ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE "NEW HAMPSHIRE STORM WATER MANUAL"

PROVIDE EROSION CONTROL MEASURES TO CONTROL EROSION AND SEDIMENTATION FROM THE PROJECT SITE. THE MEASURES INDICATED ON THE DRAWINGS ARE A MINIMUM TO BE PROVIDED. THE CONTRACTOR SHALL PROVIDE ADDITIONAL MEASURES AS NECESSARY AND APPLICABLE TO CONTROL EROSION AND SEDIMENTATION FROM LEAVING THE SITE. TEMPORARY EROSION CONTROL MEASURES SHALL BE PROVIDED AS REQUIRED TO COMPLY WITH NHDES ALTERATION OF TERRAIN GENERAL PERMIT BY RULE REQUIREMENTS AND TO MEET REQUIREMENTS OF THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP).

3. LIMIT AREAS OF EXPOSED SOILS TO THOSE AREAS THAT WILL ACTIVELY BE WORKED. TEMPORARILY STABILIZE AREAS OF DISTURBED SOIL THAT REMAIN UNWORKED FOR MORE THAN 14 DAYS USING TEMPORARY MULCHING (IF THE SOIL WILL BE PERMANENTLY STABILIZED WITHIN 30 DAYS) OR TEMPORARY SEEDING AND MULCHING (IF THE SOIL WILL NOT BE PERMANENTLY STABILIZED WITHIN 30 DAYS). PERMANENTLY STABILIZE ANY AREA OF DISTURBED SOIL BROUGHT TO FINAL GRADE WITHIN 7 DAYS. DISTURBED SOILS DO NOT INCLUDE COMPACTED GRANULAR OR STRUCTURAL FILLS.

4. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS

A MINIMUM OF 6 INCHES OF GRANULAR OR STRUCTURAL FILL HAS BEEN INSTALLED. A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED. A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH STONE OR RIPRAP HAS BEEN INSTALLED.

5. ALL SWALES SHALL BE INSTALLED EARLY IN THE CONSTRUCTION SEQUENCE. SWALES SHALL BE STABILIZED PRIOR TO DIRECTING FLOW TO THEM.

EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

B. INSPECTION AND MAINTENANCE

1. INSPECT DISTURBED AND IMPERVIOUS AREAS, AND EROSION CONTROL MEASURES. AREAS USED FOR STORAGE THAT ARE EXPOSED TO PRECIPITATION. AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE PROJECT AREA AT LEAST ONCE A WEEK AND BEFORE AND AFTER EACH STORM EVENT, GREATER THAN 0.1", PRIOR TO COMPLETION OF PERMANENT STABILIZATION. A PERSON WITH KNOWLEDGE OF EROSION AND STORMWATER CONTROL, INCLUDING THE NPDES STANDARDS MUST CONDUCT THE INSPECTION. THIS PERSON MUST BE IDENTIFIED IN THE INSPECTION LOG. IF BEST MANAGEMENT PRACTICES (BMPs) NEED TO BE MODIFIED OR IF ADDITIONAL BMPs ARE NECESSARY, IMPLEMENTATION MUST BE COMPLETED WITHIN 7 CALENDAR DAYS AND PRIOR TO ANY STORM EVENT (RAINFALL). ALL MEASURES MUST BE MAINTAINED IN EFFECTIVE OPERATING CONDITION UNTIL AREAS ARE PERMANENTLY STABILIZED.

2. KEEP AND MAINTAIN A LOG (REPORT) SUMMARIZING THE SCOPE OF THE INSPECTION, NAME(S) AND QUALIFICATIONS OF THE PERSONNEL MAKING THE INSPECTION. THE DATE(S) OF THE INSPECTION. AND MAJOR OBSERVATIONS RELATING TO OPERATION OF EROSION AND SEDIMENTATION CONTROLS AND POLLUTION PREVENTION MEASURES. MAJOR OBSERVATIONS MUST INCLUDE: BMPs THAT NEED TO BE MAINTAINED; LOCATION(S) OF BMPs THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR LOCATION; AND LOCATION(S) WHERE ADDITIONAL BMPs ARE NEEDED THAT DID NOT EXIST AT THE TIME OF INSPECTION. FOLLOW-UP TO CORRECT DEFICIENCIES OR ENHANCE CONTROLS MUST ALSO BE INDICATED IN THE LOG AND DATED, INCLUDING WHAT ACTION WAS TAKEN AND WHEN.

3. MAINTAIN ALL EROSION CONTROL MEASURES FOR THE LIFE OF THE PROJECT AND UNTIL PERMANENT STABILIZATION OF THE ENTIRE SITE IS ESTABLISHED. PERMANENT STABILIZATION SHALL CONSIST OF AT LEAST 90-PERCENT VEGETATION OR PAVEMENT.

4. PROTECT ALL STABILIZED AREAS FROM EROSION AND IMMEDIATELY REPAIR/REVEGETATE ERODED AREAS.

5. SEDIMENT ACCUMULATIONS SHALL BE REMOVED FROM HAYBALE BARRIERS AND SILT FENCES WHEN THE SEDIMENT DEPTH REACHES 6 INCHES.

6. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES WITHIN 30 DAYS AFTER THE TRIBUTARY AREA HAS BEEN PERMANENTLY STABILIZED. REMOVE ANY ACCUMULATED SEDIMENTS AND STABILIZE.

C. SEQUENCE OF CONSTRUCTION

1. INITIAL OPERATIONS INCLUDE INSTALLATION OF EROSION CONTROL DEVICES.

2. CLEAR TREES, GRUB OUT STUMPS AND STRIP TOPSOIL.

COMMENCE LARGE-SCALE EARTH EXCAVATION MOVING OPERATIONS.

COMPLETE SITE WORK CONSTRUCTION. PROVIDE SEEDING, MULCHING, OR OTHER SURFACE TREATMENTS AS INDICATED IMMEDIATELY UPON ESTABLISHMENT OF FINISH GRADES.

D. SOIL STOCKPILE STABILIZATION

1. SOIL AND FILL STOCKPILES EXPECTED TO REMAIN IN PLACE FOR LESS THAN 30 DAYS SHALL BE COVERED WITH HAY MULCH (90 LBS HAY/1000 SF) OR COVERED WITH AN ANCHORED TARP WITHIN 7 DAYS OR PRIOR TO ANY RAINFALL.

2. SOIL AND FILL STOCKPILES EXPECTED TO REMAIN LONGER THAN 30 DAYS SHALL BE SEEDED WITH A CONSERVATION MIX OF ANNUAL RYE GRASS (0.9 LB/1000 SF) AND HAY MULCHED (90 LBS. HAY/1000 SF) WITHIN 7 DAYS OR PRIOR TO ANY RAINFALL.

3. ALL SOIL AND FILL STOCKPILES SHALL HAVE A SEDIMENT BARRIER (e.g. HAY-BALE BARRIER OR SILT FENCING) INSTALLED AROUND THE DOWNHILL EDGE OF THE STOCKPILE TO TRAP SEDIMENTS.

E. TEMPORARY SEEDING

BEDDING - REMOVE STONES AND TRASH THAT WILL INTERFERE WITH SEEDING THE AREA. WHERE FEASIBLE, TILL THE SOIL TO A DEPTH OF ABOUT 4" TO PREPARE SEED BED AND MIX THE FERTILIZER INTO THE SOIL.

2. FERTILIZER - FERTILIZER SHALL BE UNIFORMLY SPREAD OVER THE AREA PRIOR TO BEING TILLED INTO THE SOIL. A 10-10-10 MIX OF FERTILIZER SHOULD BE APPLIED AT A RATE OF 300 LBS PER ACRE.

3. SEED MIXTURE - USE ANY OF THE FOLLOWING IN UPLAND AREAS:

SEEDING RATES 112 LBS 8/15 - 9/5SPRING - 5/15 1 INCH OATS **ANNUAL** 0.25 INCH RYEGRASS 40 LBS 1.0 LBS WITH MULCH

4. MULCHING FOR TEMPORARY SEEDING - WHERE IT IS IMPRACTICAL TO INCORPORATE FERTILIZER AND SEED INTO MOIST SOIL, THE SEEDED AREA SHALL BE MULCHED TO FACILITATE GERMINATION. MULCH IN THE FORM OF HAY OR STRAW SHALL BE APPLIED AT A RATE OF 70 TO 40 90 LBS PER 1.000 SF.

5. REMOVE TEMPORARY GROWTH FROM TEMPORARY SEEDING PRIOR TO PERMANENT SEEDING.

F. MULCHING

PROVIDE TEMPORARY MULCHING ON SLOPES, CHANNELS, OTHER EROSION PRONE AREAS, AND ALL EXPOSED SOILS THAT CANNOT RECEIVE PERMANENT COVER WITHIN 14 DAYS OF DISTURBANCE. ALSO PROVIDE MULCH FOLLOWING TEMPORARY AND PERMANENT SEEDING AS SPECIFIED. MULCH ANCHORS SHALL BE USED ON SLOPES GREATER THAN 5% IN FALL (PAST OCTOBER 1, AND OVER WINTER TO

MULCH TYPE HAY OR STRAW WOOD CHIPS OR 480 TO 920 LBS. BARK MULCH JUTE AND FIBROUS AS PER MANUFACTURERS' SPECIFICATIONS CRUSHED STONE SPREAD MORE THAN 1/4" TO 1-1/2" 1/2" THICK

G. TEMPORARY EROSION CONTROL MAT SPECIFICATIONS

1. STRAW EROSION CONTROL MAT CONSISTING OF A MACHINE PRODUCED MAT OF 100 PERCENT AGRICULTURAL STRAW FIBER, MINIMUM WEIGHT: 0.5 LBS/SY. NETTINGS SHALL BE LIGHTWEIGHT PHOTODEGRADEABLE WITH PHOTO ACCELERATORS, TOP SIDE ONLY, MINIMUM WEIGHT: 1.5 LB/SF. THE BLANKET SHALL BE SEWN TOGETHER WITH DEGRADABLE THREAD. MINIMUM WIDTH: 48". MINIMUM THICKNESS: 0.39 INCH. THE MINIMUM FUNCTIONAL LONGEVITY OF THE EROSION CONTROL MAT SHALL BE 45 DAYS.

H. EXTENDED USE EROSION CONTROL BLANKET SPECIFICATION

1. STRAW EROSION CONTROL MAT CONSISTING OF A MACHINE PRODUCED MAT OF 100 PERCENT AGRICULTURAL STRAW FIBER, MINIMUM WEIGHT: 0.5 LBS/SY. NETTINGS SHALL BE 100 PERCENT BIODEGRADABLE WOVEN NATURAL ORGANIC FIBER, TOP SIDE ONLY, MINIMUM WEIGHT: 9.3 LB/1000 SF. THE NETTING SHALL CONSIST OF MACHINE DIRECTIONAL STRANDS FORMED FROM TWO INTERTWINED YARNS WITH CROSS DIRECTIONAL STRANDS INTERWOVEN THROUGH THE TWISTED MACHINE STRANDS (LENO WEAVE). THE BLANKET SHALL BE SEWN TOGETHER WITH DEGRADABLE THREAD. MINIMUM WIDTH: 6.7FT, MINIMUM THICKNESS: 0.24 INCH. THE MINIMUM FUNCTIONAL LONGEVITY OF THE EROSION CONTROL MAT SHALL BE 12 MONTHS.

I. WINTER STABILIZATION

THE WINTER CONSTRUCTION PERIOD IS FROM NOVEMBER 30 THROUGH MAY 1. IF THE SITE IS NOT STABILIZED BY NOVEMBER 30 THEN THE SITE SHALL BE PROTECTED WITH OVER-WINTER STABILIZATION.

PROVIDE STABILIZATION AS FOLLOWS WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAN 5 DAYS:

a. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY NOVEMBER 30TH, OR WHICH ARE DISTURBED AFTER NOVEMBER 30TH SHALL BE SEEDED AND COVERED WITH 3 TO 4 TONS OF HAY OR STRAW MULCH PER ACRE SECURED WITH ANCHORED NETTING, OR 2 INCHES OF EROSION CONTROL MIX.

b. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF GREATER THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY NOVEMBER 30TH, OR WHICH ARE DISTURBED AFTER NOVEMBER 30TH, SHOULD BE SEEDED AND COVERED WITH A PROPERLY INSTALLED AND ANCHORED EROSION CONTROL BLANKET OR WITH A MINIMUM OF 4 INCH THICKNESS OF EROSION CONTROL MIX. UNLESS OTHERWISE SPECIFIED BY THE MANUFACTURER. NOTE THAT COMPOST BLANKETS SHOULD NOT EXCEED 2 INCHES IN THICKNESS OR THEY MAY OVERHEAT.

INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MIX SHALL NOT OCCUR OVER ACCUMULATED SNOW OR FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

3. ALL MULCH APPLIED DURING WINTER SHALL BE ANCHORED (e.g, BY NETTING, TRACKING, WOOD CELLULOSE FIBER).

4. STOCKPILES OF SOIL MATERIALS SHALL BE MULCHED FOR OVER WINTER PROTECTION WITH HAY OR STRAW AT TWICE THE NORMAL RATE OR WITH A FOUR-INCH LAYER OF EROSION CONTROL MIX. MULCHING SHALL BE DONE WITHIN 24 HOURS OF STOCKING, AND RE-ESTABLISHED PRIOR TO ANY RAINFALL OR SNOWFALL. NO SOIL STOCKPILE SHALL BE PLACED (EVEN COVERED WITH MULCH) WITHIN 100 FEET FROM ANY WETLAND OR OTHER WATER RESOURCE AREA.

5. NO MORE THAN ONE ACRE OF THE SITE SHALL BE EXPOSED (WITHOUT STABILIZATION) AT ANY ONE TIME. GENERALLY THE EXPOSED AREA SHOULD BE LIMITED TO ONLY THOSE AREAS IN WHICH WORK WILL OCCUR DURING THE FOLLOWING 15 DAYS AND THAT CAN BE MULCHED IN ONE DAY PRIOR TO ANY SNOW OR RAINFALL EVENT.

J. OFF-SITE VEHICLE TRACKING

SWEEP ADJACENT PAVED AREAS AND ROADS AS NECESSARY TO KEEP THEM FREE OF SEDIMENTS RESULTING FROM CONSTRUCTION ACTIVITIES.

PROVIDE A STABILIZED CONSTRUCTION EXIT AT ALL LOCATIONS USED FOR EXITING THE CONSTRUCTION SITE AS DETAILED ON THE DRAWINGS.

K. HOUSEKEEPING

1. WASTE MATERIALS SHALL BE COLLECTED AND STORED IN SECURELY LIDDED RECEPTACLES. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN A DUMPSTER PROVIDED BY THE CONTRACTOR. CONSTRUCTION WASTE MATERIALS SHALL NOT BE BURIED ON SITE.

2. HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATIONS OR BY THE MANUFACTURER.

3. MATERIALS STORED ON SITE SHALL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR PROPER (ORIGINAL IF POSSIBLE) CONTAINER AND IF POSSIBLE UNDER A ROOF OR OTHER ENCLOSURE. STORE ONLY SUFFICIENT AMOUNTS OF MATERIALS TO COMPLETE THE JOB.

4. DISPOSE OF SURPLUS MATERIALS IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS, STATE AND FEDERAL CODES.

5. CONSTRUCTION RELATED EQUIPMENT AND VEHICLES SHALL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTATIVE MAINTENANCE TO REDUCE LEAKAGE.

L. DUST CONTROL


. CONTROL DUST WITH PERIODIC WATERING OF THE EXPOSED SOIL SURFACES WITH ADEQUATE WATER TO CONTROL DUST FROM BECOMING AIRBORNE, REPETITIVE TREATMENTS SHALL BE APPLIED AS NEEDED TO CONTROL DUST THROUGHOUT CONSTRUCTION UNTIL AREAS HAVE BEEN

2. OTHER METHODS TO CONTROL DUST SHALL BE ALLOWED WITH APPROVAL BY THE CONTRACT ADMINISTRATOR.

1 4


1 3


l 2



WHEN JOINTS ARE NECESSARY, FILTER FABRIC SHALL BE SPLICED TOGETHER ONLY AT SUPPORT POST, WITH A MINIMUM 6" OVERLAP, AND SECURELY SEALED.

- 2. SILT FENCES SHALL BE INSPECTED AFTER EACH RAINFALL AND REPAIRS/REPLACEMENT SHALL BE MADE IMMEDIATELY.
- SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT.
- 4. SILT FENCES SHALL BE REMOVED AFTER SATISFACTORY VEGETATIVE COVER IS ESTABLISHED OR DISTURBED AREAS ARE OTHERWISE STABILIZED. PROVIDE PLANTING SOIL, FINISH GRADE, SEED AND MULCH DISTURBED AREAS.





CONSTRUCTION SPECIFICATIONS: 1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 2 TO 3 INCH STONE. RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.

- 2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 50 FEET.
- 3. THE THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6
- 4. THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR EGRESS OCCURS OR 10 FEET, WHICHEVER IS GREATER.

5. GEOTEXTILE SEPARATION FILTER FABRIC SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO


- PLACING THE STONE. 6. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION
- ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE. 7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO ADJACENT PAVED AREAS. THIS MAY REQUIRE PERIODIC TOP
- 8. WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO ADJACENT PAVED AREAS. WHEN WASHING IS REQUIRED, IT SHALL BE PERFORMED ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.

DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT

OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED, OR TRACKED

STABILIZED CONSTRUCTION EXIT

ONTO ADJACENT PAVED AREAS SHALL BE REMOVED IMMEDIATELY.



1. IN-BASIN BAG FILTERS SHALL BE "DANDY SACK" BY TENCATE OR APPROVED EQUAL. INSTALL ACCORDING TO THE MANUFACTURER'S INSTRUCTIONS.

2. REMOVE ACCUMULATED SEDIMENTS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

B2 CATCH BASIN INLET PROTECTION






KEY PLAN WHITTEMORE /HAMEL RENOVATION REVISIONS


MARK DATE ISSUE **ISSUANCES** DATE ISSUANCE

01/16/2015 60% DD Progress

DETAILS

C-501









AND EXPANSION RECREATION CENTER

SEAL

KEY PLAN

WHITTEMORE RENOVATION REMOVATION

TRUE NORTH

REVISIONS


MARK DATE ISSUE

ISSLIANCES

DATE ISSUANCE
01/16/2015 60% DD Progress


LANDSCAPE PLAN

LS101




- 1. EXCAVATE CIRCULAR PLANTING PIT 3X THE DIAMETER OF ROOT BALL WITH SIDES SLOPING INWARD AT 45°ANGLE.
- 2. FILL EXCAVATIONS WITH WATER AND ALLOW TO PERCOLATE. NOTIFY ARCHITECT OF UNEXPECTED WATER SEEPAGE OR RETENTION OF WATER.
- 3. SET TREE WITH ROOT FLARE 2" ABOVE SURROUNDING FINISHED GRADE. DO NOT BREAK ROOT BALL. 4. REMOVE BURLAP, STRAPS, WIRE CAGE AND OTHER MATERIALS FROM TOP 1/4 OF ROOTBALL.
- 5. BACK FILL WITH PLANTING SOIL MIX IN LAYERS. TAMP LIGHTLY TO ELIMINATE VOIDS AND AIR POCKETS. 6. WATER THOROUGHLY WHEN ONE-HALF OF PLANTING PIT IS FILLED.
- 7. PLACE FERTILIZER TABLETS ONE INCH FROM ROOT BALL WHEN ONE-HALF OF PLANTING PIT IS FILLED.
- 8. PLACE REMAINDER OF FILL AND WATER THOROUGHLY. 9. CONSTRUCT TRENCH EDGE AND MULCH AS SPECIFIED. DO NOT PLACE MULCH WITHIN 3 INCHES OF TRUNK. 10. STABILIZE TREE AS SPECIFIED.

TYPICAL TREE ROOT BALL PIT




2. ROTOTILL BED TO 12" DEPTH. SPREAD 3" MIN. LAYER OF PLANTING SOIL MIX OVER BED. ROTOTILL SOIL MIX INTO TOP OF BED. INSTALL PLANTS AND MULCH. WATER THOROUGHLY.


4 GROUNDCOVER PLANTING



2. ON MULTI-STEM TREES, ATTACH GUYS TO THE LARGEST TRUNK. 3. ON EVERGREEN TREES, ATTACH GUYS 1/2 WAY UP HEIGHT OF TREE. 4. REMOVE STAKING AND GUYING AFTER ONE YEAR.

TREE STAKING AND GUYING





2. ROTOTILL BED TO 12" DEPTH. SPREAD 3" MIN. LAYER OF PLANTING SOIL MIX OVER BED. ROTOTILL SOIL MIX INTO TOP OF BED. INSTALL PLANTS AND MULCH. WATER THOROUGHLY.

3 GROUP SHRUB PLANTING



ARCHITECTS

22630 DAVIS DRIVE, SUITE

20164 703.437.6600

JAK

OAK POINT

ASSOCIATES

175 STERLING, VIRGINIA

KEY PLAN WHITTEMORE RENOVATION [**REVISIONS** MARK DATE ISSUE

ISSÚÁNCES

LANDSCAPE

1 4


5 TRENCH EDGE - SECTION

C:\Dfile\21304.03-C-501.dwg 11/10/2014 11:03:32 AM EST

l 3 1 2

DETAILS

DATE ISSUANCE 01/16/2015 60% DD Progress





HAMEL RENOV SEAL

HAMEL HAMEL RENOV. ADDITION WHITTEMORE RENOVATION TRUE NORTH PROJECT NORTH **REVISIONS** MARK DATE ISSUE

INTERIM REVIEW ONLY

KEY PLAN

OVERALL FLOOR PLAN - 1ST FLOOR

ISSUANCES


ISSUANCE



HAMEL RECREATION CENTER RENOVATION AND EXPANSION PROJECT 105 MAIN STREET, DURHAM, NEW HAMPSHIR


INTERIM REVIEW ONLY

THESE DOCUMENTS ARE INCOMPLETE
AND ARE RELEASED FOR INTERIM
REVIEW ONLY AND ARE NOT INTENDED
FOR REGULATORY APPROVAL, PERMIT,
BIDDING OR CONSTRUCTION PURPOSES.



OVERALL FLOOR PLAN - 2ND FLOOR

A-102



HUGHES GROUP

ARCHITECTS

22630 DAVIS DRIVE, SUITE 175
STERLING, VIRGINIA 20164
703.437.6600

HAMEL STUDENT RECREATION CENTER

RENOVATION AND EXPANSION

PROJECT 105 MAIN STREET, DURHAM, NEW HAMPSHIRE 03824

KEY PLAN

WHITTEMORE
RENOVATION
HAMEL
RENOV.
HAMEL
ADDITION

REVISIONS
MARK
DATE ISSUE

REVISIONS


MARK DATE ISSUE

ISSUANCES

DATE ISSUANCE
01/16/15 EARLY RELEASE

OVERALL FLOOR PLAN
- 3RD FLOOR/LOWER
ROOF

A-103






SEAL

WHITTEMORE RENOVATION

MARK DATE ISSUE

ISSUANCES ISSUANCE 01/16/15 EARLY RELEASE

OVERALL FLOOR PLAN - ROOF





HAMEL STUDENT RECREATION CENTER

RENOVATION AND EXPANSION

PROJECT 105 MAIN STREET, DURHAM, NEW HAMPSHIRE 03824

KEY PLAN

WHITTEMORE RENOVATION HAMEL ADDITION

TRUE NORTH

REVISIONS

MARK DATE ISSUE

ISSUANCES ATE ISSUANCE

DATE ISSUANCE

01/16/15 EARLY RELEASE


BUILDING ELEVATION -OVERALL


4-201

ABBREV.	MATERIAL	MANUFACTURER (BOD)	#	COLOR	REMARKS
\S-1	ALUMINUM STOREFRONT	KAWNEER		TBD	
BR-1	BRICK	TBD		TBD	
CD-1	COILING DOOR	TBD		TBD	
CMP-1	COMPOSITE METAL PANEL	TBD	TBD	TBD	
CMP-2	COMPOSITE METAL PANEL	TBD	TBD	TBD	
GLS-1	INSULATED GLAZING	TBD	TBD	TBD	
GR-1	GRANITE SILL	TBD		TBD	
LTR-1	ALUMINUM PIN MOUNTED LETTER	PREFINISHED AL.		TBD	BACKLIT
LVR-1	METAL LOUVER	TBD	TBD	TBD	
LVR-2	METAL LOUVER	TBD	TBD	TBD	
MC-1	METAL COPING	TBD	TBD	TBD	
MP-1	FLAT LOCK METAL PANEL	TBD	TBD	TBD	
MTR-1	MORTAR	TBD	TBD	TBD	

GENERAL NOTES

2








HAMEL STUDENT RECREATION CENTER RENOVATION AND EXPANSION

SEAL

INTERIM REVIEW ONLY


THESE DOCUMENTS ARE INCOMPLETE
AND ARE RELEASED FOR INTERIM
REVIEW ONLY AND ARE NOT INTENDED
FOR REGULATORY APPROVAL, PERMIT,
BIDDING OR CONSTRUCTION PURPOSES.




BUILDING ELEVATIONS
- HAMEL ADDITION

A-204

Copyright 2014 © Hughes Group Architects







HAMEL RENOV SEAL

WHITTEMORE RENOVATION HAMEL RENOV. HAMEL ADDITION PROJECT NORTH TRUE NORTH **REVISIONS** MARK DATE ISSUE

> ISSUANCES ISSUANCE

01/16/15 EARLY RELEASE

BUILDING SECTIONS