Pauly's Pocket Updates

Add 3 brackets on east side (for total of 4)

Add in one more bracket on north side Slide existing bracket down to align with jamb







Add in trim pieces at jambs to conceal brick (typical at locations of existing building facade)

Leave black window casing as is: Painting or removing integral trim will create challenging maintenance item in the future.

Pauly's Pocket Updates

Two possible options that allow for working with the existing lunette. My choice is the original option where the arc points align with the columns below or option 2 here. Have not refined the trim, but wanted to show the massing that we would have to work with.



Existing Condition



#2: Added trim work (crown molding)



#3: Added panel element



Pauly's Pocket

