# OWNER

ALPHA SIGMA HOUSE CORP. OF KAPPA DELTA SORORITY C/O IN DEMAND REALTY PO BOX 9 SOMERSWOTH, NH 03878 S.C.R.D. 1859, PAGE 0532

CIVIL ENGINEER




# SURVEYOR




# ARCHITECT

AG ARCHITECTS 634 CENTRAL AVENUE DOVER, NH 03820 PHONE: 603-743-3700








# TABLE OF CONTENTS


TITLE	SHEET
TOPOGRAPHIC PLAN.	1
PROPOSED SITE PLAN.	. C1
UTILITY & EROSION CONTROL PLAN	. C2
CONSTRUCTION STAGING PLAN	. C3
CONSTRUCTION DETAILS	. D1-D3
LIGHTING PLAN	. L1
LANDSCAPING PLAN	. L2
ARCHITECTURAL PLANS.	A1.1
ARCHITECTURAL PLANS.	A3.1-A3.5
ARCHITECTURAL PLANS.	A4.1-A4.3
ARCHITECTURAL PHASING PLANS.	. A2.1

[				
	3.	LANDSCAPING PLAN ADDED	1/3/19	MCS
	2.	DESIGN REVISIONS UPDATED THRU 12/18/18	12/18/18	MCS
	1.	DESIGN REVISIONS	11/29/18	MCS
	0.	INITIAL SUBMISSION TO DURHAM PLANNING BOARD	11/19/18	EHK
	NO.	REVISIONS	DATE	INT.




		MCS MCS MCS MCS EHK EHK
	MADBURY RD.	1/3/19 12/18/18 12/17/18 11/19/18 DATE
	GARRISON AVE.	
<u>.ul/</u>	GARRISON AVE.	
		COMMISSION VING BOARD
DOR	MILL RD. FOLLAR B	REVISIONS WISION SERVATION COM RHAM PLANNING
	The set of	
		LIGHTING AND BIKE RA( STORMWATER DRAINAGE DESIGN REVISION FOR ( DESIGN REVISION FOR ( DESIGN REVISION TO INITIAL SUBMISSION TO
		LIGHTING AND STORMWATER DESIGN REVISI DESIGN REVISI DESIGN REVISI INITIAL SUBMIS
		4. LIGH 3. STO 2. DES 1. DES 0. INIT
	<u>SITE DATA BLOCK:</u> PLAN INTENT: THE PROPOSAL IS TO CONSTRUCT AN ADDITION TO THE EXISTING BUILDING ON THE SUBJECT PARCEL	
	ZONE: CB (CENTRAL BUSINESS) DIMENSIONAL REQUIREMENTS:	AL NEW HAL
	MIN. LOT AREA 5,000 sq.ft. MIN. FRONTAGE 50 ft. MIN. FRONT/SIDE/REAR SETBACK N/A SETBACK REQUIREMENTS ARE OUTLINED IN THE "DEVELOPMENT STANDARD" SECTION OF THE DURHAM ZONING ORDINANCE.	SEAL SEAL
	THE PROPERTY IS SUBJECT TO ANY AND ALL APPLICABLE ZONING REGULATIONS NOT OUTLINED ABOVE.	/19/18 = 10' S Ng
NOA	THE WCOD APPLIES TO THIS PROPERTY. <u>GENERAL NOTES:</u>	11/ 7: 11/ 3Y: MJS 3Y: MJS
EGA SING	1. <u>OWNER OF RECORD:</u> ALPHA SIGMA HOUSE CORP. OF KAPPA DELTA SORORITY C/O IN DEMAND REALTY PO BOX 9	
RKWAY NORTH IN	SOMERSWOTH, NH 03878 S.C.R.D. 1859, PAGE 0532 2. LOT AREA: 0.63 ACRES (27429± S.F.)	DATE: SCALE: DESIGNE DRAWN DWG FIL 18-06
ΓΥ	<ol> <li>FIELD SURVEY PERFORMED BY G.A.N. &amp; E.J.S. DURING 9/18 USING A TRIMBLE S7 TOTAL STATION WITH A TRIMBLE TSC3 DATA COLLECTOR AND A SOKKIA B21 AUTO</li> </ol>	
	LEVEL. TRAVERSE ADJUSTMENT BASED ON LEAST SQUARE ANALYSIS. 5. IMPERVIOUS SURFACE RATIO: EXISTING = 49.2% (13,501 S.F.) PROPOSED = 57.9% (15,888 S.F.) DISCONNECTED IMPERVIOUS COVER = 0 S.F.	
	EFFECTIVE IMPERVIOUS AREA (EIA) = 15,888 S.F. 6. HORIZONTAL DATUM BASED ON MAGNETIC OBSERVATION.	AN for LTA T 12-2 ROAD MH
	<ol> <li>VERTICAL DATUM IS BASED ON NAVD88 PER DISK UNH3 (ELEVATION=76.72').</li> <li>PROPER FIELD PROCEDURES WERE FOLLOWED IN ORDER TO GENERATE CONTOURS AT 1' INTERVALS. ANY MODIFICATION OF THIS INTERVAL WILL DIMINISH THE INTEGRITY</li> </ol>	PL DE DE M, N
	OF THE DATA, AND DOUCET SURVEY, INC. WILL NOT BE RESPONSIBLE FOR ANY SUCH ALTERATION PERFORMED BY THE USER. 9. UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON OBSERVABLE PHYSICAL	ITE Prepa MAP _ MAD
CE	EVIDENCE AND PAINT MARKS FOUND ON-SITE. 10. THE ACCURACY OF MEASURED UTILITY INVERTS AND PIPE SIZES/TYPES IS SUBJECT TO NUMEROUS FIELD CONDITIONS, INCLUDING; THE ABILITY TO MAKE VISUAL OBSERVATIONS, DIRECT ACCESS TO THE VARIOUS ELEMENTS, MANHOLE	C S 14X K, F S
NE ENCE	CONFIGURATION, ETC. 11. ALL ELECTRIC, GAS, TEL. WATER, SEWER AND DRAIN SERVICES ARE SHOWN IN SCHEMATIC FASHION, THEIR LOCATIONS ARE NOT PRECISE OR NECESSARILY	
)	ACCURATE. NO WORK WHATSOEVER SHALL BE UNDERTAKEN ON THIS SITE USING THIS PLAN TO LOCATE THE ABOVE SERVICES. CONSULT WITH THE PROPER AUTHORITIES CONCERNED WITH THE SUBJECT SERVICE LOCATIONS FOR INFORMATION REGARDING SUCH. CALL DIG-SAFE AT 1-888-DIG-SAFE.	
EDGE OF LOT	12. THIS IS NOT A BOUNDARY SURVEY AND SHALL NOT BE USED AS SUCH. APPROXIMATE PROPERTY LINES SHOWN HEREON ARE BASED ENTIRELY ON THE REFERENCE PLAN.	
	13. THE FEMA FLOOD MAP FOR THIS AREA IS MAP 33017C0318E EFFECTIVE 9/30/2015 AND THIS PARCEL IS NOT WITHIN THE 100 YEAR FLOOD ZONE. REFERENCE PLANS:	
	1. "RE-SUBDIVISION OF LAND IN DURHAM" DATED AUGUST 24, 1980 BY JOHN W. DURGIN ASSOCIATES, INC. S.C.R.D. PLAN 21-86.	ING, P,C, ENVIRONMENTAL 0. B0x 359 1 03857 ax: (603) 659-4627 sineering.com
SW'LY PAD	Ŕ	
		NE NEWARR 0.659-45
	MAGNETIC	ENG CINL • ST 5 R PHONE: (603
	SCALE: 1 INCH = 10 FT.	

JOB: 18-067



\_ EXISTING EDGE OF PARKING LOT



GRADING, DRAINAGE, UTILITY & EROSION CONTROL NOTES ALL EROSION AND SEDIMENTATION CONTROL STRUCTURES SHALL REMAIN IN PLACE AND BE MAINTAINED UNTIL THE VEGETATION IS ESTABLISHED AND THE GROUND SURFACE IS STABILIZED. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE MONITORED BY THE APPLICANT ON A PERIODIC BASIS DURING CONSTRUCTION AND ANY DEFICIENCIES SHALL BE CORRECTED AS SOON AS POSSIBLE. 2. REFER TO CONSTRUCTION AND SEQUENCING AND EROSION CONTROL NOTES ON SHEET

3. ALL DRIVEWAY AND PARKING AREA WORK SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, AS PUBLISHED BY THE STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION. 4. ALL DISTURBED AREAS NOT PAVED OR OTHERWISE TREATED SHALL RECEIVE 4" OF

LOAM. SEED AND MULCH AS SPECIFIED IN THE NOTES ON SHEET D1. 5. <u>COMPACTION REQUIREMENTS:</u>

LOCATION: BELOW PAVED OR CONCRETE AREAS MINIMUM COMPACTION\* TRENCH BEDDING MATERIAL AND SAND BLANKET BACKFILL 95% BELOW LOAM AND SEED AREAS 90% \*ALL PERCENTAGES OF COMPACTION SHALL BE OF THE MAXIMUM PROCTOR DENSITY.

6. ADJUST ALL MANHOLES, CATCH BASINS ETC. WITHIN LIMITS OF WORK TO FINISHED GRADE. 7. EROSION CONTROL DEVICES SHALL BE INSPECTED AFTER EACH RAIN STORM OF 0.25 INCHES OR GREATER. DAMAGED EROSION CONTROL DEVICES SHALL BE


REPAIRED/MODIFIED AS NECESSARY. 8. ALL TEMPORARY LOAM STOCKPILES SHALL RECEIVE TEMPORARY EROSION CONTROL MEASURES.

MAGNETIC SCALE: 1 INCH = 10 FT.

> FINAL APPROVAL BY DURHAM PLANNING BOARD. CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER CERTIFIED

DATE

RE · UJ 10, MJS DV DR  $\bigcirc$  $\nabla$ EU ND PROPOSE AI . G ENGINEERING, CIVIL • STRUCTURAL • ENVIRON JOB: 18-067



		MCS MCS
	MADBEURY RD. SITE	1/3/19 DATE
-	SITE COE DR.	
<u>////</u>	GARRISON AVE.	
	May Si a Moon	
		OARD
 .00R	MUL 80. 72212	ANNING B
	MUL RO. FOLKA BO	DURHAM PLANNING BOARD
		10
		AL SUBMISSION
FENCE		6. INITIAL NO.
		N
		SEAL STATE HALL STATE AND
IN		11/19/18 1" = 10' MJS MJS MJS N.dwg
IN 10A 5'		BY: BY: Civil 7
/EGA JSING ARKWAY NORTH S IN 2		DATE: SCALE: DESIGNED DRAWN BY APPROVED DWG FILE: 18-067
ITY		Z
		PLAN
		SING
		STAC STAC d for DELTA DELTA LOT 12 RY ROAL
		CONSTRUCTION STAGING prepared for KAPPA DELTA TAX MAP 2, LOT 12-2 25 MADBURY ROAD DURHAM, NH
		UCTI KA TAX M
USED ON		ISTR
		CON
		4627
		<b>ERING, P.C.</b> URAL • ENVIRONMENTAL D ST., P.O. BOX 359 RKET, NH 03857 4979, FAX: (603) 659-4627 @MJS-ENGINEERING. COM
N SW'LY C. PAD		THE EEEE CONTRACT OF THE CONTRACT OF THE CONTRACT, NH CON
		ENGINEERING, P.C. CML • STRUCTURAL • ENVIRÔNMENTAL 5 RAILROAD ST., P.O. BOX 359 NEWMARKET, NH 03857 PHONE: (603) 659-4979, FAX: (603) 659-4627 E-MAIL: MJS@MJS-ENGINEERING.COM
		LHONE CONTRACTOR
	- Bacca	
MAGNETIC		
10		JOB: 18-067
	SCALE: 1 INCH = 10 FT.	$\bigcirc$

## CONSTRUCTION SEQUENCING AND EROSION CONTROL NOTES:

AREA OF DISTURBANCE/STABILIZATION A. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION. BUT IN NO CASE SHALL THE AREA OF UNSTABILIZED SOIL EXCEED 5 ACRES AT ANY ONE TIME BEFORE THE AREA IS STABILIZED. B. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: B.1. IN AREAS TO BE PAVED, BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHDOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION, 2006, ITEM NO. 304.1 OR 304.2 HAVE BEEN INSTALLED; IN AREAS NOT TO BE PAVED B.2.1. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; B.2.2. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED; EROSION CONTROL BLANKETS HAVE BEEN INSTALLED IN ACCORDANCE WITH B.2.3. ENV-WQ 1506.03. C. ALL DISTURBED AREAS SHALL BE TEMPORARILY STABILIZED WITHIN 45 DAYS AND PERMANENTLY STABILIZED NO LATER THAN 3 DAYS AFTER FINAL GRADING.

## EROSION CONTROL PRACTICES A. INSTALLATION

- A.1. INSTALL ALL EROSION CONTROLS AS SHOWN ON THE GRADING PLAN, TYPICAL DETAILS, AND IN CONFORMANCE WITH THE EROSION AND SEDIMENT CONTROL NOTES ON THIS PAGE. MANUFACTURER'S SPECIFICATIONS SHALL BE FOLLOWED. B. INSPECTION
- B.1. INSPECT ALL EROSION CONTROLS WEEKLY AND AFTER EVERY RAIN EVENT OF 0.25 INCHES OR GREATER UNLESS OTHERWISE NOTED. TEMPORARY STABILIZATION PRACTICES SHALL BE INSPECTED ONCE PER WEEK B.2.
- DURING CONSTRUCTION UNTIL EXPOSED SURFACES ARE STABILIZED. B.3. ANY SIGNS OF RILL OR GULLY EROSION SHALL BE IMMEDIATELY REPAIRED.
- MAINTENANCE MAINTAIN EROSION CONTROLS PER THE TYPICAL DETAILS AND IN CONFORMANCE C.1. WITH THE EROSION AND SEDIMENT CONTROL NOTES ON THIS PAGE.
- . REMOVAL D.1. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE 85% VEGETATIVE COVER HAS BEEN ESTABLISHED.
- AFTER REMOVAL, ALL DISTURBED AREAS SHALL BE REGRADED, FERTILIZED, AND D.2. RESEEDED. MONITOR TO ENSURE VEGETATIVE GROWTH IS ESTABLISHED AND REPAIR AS NEEDED UNTIL MINIMUM OF 85% VEGETATIVE COVER IS ESTABLISHED.

## COLD WEATHER SITE STABILIZATION SHALL BE UTILIZED BETWEEN NOVEMBER 30TH AND MAY 1ST. THE AREA OF EXPOSED,

- JNSTABILIZED SOIL SHALL BE LIMITED TO 1 ACRE AND SHALL BE PROTECTED AGAINST EROSION BY THE FOLLOWING METHODS PRIOR TO ANY THAW OR SPRING MELT EVENT. B. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY NOVEMBER 30TH, OR WHICH ARE DISTURBED AFTER NOVEMBER 30TH, SHALL BE SEEDED AND COVERED WITH 3-4 TONS OF HAY OR STRAW MULCH PER ACRE SECURED WITH ANCHORED NETTING OR TACKIFIER, OR 2 INCHES OF EROSION CONTROL MIX MEETING THE FOLLOWING CRITERIA;
- B.1. THE MIX SHALL HAVE AN ORGANIC PORTION BETWEEN 25% AND 65%, DRY WEIGHT BASIS, AND BE FIBROUS AND ELONGATED SUCH AS FROM SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR EQUIVALENT MANUFACTURED PRODUCTS;
- B.2. WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS SHALL NOT BE USED AS THE ORGANIC MATERIAL; THE MIX SHALL NOT CONTAIN SILTS, CLAYS, OR FINE SANDS
- B.4. THE MIX SHALL HAVE A PARTICLE SIZE BY WEIGHT OF 100% PASSING A 3-INCH SCREEN, 90% TO 100% PASSING A 1-INCH SCREEN, 70% TO 100% PASSING A 0.75-INCH SCREEN, AND 30% TO 75% PASSING A 0.25 INCH SCREEN; B.5. THE MIX pH SHALL BE BETWEEN 5.0 AND 8.0;
- C. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE GREATER THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY NOVEMBER 30TH, OR WHICH ARE DISTURBED AFTER NOVEMBER 30TH, SHALL BE SEEDED AND COVERED WITH A PROPERLY INSTALLED AND ANCHORED EROSION CONTROL BLANKET OR WITH A MINIMUM 4 INCH THICK NESS OF EROSION CONTROL MIX MEETING THE CRITERIA
- SPECIFIED ABOVE IN (B)(1-5);D. INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MIX, MEETING THE CRITERIA SPECIFIED IN (B)(1-5) SHALL NOT OCCUR OVER SNOW OF GREATER THAN 1-INCH IN DEPTH.
- INSTALLATION OF EROSION CONTROL BLANKETS SHALL NOT OCCUR OVER SNOW OF GREATER THAN 1 INCH IN DEPTH OR ON FROZEN GROUND. F. ALL PROPOSED STABILIZATION IN ACCORDANCE WITH (A) OR (B) SHALL BE COMPLETED
- WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAN 5 DAYS. G. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY NOVEMBER 30TH, OR WHICH ARE DISTURBED AFTER NOVEMBER 30TH,
- SHALL BE STABILIZED WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS. H. AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES WHERE ACTIVE CONSTRUCTION OF THE ROAD OR PARKING AREA HAS STOPPED FOR THE WINTER SEASON SHALL BE PROTECTED WITH A MINIMUM 3-INCH LAYER OF BASE COURSE

GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHDOT STANDARD SPECIFICATION

## TEMPORARY VEGETATION

INSTALL EROSION AND SEDIMENT CONTROL MEASURES AS SPECIFIED ABOVE. A.1. ENSURE RUNOFF IS DIVERTED FROM SEEDED AREA.

FOR ROAD AND BRIDGE CONSTRUCTION, 2006, ITEM NO. 304.1 OR 304.2.

- A.2. A.3. ON SLOPES OF 4:1 OR STEEPER, CREATE HORIZONTAL GROOVES PERPENDICULAR O THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE RUNOFF. B SEED BED PREPARATION
- REMOVE STONES AND TRASH FROM AREA TO BE SEEDED. B.2. COMPACTED SOIL SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE
- APPLYING FERTILIZER, LIME, AND SEED. B.3. LOW PHOSPHATE, SLOW RELEASE NITROGEN OR LIMESTONE SHALL BE USED. APPLY 10-0-10 LOW PHOSPHATE FERTILIZER AT A RATE OF 600 LBS PER ACRE. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE.

## SEEDING C.1. SEED PER THE FOLLOWING RECOMMENDATIONS

SEASON	APPLICATION DATE	MIXTURE TYPE	QUANTITY (Ib./Ac.)
EARLY SPRING	NO LATER THAN 5/15	OATS	80
LATE SPRING/ FALL	4/1 TO 6/1 & 8/15 TO 9/15	PERENNIAL RYE	30
EARLY SPRING/ FALL	4/1 TO 5/15 & 8/15 TO 9/15	ANNUAL RYE	40
FALL	8/15 TO 9/15	WINTER RYE	112

- C.2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING.
- TEMPORARY SEEDING SHOULD TYPICALLY OCCUR PRIOR TO SEPTEMBER 15TH. C.4. AREAS SEEDED BETWEEN MAY 15TH AND AUGUST 15TH SHOULD BE COVERED WITH HAY OR STRAW MULCH. VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA SHOULD BE ACHIEVED PRIOR TO OCTOBER 15TH. IF THIS CONDITION IS NOT ACHIEVED, IMPLEMENT OTHER TEMPORARY STABILIZATION
- MEASURES FOR OVERWINTER PROTECTION. MAINTENANCE D.1. TEMPORARY SEEDING SHOULD BE INSPECTED WEEKLY AND AFTER ANY RAINFALL EXCEEDING 1/2 INCH IN 24 HOURS ON ACTIVE CONSTRUCTION SITES. TEMPORARY SEEDING SHOULD ALSO BE INSPECTED JUST PRIOR TO SEPTEMBER 15, TO ASCERTAIN WHETHER ADDITIONAL SEEDING IS REQUIRED TO PROVIDE STABILIZATION OVER THE WINTER PERIOD.
- D.2. BASED ON INSPECTION, AREAS SHOULD BE RESEEDED TO ACHIEVE FULL STABILIZATION OF EXPOSED SOILS. IF IT IS TOO LATE IN THE PLANTING SEASON TO APPLY ADDITIONAL SEED, THEN OTHER TEMPORARY STABILIZATION MEASURES SHOULD BE IMPLEMENTED.
- AT A MINIMUM, 85% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION. D.3 D.4. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHOULD BE MADE AND AREAS SHOULD BE RESEEDED, WITH OTHER TEMPORARY MEASURES (E.G., MULCH) USED TO PROVIDE EROSION PROTECTION DURING THE PERIOD OF VEGETATION ESTABLISHMENT.

## SOIL STOCKPILES GENERAL

- A.1. PLACE IN THE LOCATIONS SHOWN ON THE PLAN. ADDITIONAL STOCKPILES MUST BE LOCATED 50 FEET FROM DITCHES AND CULVERT INLETS. B. PROTECTION OF STOCKPILES
- B.1. PROTECT SOIL AND AGGREGATE STOCKPILES WITH TEMPORARY PERIMETER SEDIMENT BARRIER SUCH AS SILT FENCE OR SILT SOCK. COVER ACTIVE STOCKPILES WITH ANCHORED PROTECTIVE COVERING PRIOR TO B.2.
- EXPECTED STORM EVENTS. B.3. INACTIVE STOCKPILES SHALL BE COVERED WITH ANCHORED TARPS OR TEMPORARILY SEEDED AND MULCHED PER THE TEMPORARY VEGETATION AND MULCHING NOTES ON THIS PAGE

# B.4. STOCKPILES THAT ARE A SOURCE OF DUST SHALL BE COVERED.

- DUST CONTROL A. DUST SHALL BE CONTROLLED ON SITE DURING CONSTRUCTION BY IMPLEMENTING THE FOLLOWING DUST CONTROL MEASURES A.1. MULCHING AND VEGETATIVE COVER TO REDUCE DUST.
- A.2. MECHANICAL SWEEPERS AND FINE WATER SPRAYS.
- A.3. COVER SURFACES WITH CRUSHED STONE OR COARSE GRAVEL.

	OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW
	EQUIPMENT. THE FINAL HARROWING OPERATION SHOUL
	CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY U PREPARED. ALL BUT CLAY OR SILTY SOILS AND COAR
	ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE.
B.2.	REMOVE FROM THE SURFACE ALL STONES 2 INCHES
	DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WI CONCRETE, CLODS, LUMPS, TRASH OR OTHER UNSUIT
В.З.	INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC
	COMPACTED; THE AREA MUST BE TILLED AND FIRMED
B.4.	WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRU- SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING F
B.5.	LOW PHOSPHATE, SLOW RELEASE NITROGEN OR LIMES
D.0.	10-0-10 LOW PHOSPHATE FERTILIZER AT A RATE OF
	LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PL
	AT A RATE OF 3 TONS PER ACRE.
C. SEI C.3.	UNLESS OTHERWISE NOTED, GRASS SEED MIXTURE 'C
0.0.	THE SPECIFIED RATE AS NOTED IN THE 'SEED MIXTURE
	VEGETATION' TABLE.
C.4.	APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER,
	SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED
	NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HY MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING OF
	THE CONTOUR.
C.5.	WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPAC
	HYDROSEEDER IS USED, THE SEEDBED SHOULD BE F OPERATIONS WITH A ROLLER, OR LIGHT DRAG.
C.6.	WHEN HYDROSEEDING (HYDRAULIC APPLICATION), PREI
0.0.	SPECIFIED ABOVE OR BY HAND RAKING TO LOOSEN A
	TO REMOVE SURFACE STONES LARGER THAN 2 INCHE
C.7.	SLOPES MUST BE NO STEEPER THAN 2 TO 1.
C.8.	LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUS OF FIBER MULCH ON CRITICAL AREAS IS NOT RECOM
	TO HOLD STRAW OR HAY). BETTER PROTECTION IS GA
	AND HOLDING IT WITH ADHESIVE MATERIALS OR 500
0.0	FIBER MULCH.
C.9.	SEEDING RATES MUST BE INCREASED 10% WHEN HYD
D. MAI	INTENANCE
D.1.	PERMANENTLY SEEDED AREAS SHOULD BE INSPECTED
D.2. D.3.	MOW SEEDED AREAS AS NECESSARY. BASED ON INSPECTION, AREAS SHOULD BE REPAIRED
D.J.	ENSURE 85% OF THE SOIL SURFACE IS COVERED BY
MULCH	ING & EROSION CONTROL MATTING
A GEI	NFRAL
A.1.	APPLY PRIOR TO A STORM EVENT. CLOSELY MONITO ADEQUATE WARNING OF SIGNIFICANT STORMS.
A.2.	MULCHING WITHIN A SPECIFIED TIME PERIOD FROM OF
A.2.	1. WITHIN 100 FEET OF WETLANDS THE TIME PERIOD
A O (	THAN 7 DAYS. 2. IN OTHER AREAS IT SHALL BE NO GREATER THAN
A.2.2 B. TEN	Z. IN OTHER AREAS IT SHALL BE NO GREATER THAN MPORARY MULCHING
B.1.	HAY OR STRAW MULCHES
B.1.1	
R 1 '	UNDESIRABLE SEEDS AND COARSE MATERIALS. 2. APPLICATION RATE SHALL BE 2 BALES/1,000 SF
D.1.4	TONS/ACRE TO COVER 75–90% OF THE GROUND
	3. ANCHÓRING
B.1	.3.1. NETTING: NETTING SHALL BE JUTE, WOOD FIBE
	PLASTIC NETTING INSTALLED PER MANUFACTUR

PERMANENT VEGETATION

SITE PREPARATIO


B. SEED BED PREPARATION

	PLASTIC NETTING INSTALLED PER MANUF
B.1.3.2.	TACKIFIER: APPLY POLYMER OR ORGANI
	STRAW MULCH. APPLY PER MANUFACT
	APPLICATION RATES ARE 40-60 LBS/A
R 1 4	80-120 LBS/ACRE FOR ORGANIC LIQUI WINTER APPLICATION: APPLY TO A DEPTH C
D.1.4.	ABOVE LISTED APPLICATION RATE. NOTE TH
	MULCH WILL NEED TO BE REMOVED AND TH
	THE SPRING.
D 1 5	MAINTENANCE
B.1.5.1.	
	DISPLACEMENT OF MULCH. REPAIR AS N
	UNTIL 85% VEGETATIVE COVER IS ESTAE
3.2. ERU	SION CONTROL BLANKET OR MATTING
B.2.1.	REFER TO PLANS FOR TYPICAL EROSION CO
	PER MANUFACTURERS SPECIFICATIONS.
	APPLICATION AND TIMING
B.2.2.1.	DURING THE GROWING SEASON (APRIL
	BASE OF GRASSED WATERWAYS, STEEP
	DISTURBED SOIL WITHIN 100 FEET OF L
B.2.2.2.	DURING THE LATE FALL AND WINTER (S
	ADDITION TO THOSE LISTED ABOVE USE
	WATERWAYS AND MODERATE SLOPES (G
B 2 3	MAINTENANCE
	INSPECT PERIODICALLY AND BEFORE AN
0.2.0.1.	CONTACT WITH THE SOIL UNTIL 85% VE
	REPAIR AND RESTAPLE AS NECESSARY.
PERMAN	IENT MULCHING
	DD CHIPS OR GROUND BARK
	APPLY TO A THICKNESS OF 2 TO 6 INCHES
0.1.1.	
	10-20 TONS/ACRE OR 460-920 POUNDS/
040	PLAN.
C.1.2.	MAINTENANCE:
C.1.2.1.	INSPECT ANNUALLY AND AFTER RAIN EV
	A 24 HOUR PERIOD. REPAIR/REPLACE
C.2. ERO	SION CONTROL MIX
~ ~ 4	COMPOSITION OF THE MIN CHARLE DE 10 EC

	A 24 HOUR PERIOD. REPAIR/REPLACI
C.2. ERO	SION CONTROL MIX
C.2.1.	COMPOSITION OF THE MIX SHALL BE AS F
C.2.1.1.	ORGANIC MATTER CONTENT SHALL BE
C.2.1.2.	PARTICLE SIZE BY WEIGHT SHOULD BE
	90-100% PASSING THE 1" SCREEN, 7
	SCREEN, AND 30-75% PASSING THE
C.2.1.3.	THE ORGANIC PORTION SHALL BE ELOI
	NOT CONTAIN WOOD AND BARK CHIPS,
	REPROCESSED WOOD PRODUCTS.
C.2.1.4.	THE MIX SHALL NOT CONTAIN SILTS, C
C.2.1.5.	SOLUBLE SALTS CONTENT SHALL BE <
	5.0-8.0,
C.2.2.	PLACEMENT OF BERM

C.2.2.1. PLACE BERM ALONG A LEVEL CONTOUR. BERM MUST BE A MINIMUM OF 12" HIGH ON THE UPHILL SIDE AND 2 FEET WIDE.

C.2.3. MAINTENANCE C.2.3.1. INSPECT PERIODICALLY AND AUGMENT AS NEEDED TO MAINTAIN INITIAL THICKNESS. REPLACE IF NO LONGER FUNCTIONING AS INTENDED.



3.

## A.1. REFER TO SITE PREPARATION FOR TEMPORARY SEEDING.

B.1. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH HARROW OR OTHER SUITABLE IN SHOULD BE ON THE GENERAL NABLY UNIFORM, FINE SEEDBED IS ND COARSE SANDS SHOULD BE

> INCHES OR LARGER IN ANY CH AS WIRE, CABLE, TREE ROOTS, UNSUITABLE MATERIAL. TRAFFIC HAS LEFT THE SOIL FIRMED AS ABOVE CONSTRUCTION OPERATIONS, LOOSEN YING FERTILIZER, LIME AND SEED.

OR LIMESTONE SHALL BE USED. APPLY RATE OF 600 LBS PER ACRE. APPLY LCIUM PLUS MAGNESIUM OXIDE)

TURE 'C' SHALL BE APPLIED AT MIXTURES FOR PERMANENT

SEEDER, DRILL, CULTIPACKER TYPE NG SEED AND FERTILIZER). INCH. HYDROSEEDING THAT INCLUDES DING OPERATIONS SHOULD BE ON

ULTIPACKER TYPE SEEDER OR LD BE FIRMED FOLLOWING SEEDING

N), PREPARE THE SEEDBED AS DOSEN AND SMOOTH THE SOIL AND 2 INCHES IN DIAMETER.

TANEOUSLY WITH THE SEED. THE USE RECOMMENDED (UNLESS IT IS USED ON IS GAINED BY USING STRAW MULCH OR 500 POUNDS PER ACRE OF WOOD HEN HYDROSEEDING.

SPECTED MONTHLY.

EPAIRED AND/OR RESEEDED TO RED BY VEGETATION.

MONITOR THE WEATHER TO HAVE FROM ORIGINAL SOIL EXPOSURE PERIOD SHOULD BE NO GREATER

ER THAN 14 DAYS.

STRAW SHALL BE AIR-DRIED, FREE OF IAI S ,000 SF (70-90 POUNDS) OR 1.5-2.0 GROUND.

OOD FIBER, OR BIODEGRADABLE JFACTURER'S SPECIFICATIONS. IC TACKIFIER TO ANCHOR HAY OR TURER'S SPECIFICATIONS. TYPICAL ACRE FOR POLYMER MATERIAL AND

OF 4 INCHES OR DOUBLE THE THAT IF SEEDING IS NECESSARY THE AREA SEEDED AND MULCHED IN

N STORMS FOR RILLS OR NECESSARY. CONTINUE INSPECTIONS BLISHED.

CONTROL MATTING DETAIL. INSTALL

15 – SEPTEMBER 15) USE ON THE SLOPES (15% OR GREATER), ANY LAKES, STREAMS, AND WETLANDS. SEPTEMBER 15 – APRIL 15) IN E ON SIDE SLOPES OF GRÁSSED GREATER THAN 8%).

ND AFTER STORM EVENTS TO ENSURE EGETATIVE COVER IS ESTABLISHED.

ES. TYPICAL APPLICATION RATES ARE 1,000 SF. REFER TO LANDSCAPE

VENTS OF 2.5 INCHES OR MORE IN AS NECESSARY. FOLLOWS:

BETWEEN 25-65% DRY WEIGHT BASIS. 100% PASSING THE 3" SCREEN, 70-100% PASSING THE 0.75 INCH 0.25 INCH SCREEN.


NGATED AND FIBROUS. IT SHALL GROUND CONSTRUCTION DEBRIS, OR

CLAYS, OR FINE SANDS. < 4.0MMHOS/CM AND A pH OF

USE SEEDING DROUGHTY WELL	MODERATELY WELL DRAINED
MIXTURE DROUGHTY DRAINED	
STEEP CUTS AND FILLS, BORROW ANDAFAIRGOODDISPOSAL AREASBPOORGOODDFAIREXCELLENT	GOOD FAIR EXCELLENT EXCELLENT
WATERWAYS, EMERGENCY SPILLWAYS, AND OTHER CHANNELS WITH FLOWING WATER.AGOODGOODCGOODEXCELLENT	GOOD EXCELLENT
LIGHTLY USED PARKING LOTS, ODD AREAS, UNUSED LANDS, AND LOW INTENSITY USEAGOODGOODRECREATION SITES.CGOODEXCELLENT	GOOD FAIR EXCELLENT
PLAY AREAS AND ATHLETIC FIELDS. (TOPSOIL E FAIR EXCELLENT IS ESSENTIAL FOR GOOD TURF.)	EXCELLENT EXCELLENT

NOTE: POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREAS AND ATHLETIC FIELDS.

	SEED MIXTURES FOR PERMANE	NT VEGETATION	
MIXTURE	SPECIES	POUNDS PER ACRE	POUNDS PER 1,000 SF
A	TALL FESCUE	20	0.45
	CREEPING RED FESCUE	20	0.45
	<u>REDTOP</u>	<u>2</u>	<u>0.05</u>
	TOTAL	42	0.95
В	TALL FESCUE	15	0.35
	CREEPING RED FESCUE	10	0.25
	CROWN VETCH	15	0.35
	OR	-	-
	<u>FLATPEA</u>	<u>30</u>	0.75
	TOTAL	40 OR 55	0.95 OR 1.35
С	TALL FESCUE	20	0.45
	CREEPING RED FESCUE	20	0.45
	<u>BIRDSFOOT_TREFOIL</u>	<u>8</u>	<u>0.20</u>
	TOTAL	48	1.10
D	TALL FESCUE	20	0.45
	<u>FLATPEA</u>	<u>30</u>	<u>0.75</u>
	TOTAL	50	1.20
E	CREPPING RED FESCUE	50	1.15
	<u>KENTUCKY BLUEGRASS</u>	<u>50</u>	<u>1.15</u>
	TOTAL	100	2.30
F	TALL FESCUE	150	3.60



## CONSTRUCTION SEQUENCING:


7.

THE ESTIMATED START OF PHASE 1 CONSTRUCTION IS MARCH 1, 2019 AND THE ESTIMATED END OF CONSTRUCTION IS SEPTEMBER 31, 2020. PHASE 2 SCHEDULE IS PENDING. THE FOLLOWING CONSTRUCTION SEQUENCING SHALL BE FOLLOWED;


- COMPLETE A PRE-CONSTRUCTION MEETING WITH ALL PARTIES AS REQUIRED BY CONDITIONS OF APPROVAL. CONTACT DIG-SAFE, INDIVIDUAL UTILITIES, AND TOWN DEPARTMENTS TO GET ALL UTILITIES DISCONNECTED PRIOR TO START OF CONSTRUCTION. PROPERLY DISCONTINUE SERVICES OR TEMPORARILY CAP SERVICES IN ACCORDANCE WITH TOWN REQUIREMENTS. CONTACT BUILDING DEMOLITION CONTRACTOR AND HAVE BUILDING CERTIFIED FROM ENVIRONMENTAL CONCERNS PRIOR TO DEMOLITION.
- SEDIMENT AND EROSION CONTROLS SHALL BE INSTALLED PRIOR TO EARTH MOVING OPERATIONS. INSTALL TEMPORARY CONSTRUCTION SAFETY FENCE IN ACCORDANCE WITH PLANS, AND ABUTTERS.
- INSTALL TEMPORARY CONSTRUCTION ENTRANCE OR USE TRACKOUT MAT OR PLATES AS REQUIRED DURING ALL EXCAVATION ACTIVITY ON THE SITE COMPLETE DEMOLITION OF BUILDING AS REQUIRED AND DISPOSE OF ALL DEMOLITION MATERIAL AT OFFSITE APPROVED DEMOLITION
- FACILITY. ALL DEMOLITION SHALL BE IN ACCORDANCE WITH THE BUILDING DEMOLITION PLAN. 8. CONSTRUCT AND STABILIZE ALL TEMPORARY EROSION CONTROLS INCLUDING CONSTRUCTION ENTRANCES, SWALES AND SEDIMENTATION BASINS IF REQUIRED. A TEMPORARY SEDIMENT BASIN MAY BE REQUIRED FOR CONSTRUCTION OF THE ADDITION PRIOR TO
- COMPLETING CONSTRUCTION OF THE UNDERGROUND TREATMENT SYSTEM. GRADE ONLY WITHIN THE LIMITS AS SHOWN ON THE PLANS. TOTAL SITE DISTURBANCE DEPICTED ON THESE PLANS IS 5,300 SQUARE FEET. 10. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION. ALL DISTURBED AREAS SHALL BE TEMPORARILY
- STABILIZED WITHIN 45 DAYS AND PERMANENTLY STABILIZED NO LATER THAN 3 DAYS AFTER FINAL GRADING. REFER TO SECTION 4.13 FOR STABILIZATION REQUIREMENTS. 11. STRIP TOP SOIL AND STOCKPILE FOR REUSE. STABILIZE IN ACCORDANCE WITH SECTION 4.3.
- PFRFORM CUTS AND FILLS AS NECESSARY 13. EXCAVATE FOR FOUNDATIONS AND UTILITIES AND CONSTRUCT IN ACCORDANCE WITH SITE PLANS AND STRUCTURAL PLANS COMPLETE ALL INSPECTIONS AND TESTING AS REQUIRED PRIOR TO BACKFILLING.
- 14. INSTALL DRAINAGE AND UTILITY STRUCTURES AND STABILIZE PRIOR TO RECEIVING RUNOFF. THIS WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE DETAILED CONSTRUCTION PLANS. THIS WORK SHALL OCCUR IN CONJUNCTION WITH FOUNDATION ADDITION, AND SIDEWALK CONSTRUCTION. 15. CONSTRUCT STORMTECH UNDERGROUND DRAINAGE SYSTEM IN ACCORDANCE WITH THE PLANS, SPECIFICATIONS AND MANUFACTURERS
- RECOMMENDATIONS. GRADES AND FILL MATERIAL IS SHOWN ON THE PLANS AND DETAILS. 16. COMPLETE GRADING AND INSTALL PERMANENT SEEDING AND PLANTINGS
- INSTALL REMAINING DRAINAGE AND UTILITY STRUCTURES AND STABILIZE PRIOR TO RECEIVING RUNOFF. INSPECT, MAINTAIN, AND IF NECESSARY, REPAIR ALL EROSION AND SEDIMENT CONTROL MEASURES.
- 19. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AFTER SITE IS STABILIZED AND RESEED ANY AREAS DISTURBED BY REMOVAL. THE APPROXIMATE DATE FOR REMOVAL OF EROSION CONTROLS IS SEPTEMBER 1, 2020.

ADDITIONAL NOTES: NO FUEL SHALL BE STORED ON SITE DURING CONSTRUCTION.

- DURING CONSTRUCTION DUST SHALL BE PREVENTED FROM BECOMING A SAFETY OR HEALTH HAZARD BY THE IMPLEMENTATION OF ACCEPTED CONTROL METHODS SUCH AS WATERING.
- ALL CONSTRUCTION MATERIALS THAT ARE SPILLED OR DEPOSITED ON THE PUBLIC ROADWAYS SHALL BE REMOVED BY THE CONTRACTOR
- 4. DO NOT BEGIN CONSTRUCTION UNTIL ALL LOCAL, STATE, AND FEDERAL PERMITS HAVE BEEN APPLIED FOR AND RECEIVED ALL INSPECTIONS/OBSERVATION SERVICES FOR THE INSTALLATION OF WATER. WASTEWATER, STORMWATER MANAGEMENT, 5. POROUS PAVEMENT, AND OTHER INFRASTRUCTURE SHALL BE PERFORMED BY AUTHORIZED REPRESENTATIVES OF THE TOWN OF DURHAM AS STIPULATED BY THE DURHAM DEPARTMENT OF PUBLIC WORKS. THE DEVELOPER SHALL REIMBURSE THE TOWN FOR ALL ASSOCIATED INSPECTION/OBSERVATION COSTS.



- 1. CARE SHALL BE TAKEN TO INSURE THAT THE BRICK INVERT IS A SMOOTH CONTINUATION OF THE SEWER INVERT. INVERT BRICKS SHALL BE LAID ON EDGE.
- INVERT AND SHELF TO BE PLACED AFTER LEAKAGE TEST. ALTERNATE INVERT DETAILS: REPLACE BRICK INVERT W/ CAST-IN-PLACE CONCRETE.
- BRICK MASONRY OR 2,000 PSI CONCRETE UNDER BRICK SHELF



## <u>SECTION VIEW</u>

# **INSIDE DROP MANHOLE DETAIL**

N. T. S.

- 1. 4" SERVICES REQUIRE A 6" DIAMETER DROP, OTHERWISE, DROP DIAMETER
- SHALL MATCH INLET DIAMETER. 2. A MINIMUM OF TWO ANCHOR STRAPS SHALL BE USED. ANCHOR STRAPS
- AND BOLTS TO BE STAINLESS STEEL AND NOT MORE THAN 3' ON CENTER
- STRAPS SHALL BE 1" WIDE AND BOLTS 3/8" x 2-1/2" LONG. 3. THERE SHALL BE NO STEPS INSTALLED WITHIN THE MANHOLES.

# SEWER NOTES:

PER THE REQUIREMENTS OF "STANDARDS OF DESIGN AND CONSTRUCTION FOR SEWERAGE AND WASTEWATER TREATMENT FACILITIES."

- GRAVITY SEWER CONSTRUCTION MATERIALS (Env-Wg 704.05) (A) PLASTIC GRAVITY SEWER PIPE AND FITTINGS SHALL BE 8 INCH PVC SDR 35 SEWER PIPE (EXCEPT SEWER SERVICE SHALL BE 6" SDR 35 PVC WHERE NOTED)
- AND SHALL COMPLY WITH ASTM D3034-04a. (B) PLASTIC SEWER PIPE SHALL HAVE A PIPE STIFFNESS RATING OF AT LEAST 46 PSI AT 5 PERCENT PIPE DIAMETER DEFLECTION, AS MEASURED IN ACCORDANCE WITH ASTM D2412-02 DURING MANUFACTURE.
- (C) JOINT SEALS FOR PVC PIPE SHALL BE OIL RESISTANT COMPRESSION RINGS OF ELASTOMERIC MATERIAL CONFORMING TO ASTM D3212-96(a)(2003)e1 AND SHALL BE PUSH-ON, BELL AND SPIGOT TYPE.

## **GRAVITY SEWER PIPE TESTING REQUIREMENTS** <u>(Env-Wq 704.07)</u>

- (A) ALL NEW SEWERS SHALL BE TESTED FOR WATER TIGHTNESS BY THE USE OF LOW-PRESSURE AIR TESTS. (B) LOW-PRESSURE AIR TESTING SHALL BE IN CONFORMANCE WITH:
- (1) ASTM F1417-92(2005) "STANDARD TEST METHOD FOR INSTALLATION ACCEPTANCE OF PLASTIC GRAVITY SEWER LINES USING LOW-PRESSURE AIR";
- (2) UNI-BELL PVC PIPE ASSOCIATION UNI-B-6, "LOW-PRESSURE AIR TESTING OF INSTALLED SEWER PIPE" (1998). (C) ALL NEW GRAVITY SEWERS SHALL BE CLEANED AND VISUALLY INSPECTED AND
- SHALL BE TRUE TO LINE AND GRADE FOLLOWING INSTALLATION AND PRIOR TO USF (D) ALL PLASTIC SEWER PIPE SHALL BE DEFLECTION TESTED NOT LESS THAN 30
- DAYS FOLLOWING INSTALLATION. (E) THE MAXIMUM ALLOWABLE DEFLECTION OF FLEXIBLE SEWER PIPE SHALL BE  $7\frac{1}{2}$


PERCENT OF AVERAGE INSIDE DIAMETER.

## PROTECTION OF WATER SUPPLIES (Env-Wg 704.12) (A) SEWERS SHALL BE LOCATED AT LEAST 10 FEET HORIZONTALLY FROM ANY

- EXISTING OR PROPOSED WATER MAIN. (B) A DEVIATION FROM THE SEPARATION REQUIREMENTS OF (A) ABOVE SHALL BE ALLOWED WHERE NECESSARY TO AVOID CONFLICT WITH SUBSURFACE STRUCTURES, UTILITY CHAMBERS, AND BUILDING FOUNDATIONS, PROVIDED THAT THE SEWER IS CONSTRUCTED IN ACCORDANCE WITH THE FORCE MAIN
- CONSTRUCTION REQUIREMENTS SPECIFIED IN Env-Wg 704.06. (C) WHENEVER SEWERS MUST CROSS WATER MAINS, THE SEWER SHALL BE CONSTRUCTED AS FOLLOWS: (1) VERTICAL SEPARATION OF THE SEWER AND WATER MAIN SHALL BE NOT LESS THAN 18 INCHES, WITH WATER ABOVE SEWER; AND


(2) SEWER PIPE JOINTS SHALL BE LOCATED AT LEAST 6 FEET


HORIZONTALLY FROM THE WATER MAIN.





٩L	ΒY	THE	DURHAM	PLANNING	BOARD.

N. T. S









1

C

W3


NOTES:
1) EXACT MOUNTING DETAILS TO BE DETERMINED AT JOBSITE BY OTHERS.
2) CALCULATIONS MAY or MAY NOT SHOW THE EFFECT OF SHADOWING CAUSED BY


- BUILDINGS AND OBJECTS WITHIN THE CALCULATED SPACE OR IN THE SITE AREA. 3) READINGS SHOWN ARE INITIAL HORIZONTAL FOOTCANDLES ON A FLAT SITE
- WITHOUT REFLECTIONS OR OBSTRUCTIONS UNLESS OTHERWISE INDICATED.
- 4) THIS CALCULATION IS BASED ON LIMITED INFORMATION SUPPLIED BY OTHERS TO
- SWANEY LIGHTING ASSOCIATES AND STANDARD ASSUMPTIONS OF THE SPACE AND/OR SITE. 5) CONFORMANCE TO CODES AND OTHER LOCAL REQUIREMENTS AS DETERMINED BY THE AHJ ARE THE RESPONSIBILITY OF THE OWNER AND/OR THE OWNER'S REPRESENTATIVE.
- 6) THIS LAYOUT DRAWING MUST BE COORDINATED WITH THE SITE LOCATION FOR
- CORRECT FIXTURE ORIENTATION.
- 7) DOCUMENTS PRINTED OR PLOTTED FROM ELECTRONIC FILES MAY APPEAR AT OTHER THAN THE DESIRED OR ASSUMED GRAPHIC SCALES.
- IT IS THE RESPONSIBILITY OF THE RECIPIENT TO VERIFY THAT THE PRINTED OR PLOTTED-TO-SCALE DRAWING IS PRINTED TO SCALE.

Calculation Summary						
Label	Avg	Max	Min	Avg/Min	Max/Min	
property line	0.21	0.7	0.0	N.A.	N.A.	
RAMP	5.83	10.5	1.3	4.5	8.1	
SITE	0.53	17.2	0.0	N.A.	N.A.	

## Luminaire Schedule (note fixture cataloge numbers are not complete)

У	Lum. Lumens	LLF	Lum. Watts	Description				
	1679	0.900	20.4	SL1-18L3K				
	1080	0.900	12.7	LF4SQSL-4SQSL11L30K8				
	2588	0.900	28.6	LNC2-12L-3K-070-4				
	1680	0.900	22.2	LNC-9LU-3K-4				
	849	0.900	13	LNC-5LU-3K-4-X				





# Landscape Notes

- 1. Design is based on drawings by MJS Engineering dated December 2018 and may require adjustment due to actual field conditions
- 2. The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site from erosion.
- Erosion Control shall be in place prior to construction.
- 4. Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water bodies, Wetlands and/or drainage ways prior to any construction.
- 5. The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any
- discrepancies or changes in layout and/or grade relationships prior to construction. 6. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A
- graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.
- Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line at a minimum and shall include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portalets within the tree protection area.
- 8. Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the Contractor. 9. The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call
- DIGSAFE at 1-888-344-7233. 10. The Contractor shall procure any required permits prior to construction. 11. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates,
- macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement. 12. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a
- contractor is aware of a potential issue, and does not bring it to the attention of the landscape architect or owner's representative immediately, they may be responsible for the labor and materials associated with correcting the problem. 13. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
- 14. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern. 15. All plants shall be legibly tagged with proper botanical name. 16. The Contractor shall guarantee all plants for not less than one year from time of acceptance.
- 17. Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work. 18. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.
- 19. All landscaping shall be provided with either of the following a. An underground sprinkling system
- b. An outside hose attachment within 150 feet 20. If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas. 21. The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, and watering of plants. Plants shall be appropriately watered prior to, during and after planting. It is the contractor's responsibility to provide water from off site, should it not be available on site.
- 22. All disturbed areas will be dressed with 6" of topsoil and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost. 23. Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native bark not longer than 4" in length and 1/2" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be
- 24. Drip strip shall extend to 6" beyond roof overhang and shall be edged with 3/16" thick metal edger. 25. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied
- mulch) over the root ball of any plant. 26. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a
- height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy. 27. Snow shall be stored a minimum of 5' from shrubs and trunks of trees.
- 28. Landscape Architect is not responsible for the means and methods of the contractor.

Plant Li	st				
SHRUBS					
Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Cle	Clethra alnifolia 'Ruby Spice'	Ruby Spice Summersweet	40	5 gal	
PERENNIA	LS, GROUNDCOVERS, VINES and AN	INUALS			
Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Hos	Hosta 'Sum and Substance'	Sum and Substance Hosta	4	1 gal	
Vm	Vinca minor 'Bowles'	Bowles Periwinkle	3	50/plugs/flat	



