OWNER TOOMERFS, LLC 37 MAIN STREET UNIT O DURHAM, NH 03824


CIVIL ENGINEER



LANDSCAPE ARCHITECT

WOODBURN & COMPANY 103 KENT PLACE NEWMARKET, NEW HAMPSHIRE (603) 659–5949 SURVEYOR

NORWAY PLAINS ASSOCIATES, INC. 2 CONTINENTAL BOULEVARD ROCHESTER, NEW HAMPSHIRE 03867 (603) 335-3948



SITE PLAN

for

TOOMERFS, LLC

19 MAIN STREET & 21 MAIN STREET DURHAM, NH

REVISED 6 APRIL, 2021





TABLE OF CONTENTS

TITLE	SHEET
EXISTING CONDITIONS PLAN.	.E1
PROPOSED SITE PLAN.	C-101
GRADING, DRAINAGE, UTILITY & EROSION CONTROL PLAN	C-102
DEMOLITION PLAN	C-103
LANDSCAPING PLAN	L1
LIGHTING PLAN	LT1
CONSTRUCTION DETAILS	C-501-C-506



2.	REVISIONS PER TOWN ENGINEER REVIEW LETTER DATED 02/22/2021	04/06/21	AWS
1.	DRAINAGE UPDATES	02/02/21	AWS
0.	INITIAL ALTERNATE ENTRANCE SUBMISSION	01/05/21	AWS
NO.	REVISIONS	DATE	INT.



CIVIL ENGINEERS

reserved registry of deeds

NOTES:

location: 20 main street tm 4—56 christine & mark h. henderson 1 main street, suite 16


locatio tr st george

- 1. Total parcel area: Map 5, Lots 1-9,1-10,1-15,1-16 3.2 acres
- 2. The parcel is zoned Church Hill Dirstirct. Tax map 5 Lots 1-9 & 1-10 are within the historic overlay district.
- 3. Minimum lot requirements: lot size = 5000 SF,
- 4. Building setbacks: Front = 15' (all Streets) Side = 5'Rear = 15'


dhs cb

locatio -

- Maximum building height: 30' Maximum Impervious Surface Ratio 80%
- 6. The lots are serviced by the municipal water and sewer system.
- 7. The proposed lot is not located within the 100 year flood zone as shown on the flood insurance rate map dated 09/30/15 community panel 33017c0318e.





existing features plan 19-21 main street durham, strafford county, nh for: Toomerfs, LLC




2 CONTINENTAL BLVD., ROCHESTER, NH 603-335-3948

P:\18pro\18-041\Internal\Drawing files\18041 CivilR.c 2021-04-07 01:40 pm










LANDSCAPE NOTES:

- 1. Design is based on drawings by MJS Engineering, P.C. dated January 20, 2021, and may require adjustment due to actual
- field conditions. 2. The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site from erosion.
- Erosion Control shall be in place prior to construction.
- 4. Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water
- bodies, Wetlands and/or drainage ways prior to any construction. The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any
- discrepancies or changes in layout and/or grade relationships prior to construction. 6. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor. Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or
- other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line at a minimum and shall include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portalets within the tree protection area.
- This plan is for review purposes only, NOT for Construction. Construction Documents will be provided upon request. Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the
- Contractor. 10. The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call DIGSAFE at 1-888-344-7233.
- 11. The Contractor shall procure any required permits prior to construction.
- 12. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement. 13. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or
- construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a contractor is aware of a potential issue and does not bring it to the attention of the landscape architect or owner's representative immediately, they may be responsible for the labor and materials associated with correcting the problem.
- 14. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in ANSI Z60.1 of the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
- 15. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern. 16. All plants shall be legibly tagged with proper botanical name.
- 17. The Contractor shall guarantee all plants for not less than one year from time of acceptance.
- 18. Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
- 19. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason. 20. All landscaping shall be provided with either of the following
- a. An underground sprinkling system b. An outside hose attachment within 150 feet
- 21. If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas.
- 22. The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, and watering of plants. Plants shall be appropriately watered prior to, during and after planting. It is the contractor's responsibility to provide water from off site, should it not be available on site.
- 23. All disturbed areas will be dressed with 6" of topsoil and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost. 24. Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native
- bark not longer than 4" in length and $\frac{1}{2}$ " in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be
- 25. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
- 26. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy.
- 27. Snow shall be stored a minimum of 5' from shrubs and trunks of trees.
- 28. Landscape Architect is not responsible for the means and methods of the contractor.

TREE PLANTING DETAIL



Trees greater than 3" in caliper shall be guyed with three guys per tree, spaced evenly around the trunk with 12 gauge wire. Plastic hose sections shall be used at attachment to trees. Each guy wire shall be flagged with a visual marker. 24" stakes or metal drive anchors shall be used to anchor the guy wires. Stakes/Anchors shall be driven 12" min. outside the edge of the planting pit into stable soil. Remove all guying NO LATER than the end of the first growing season after planting.

6" Corrugated PVC tree sock

Each tree must be planted such that the original trunk flare is visible at the top of the root ball. Trees where the original trunk flare is not visible may be rejected. Do NOT cover the top of the root ball with soil. Before planting Contractor shall inspect the rootball for the location of the original root flare. If the original root flare is not visible at the top of the root ball then the Contractor shall then gently remove from the top of the root ball any excess soil from nursery operations that may be covering the original root flare. All secondary and girdling roots shall be removed prior to planting. Trees with 4" or more of extraneous soil and/or adventitious roots greater than 1/8" shall be rejected. The tree shall be planted with the original root flare at or slightly (2-3") above surrounding finished grade.


Backfill with existing soil, in sandy and heavy clay soils add 20% max. by volume composted organic material to the existing soil.


Remove all twine, rope, wire, and burlap

If plant is shipped with a wire basket around the root ball, prior to planting, the contractor shall cut away the bottom of the wire basket, leaving the sides in place. Once the tree is placed and faced, the contractor shall remove the remainder of the wire basket and backfill the planting pit as noted above.

Plant L	ist
TREES	
Symbol	E
Am	Amelanchier cana
Ar	Acer rubrum 'Oct
Ls	Liquidambar styra
Pa	Picea abies
Pg	Picea glauca
Th	Thuja plicata 'Gre
Ua	Ulmus americana

Botanical Name	Common Name	Quantity	Size	Comments
adensis	Shadblow Serviceberry	1	2.5-3" cal	B&B
tober Glory'	October Glory Red Maple	2	2.5-3" cal	B&B
aciflua	American Sweetgum	4	2.5-3" cal	B&B
	Norway Spruce	10	7-8' ht.	B&B
	White Spruce	9	7-8' ht.	B&B
een Giant'	Green Giant Arborvitae	25	10' ht.	B&B
a 'Princeton'	Princeton American Elm	10	2.5-3" cal	B&B
'Green Vase'	Green Vase Zelkova	4	2.5-3" cal	B&B





ymbol	Label	Quantity	Manufacturer	Catalog Number	Description	Lamp	Number Lamps	Filename	Lumens Per Lamp	Light Loss Factor	Wattage	Efficiency	Distribut ion
	EX	1	XXXXX	XXXXXXX	Existing Lantern-Style Fixture; mounted at 14ft	LED	1	962TC-XRLED- 12L45T5- MDL14-SV1.IES	5166	0.9	59.1	100%	
	G5	1	Sternberg Lighting	962TC-XRLED-12L45T5- MDL14-SV1	Glenn Ellen Series; mounted at 14ft	LED	1	962TC-XRLED- 12L45T5- MDL14-SV1.IES	5166	0.9	59.1	100%	
	S2	1	Lithonia Lighting	DSX0 LED P1 30K T3M MVOLT SPA DDBXD with SSS 12 4C DM19AS DDBXD	DSX0 LED Area Fixture; mounted at 12ft	LED	1	DSX0_LED_P1_ 30K_T3M_MVOL T.ies	4248	0.9	38	100%	TYPE III, MEDIUM, BUG RATING: B1 - U0 - G1
	S 4	3	Lithonia Lighting	DSX0 LED P2 30K VLS MVOLT SPA DDBXD with SSS 18 4C DM19AS DDBXD	DSX0 LED Visual Comfort, P2 symmetric Type V distribution 30K; mounted at 20ft (18ft pole on 2ft base)	LED	1	DSX0_LED_P2_ VLS_30K.ies	7973	0.9	83	100%	TYPE VS, BUG RATING: B3 - U0 - G1
	Т4	3	Lithonia Lighting	DSX0 LED P3 30K VLS MVOLT SPA DDBXD with SSS 18 4C DM19AS DDBXD	DSX0 LED Visual Comfort; mounted at 20ft (18ft pole on 2ft base)	LED	1	DSX0_LED_P3_ VLS_30K.ies	10910	0.9	116	100%	TYPE VS, BUG RATING: B3 - U0 - G1


Statistics

Description	Symbol	Avg	Max	Min	Max/Min	Avg/
Outside of Parking Lot	+	0.0 fc	1.5 fc	0.0 fc	N/A	N//
Parking at Rooming House	+	0.2 fc	0.5 fc	0.0 fc	N/A	N//
Parking Lot	+	0.9 fc	5.2 fc	0.0 fc	N/A	N//

/Min /Α /A /A

8770 CDN:S UBICETUIC APM FILMUNT ⁺0.0 ⁺0.1 +0.0 +0. .0 0 To: +0.2 to.4 to.9 222 +4.8 +4.8 +4.94 +5.0 +2.6 1.1 +0.6 +0.6 +0.9 +1.2 +1.2 +0.9 +0.5 +0.2 +0.1 +0.0 +0.0 +0.0 0.1 +0.2 +0.3 +0.7 +1.6 +3.1 +4.0 +3.4 +1.9 +1.9 +0.7 +0.9 +1.8 +2.8 +2.7 +1.8 +0.9 +0.4 +0.9 +0.1 +0.1 +0.0 +0.0 +0.1 +0.1 +0.3 +0.5 +0.9 +1.5 +1.8 +1.6 +1.0 +0.7 +0.7 +1.1 +2.5 +3.9 +3.7 +2.8 +1.2 0.5 +0.2 +0.1 +0.1 +0.0 +0.0 +0.0 +0.8 +0.1 +0.1 +0.2 +0.3 +0.4 +0.5 +0.5 +0.4 +0.3 +0.3 +0.4 +0.6 +0.2 +1.8 +2.0 +1.4 +0.7 +0.8 +0.1 +0.0 +0.0 +0.1 +0.2 +0.4 +0.6 +0.7 +0.7 +0.6 +0.4 +0.3 +0.3 +0.2 +0.3 +0.4 +0.6 +0.8 +0.8 +0.6 +0.4 +0.2 +0.1 +0.0 +0.0 +0.0 +0.0 +0.0 +0.0 +0.1 +0.2 +0.4 +0.8 +1.3 +1.7 +1.5 +0 +0.6 +0.4 +0.3 +0.3 +0.3 +0.3 +0.4 +0.4 +0.4 +0.3 +0.2 +0.1 +0.1 +0.1 +0.0 +0.0 +0.0 +0.0 toh N0 510 5470 $\begin{array}{c} \mathbf{u}_{\mathbf{R}} \\ + \mathbf{0}.1 \\ + \mathbf{0}.1 \\ + \mathbf{0}.1 \\ + \mathbf{0}.2 \end{array} + \begin{array}{c} \mathbf{1} \mathbf{0} \\ \mathbf{0}.5 \\ + \mathbf{0}.6 \\ + \mathbf{2}.6 \\ + \mathbf{2}.6 \\ + \mathbf{1}.7 \\ + \mathbf{0}.9 \\ + \mathbf{0}.7 \\ + \mathbf{0}.9 \\ + \mathbf{0}.7 \\ + \mathbf{0}.9 \\ + \mathbf{1}.9 \\ + \mathbf{3}.3 \\ + \mathbf{3}.6 \\ + \mathbf{2}.7 \\ + \mathbf{1}.3 \\ + \mathbf{0}.6 \\ + \mathbf{0}.2 \\ + \mathbf{0}.7 \\ + \mathbf{0}.7 \\ + \mathbf{0}.9 \\ + \mathbf{1}.9 \\ + \mathbf{0}.3 \\ + \mathbf{0}.6 \\ + \mathbf{0}.7 \\ + \mathbf{0}.8 \\ + \mathbf{0}.7 \\ + \mathbf{0}.9 \\ + \mathbf{0}$ CURLINU, M C CO COLAL CORTRA RESSENTE [/] ⁺0.0 ⁺0.0 4^{+} + 0.1 + 0.2 + 0.3 + 0.4 + 0.4 + 0.4 + 0.3 + 0.3 + 0.3 + 0.4 + 0.7 + 1 + 1.3 + 1.1 + 0.6 + 0.37 + 0.6 + 0.7 + 0.6 + 0.37 + 0.6 + 0.6 + 0. $\begin{array}{c} \hline 0.0 & ^{+}0.0 & ^{+}0.1 & ^{+}0.2 & ^{+}0.4 & ^{+}0.5 & ^{+}0.7 & ^{+}0.7 & ^{+}0.5 & ^{+}0.3 & ^{+}0.2 & ^{+}0.2 & ^{+}0.2 & ^{+}0.3 & ^{+}0.4 & ^{+}0.5 & ^{+}0.5 & ^{+}0.5 & ^{+}0.3 & ^{+}0.2 & ^{+}0.0 & ^{+}0.0 \end{array}$ $0 = \frac{1}{2} + \frac{1}{2} +$ +0.1 +0.3 +0.7 +1.8 +41 +52 +52 +3.1 +1.3 +0.7 +0.5 +0.6 +0.7 +0.8 +0.7 +0.4 +0.3 +0.2 +0.1 +0.1 +0.0 +0.0 +0.0 +0.0 ^{/+}0.0 ⁺0.0 ^{/+}0,0 +0.0 +0.0 +0.0 +0.0 +0.1 +0.3 105 +0.8 +1.1 +1.1 +0.8 +0.6 +0.4 +1.9 3.7 +3.5 +1.7 +0.7 +0.3 +0.1 +0.0 +0.0 +0.0 TUBHT +0.0 + 0.0 $+ 00^{+}0.0^{+$ $0.0 \quad +0.0 \quad +0.0 \quad +0.0 \quad +0.0 \quad +0.1 \quad +0.2 \quad +0.3 \quad +0.5 \quad +0.4 \quad +0.3 \quad +0.2 \quad +0.1 \quad +0.4 \quad +0.0 \quad +$ +0.0 +0.0 +0.0 +0.1 \$ +0.0 +0.0 +0.0 +0.0 +0.0 +0.0

1и465



CONSTRUCTION SEQUENCING AND EROSION CONTROL NOTES:

AREA OF DISTURBANCE/STABILIZATION THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL THE AREA OF UNSTABILIZED SOIL EXCEED 5 ACRES AT ANY ONE TIME BEFORE THE AREA IS STABILIZED

- AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: 1. IN AREAS TO BE PAVED, BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHDOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION, 2016, ITEM NO. 304.1 OR 304.2 HAVE BEEN INSTALLED;
- 2. IN AREAS NOT TO BE PAVED
- 2.A. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; 2.B. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN
- INSTALLED 2.C. EROSION CONTROL BLANKETS HAVE BEEN INSTALLED IN ACCORDANCE WITH ENV-WQ

1506.03 DISTURBED AREAS SHALL BE TEMPORARILY STABILIZED WITHIN 45 DAYS AND PERMANENTLY STABILIZED NO LATER THAN 3 DAYS AFTER FINAL GRADING.

EROSION CONTROL PRACTICES:

- A. INSTALLATION: 1. INSTALL ALL EROSION CONTROLS AS SHOWN ON THE GRADING PLAN, TYPICAL DETAILS, AND IN CONFORMANCE WITH THE EROSION AND SEDIMENT CONTROL NOTES ON THIS PAGE. MANUFACTURER'S SPECIFICATIONS SHALL BE FOLLOWED.
- INSPECTION: INSPECT ALL EROSION CONTROLS WEEKLY AND AFTER EVERY RAIN EVENT OF 0.5 INCHES OR GREATER UNLESS OTHERWISE NOTED. TEMPORARY STABILIZATION PRACTICES SHALL BE INSPECTED ONCE PER WEEK DURING CONSTRUCTION UNTIL EXPOSED SURFACES ARE STABILIZED.
- ANY SIGNS OF RILL OR GULLY EROSION SHALL BE IMMEDIATELY REPAIRED. MAINTENANCE: 1. MAINTAIN EROSION CONTROLS PER THE TYPICAL DETAILS AND IN CONFORMANCE WITH THE
- EROSION AND SEDIMENT CONTROL NOTES ON THIS PAGE. REMOVAL 1. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE 85% VEGETATIVE
- COVER HAS BEEN ESTABLISHED. 2. AFTER REMOVAL, ALL DISTURBED AREAS SHALL BE REGRADED. FERTILIZED. AND RESEEDED. MONITOR TO ENSURE VEGETATIVE GROWTH IS ESTABLISHED AND REPAIR AS NEEDED UNTIL MINIMUM OF 85% VEGETATIVE COVER IS ESTABLISHED.

COLD WEATHER SITE STABILIZATION

- A. TO ADEQUATELY PROTECT WATER QUALITY DURING COLD WEATHER AND DURING SPRING RUNOFF, THE ADDITIONAL STABILIZATION TECHNIQUES SPECIFIED IN THIS SECTION SHALL BE EMPLOYED DURING THE PERIOD FROM OCTOBER 15 THROUGH MAY 1. B. SUBJECT TO (C), BELOW, THE AREA OF EXPOSED, UNSTABILIZED SOIL SHALL BE
- LIMITED TO ONE ACRE: AND PROTECTED AGAINST EROSION BY THE METHODS DESCRIBED IN THIS SECTION PRIOR TO ANY THAW OR SPRING MELT EVENT
- THE ALLOWABLE AREA OF EXPOSED SOIL MAY BE INCREASED IF A WINTER CONSTRUCTION PLAN IS DEVELOPED BY A QUALIFIED ENGINEER OR A CPESC SPECIALIST AND SUBMITTED TO THE DEPARTMENT FOR APPROVAL AS A REQUEST TO WAIVE THE ONE-ACRE LIMIT.
- SUBJECT TO (F) AND (G), BELOW, ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR THAT ARE DISTURBED AFTER OCTOBER 15, SHALL BE SEEDED AND COVERED WITH 3 TO 4 TONS OF HAY OR STRAW MULCH PER ACRE SECURED WITH ANCHORED NETTING OR TACKIFIER OR WITH AT LEAST 2 INCHES OF EROSION CONTROL MIX MEETING THE CRITERIA OF ENV-WQ 1506.05(B).
- SUBJECT TO (F) AND (G), BELOW, ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF 15% OR GREATER THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR THAT ARE DISTURBED AFTER OCTOBER 15, SHALL BE SEEDED AND COVERED WITH A PROPERLY INSTALLED AND ANCHORED EROSION CONTROL BLANKET OR WITH AT LEAST 4 INCHES OF EROSION CONTROL MIX MEETING THE CRITERIA OF ENV-WQ 1506.05(B).
- ANCHORED HAY MULCH OR EROSION CONTROL MIX THAT MEETS THE CRITERIA OF ENV-WQ 1506.05(B) SHALL NOT BE INSTALLED OVER SNOW GREATER THAN ONE INCH IN DEPTH.
- EROSION CONTROL BLANKETS SHALL NOT BE INSTALLED OVER SNOW GREATER THAN ONE INCH IN DEPTH OR ON FROZEN GROUND.
- H. ALL PROPOSED STABILIZATION IN ACCORDANCE WITH (D) OR (E), ABOVE, SHALL BE COMPLETED WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAN 5 DAYS. ALL DITCHES OR SWALES THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY
- OCTOBER 15, OR THAT ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR FROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS, AS DETERMINED BY THE OWNER'S ENGINEERING CONSULTANT. AFTER OCTOBER 15. INCOMPLETE ROAD OR PARKING AREAS WHERE ACTIVE CONSTRUCTION OF
- THE ROAD OR PARKING AREA HAS STOPPED FOR THE WINTER SEASON SHALL BE PROTECTED WITH A MINIMUM 3-INCH LAYER OF BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHDOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION 2016, TABLE 304-1, ITEM NO. 304.1, 304.2, OR 304.3, AVAILABLE AS NOTED IN APPENDIX B

TEMPORARY VEGETATION

- A. SITE PREPARATION INSTALL EROSION AND SEDIMENT CONTROL MEASURES AS SPECIFIED ABOVE.
- ENSURE RUNOFF IS DIVERTED FROM SEEDED AREA. ON SLOPES OF 4:1 OR STEEPER, CREATE HORIZONTAL GROOVES PERPENDICULAR TO THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE RUNOFF.
- B. SEED BED PREPARATION REMOVE STONES AND TRASH FROM AREA TO BE SEEDED.
- COMPACTED SOIL SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME, AND SEED
- APPLY FERTILIZER AT A RATE OF 600 LBS PER ACRE OF 10-10-10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE SEEDING
- 1. SEED PER THE FOLLOWING RECOMMENDATIONS

SEASON	APPLICATION DATE	MIXTURE TYPE	QUANTITY (Ib./Ac.)
EARLY SPRING	NO LATER THAN 5/15	OATS	80
LATE SPRING/ FALL	4/1 TO 6/1 & 8/15 TO 9/15	PERENNIAL RYE	30
EARLY SPRING/ FALL	4/1 TO 5/15 & 8/15 TO 9/15	ANNUAL RYE	40
FALL	8/15 TO 9/15	WINTER RYE	112

- 2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING. TEMPORARY SEEDING SHALL OCCUR PRIOR TO SEPTEMBER 15TH IN THE YEAR IN WHICH
- THE AREA BEING SEEDED WAS DISTURBED. AREAS SEEDED BETWEEN MAY 15TH AND AUGUST 15TH SHALL BE COVERED WITH HAY OR STRAW MULCH MEETING THE FOLLOWING CRITERIA: 4.A. HAY AND STRAW MULCHES SHALL BE ANCHORED WITH MULCH NETTING OR TACKIFIER SO THAT THEY ARE NOT BLOWN AWAY BY WIND OR WASHED AWAY BY FLOWING
- WATER: 4.B. MULCH MATERIALS SHALL BE SELECTED BASED UPON SOILS, SLOPE, FLOW
- CONDITIONS. AND TIME OF YEAR: 4.C. HAY OR STRAW MULCH SHALL BE APPLIED AT A RATE OF 1.5 TO 2 TONS PER ACRE, EQUIVALENT TO 70 TO 90 POUNDS PER 1,000 SQUARE FEET; IF VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA IS NOT ACHIEVED PRIOR TO OCTOBER 15TH, ONE OR MORE ADDITIONAL EROSION CONTROL
- METHODS SHALL BE IMPLEMENTED. MAINTENANCE
- 1. TEMPORARY SEEDING SHOULD BE INSPECTED WEEKLY AND AFTER ANY RAINFALL EXCEEDING 1/2 INCH IN 24 HOURS ON ACTIVE CONSTRUCTION SITES. TEMPORARY SEEDING SHOULD ALSO BE INSPECTED JUST PRIOR TO SEPTEMBER 15, TO ASCERTAIN WHETHER ADDITIONAL SEEDING IS REQUIRED TO PROVIDE STABILIZATION OVER THE WINTER PERIOD. BASED ON INSPECTION, AREAS SHOULD BE RESEEDED TO ACHIEVE FULL STABILIZATION OF
- EXPOSED SOILS. IF IT IS TOO LATE IN THE PLANTING SEASON TO APPLY ADDITIONAL SEED, THEN OTHER TEMPORARY STABILIZATION MEASURES SHOULD BE IMPLEMENTED. AT A MINIMUM, 85% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION. 4. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHOULD BE
- MADE AND AREAS SHOULD BE RESEEDED, WITH OTHER TEMPORARY MEASURES (E.G., MULCH) USED TO PROVIDE EROSION PROTECTION DURING THE PERIOD OF VEGETATION ESTABLISHMENT.

PERMANENT VEGETATION SITE PREPARATION

- REFER TO SITE PREPARATION FOR TEMPORARY SEEDING. B. SEED BED PREPARATION REFER TO SEED BED PREPARATION FOR TEMPORARY SEEDING IN CONJUNCTION WITH THESE
- NOTES 2. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OPERATION SHOULD BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM. FINE SEEDBED IS PREPARED. ALL BUT CLAY OR SILTY SOILS AND COARSE SANDS SHOULD BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE.
- REMOVE FROM THE SURFACE ALL STONES 2 INCHES OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, CONCRETE, CLODS, LUMPS, TRASH OR OTHER UNSUITABLE MATERIAL.
- INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED; THE AREA MUST BE TILLED AND FIRMED AS ABOVE.
- WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED. 6. APPLY FERTILIZER AT A RATE OF 600 LBS PER ACRE OF 10-10-10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE.
- C. SEEDING 1. UNLESS OTHERWISE NOTED, GRASS SEED MIXTURE 'C' SHALL BE APPLIED AT THE SPECIFIED RATE AS NOTED IN THE 'SEED MIXTURES FOR PERMANENT VEGETATION' TABLE APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR 2.
- HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING OPERATIONS SHOULD BE ON THE CONTOUR. WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS
- USED, THE SEEDBED SHOULD BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR LIGHT DRAG WHEN HYDROSEEDING (HYDRAULIC APPLICATION), PREPARE THE SEEDBED AS SPECIFIED ABOVE OR BY HAND RAKING TO LOOSEN AND SMOOTH THE SOIL AND TO REMOVE SURFACE
- STONES LARGER THAN 2 INCHES IN DIAMETER. SLOPES MUST BE NO STEEPER THAN 2 TO 1 LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED. THE USE OF
- FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). BETTER PROTECTION IS GAINED BY USING STRAW MULCH AND HOLDING IT WITH ADHESIVE MATERIALS OR 500 POUNDS PER ACRE OF WOOD FIBER MULCH. SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING
- TEMPORARY SEEDING SHALL OCCUR PRIOR TO SEPTEMBER 15TH IN THE YEAR IN WHICH THE AREA BEING SEEDED WAS DISTURBED.
- AREAS SEEDED BETWEEN MAY 15TH AND AUGUST 15TH SHALL BE COVERED WITH HAY OR STRAW MULCH MEETING THE FOLLOWING CRITERIA: 9.A. HAY AND STRAW MULCHES SHALL BE ANCHORED WITH MULCH NETTING OR TACKIFIER SO THAT THEY ARE NOT BLOWN AWAY BY WIND OR WASHED AWAY BY FLOWING WATER; 9.A. MULCH MATERIALS SHALL BE SELECTED BASED UPON SOILS, SLOPE, FLOW CONDITIONS, AND TIME OF YEAR; 9.B. HAY OR STRAW MULCH SHALL BE APPLIED AT A RATE OF 1.5 TO 2 TONS PER ACRE,
- EQUIVALENT TO 70 TO 90 POUNDS PER 1,000 SQUARE FEET; 10. IF VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA IS NOT ACHIEVED PRIOR TO OCTOBER 15TH, ONE OR MORE ADDITIONAL EROSION CONTROL METHODS SHALL BE IMPLEMENTED.
- MAINTENANCE PERMANENTLY SEEDED AREAS SHOULD BE INSPECTED MONTHLY. MOW SEEDED AREAS AS NECESSARY BASED ON INSPECTION, AREAS SHOULD BE REPAIRED AND/OR RESEEDED TO ENSURE 85%
- OF THE SOIL SURFACE IS COVERED BY VEGETATION.

MULCHING & EROSION CONTROL MATTING GENERAI

- 1. APPLY PRIOR TO A STORM EVENT. CLOSELY MONITOR THE WEATHER TO HAVE ADEQUATE WARNING OF SIGNIFICANT STORMS.
- 2. MULCHING WITHIN A SPECIFIED TIME PERIOD FROM ORIGINAL SOIL EXPOSURE 2.A. WITHIN 100 FEET OF WETLANDS THE TIME PERIOD SHOULD BE NO GREATER THAN 7
- 2.B. IN OTHER AREAS IT SHALL BE NO GREATER THAN 14 DAYS. 3. MULCH MATERIALS SHALL BE SELECTED BASED UPON SOILS, FLOW CONDITIONS, AND TIME OF YEAR.
- B. TEMPORARY MULCHING 1. HAY OR STRAW MULCHES
 - 1.A. ORGANIC MULCHES INCLUDING HAY AND STRAW SHALL BE AIR-DRIED, FREE OF
 - UNDESIRABLE SEEDS AND COARSE MATERIALS.
 - 1.B. APPLICATION RATE SHALL BE 2 BALES/1,000 SF (70-90 POUNDS) OR 1.5-2.0 TONS/ACRE TO COVER 75-90% OF THE GROUND.
 - 1.C. ANCHORING SHALL BE ONE OF THE FOLLOWING 1.C.1. NETTING SHALL BE JUTE, WOOD FIBER, OR BIODEGRADABLE PLASTIC NETTING INSTALLED PER MANUFACTURER'S SPECIFICATIONS. 1.C.2. TACKIFIER: APPLY POLYMER OR ORGANIC TACKIFIER TO ANCHOR HAY OR STRAW MULCH APPLY PER MANUFACTURER'S SPECIFICATIONS TYPICAL APPLICATION RATES ARE 40-60 LBS/ACRE FOR POLYMER MATERIAL AND 80-120 LBS/ACRE FOR ORGANIC LIQUID.
 - 1.D. WINTER APPLICATION: APPLY TO A DEPTH OF 4 INCHES OR DOUBLE THE ABOVE LISTED APPLICATION RATE. NOTE THAT IF SEEDING IS NECESSARY, MULCH WILL NEED TO BE REMOVED AND THE AREA SEEDED AND MULCHED IN THE SPRING. 1.E. MAINTENANCE
- 1.E.1. INSPECT PERIODICALLY AND AFTER RAIN STORMS FOR RILLS OR DISPLACEMENT OF MULCH. REPAIR AS NECESSARY. CONTINUE INSPECTIONS UNTIL 85% VEGETATIVE COVER IS ESTABLISHED. 2. EROSION CONTROL BLANKET OR MATTING
- 2.A. REFER TO PLANS FOR TYPICAL EROSION CONTROL MATTING DETAIL. INSTALL PER MANUFACTURERS SPECIFICATIONS. 2.B. APPLICATION AND TIMING
- 2.B.1. DURING THE GROWING SEASON (APRIL 15 SEPTEMBER 15) USE ON THE BASE OF GRASSED WATERWAYS, STEEP SLOPES (15% OR GREATER), ANY
- DURING THE LATE FALL AND WINTER (SEPTEMBER 15 APRIL 15) IN 2.B.2. ADDITION TO THOSE LISTED ABOVE USE ON SIDE SLOPES OF GRASSED
- WATERWAYS AND MODERATE SLOPES (GREATER THAN 8%). 3. MAINTENANCE 3.A. INSPECT PERIODICALLY AND BEFORE AND AFTER STORM EVENTS TO ENSURE CONTACT
- AS NECESSARY C. PERMANENT MULCHING
 - 1. WOOD CHIPS OR GROUND BARK 1.A. APPLY TO A THICKNESS OF 2 TO 6 INCHES. APPLICATION RATES ARE 10-20
 - TONS/ACRE OR 460-920 POUNDS/1,000 SF. 1.B. MAINTENANCE: INSPECT ANNUALLY AND AFTER RAIN EVENTS OF 2.5 INCHES OR MORE IN A 24 HOUR PERIOD. REPAIR/REPLACE AS NECESSARY.
 - 2. EROSION CONTROL MIX 2.A. SHALL BE PLACED AT A THICKNESS OF 2 INCHES OR MORE FOR MULCHING. 2.B. COMPOSITION OF THE MIX SHALL BE AS FOLLOWS: 2.B.1. ORGANIC MATTER CONTENT SHALL BE BETWEEN 25-65% DRY WEIGHT BASIS.
 - 2.B.2. PARTICLE SIZE BY WEIGHT SHOULD BE 100% PASSING THE 3" SCREEN, 90-100% PASSING THE 1" SCREEN, 70-100% PASSING THE 0.75 INCH SCREEN, AND 30-75% PASSING THE 0.25 INCH SCREEN. 2.B.3. THE ORGANIC PORTION SHALL BE ELONGATED AND FIBROUS SUCH AS FROM
 - SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR EQUIVALENT MANUFACTURED PRODUCTS. IT SHALL NOT CONTAIN WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS. THE MIX SHALL NOT CONTAIN SILTS, CLAYS, OR FINE SANDS.
 - 2.B.5. SOLUBLE SALTS CONTENT SHALL BE < 4.0MMHOS/CM AND A pH OF 5.0-8.0, 2.C. PLACEMENT OF BERM 2.C.1. PLACE BERM ALONG A LEVEL CONTOUR. BERM MUST BE A MINIMUM OF 12"
 - SLOPE OF LESS THAN 5%. 2.D. MAINTENANCE: INSPECT PERIODICALLY AND AUGMENT AS NEEDED TO MAINTAIN INITIAL THICKNESS. REPLACE IF NO LONGER FUNCTIONING AS INTENDED.

FINAL APPROVAL BY DU	IRHAM P
CERTIFIED BY MICHAEL I	BEHREND
CERTIFIED	
DATE	

DISTURBED SOIL WITHIN 100 FEET OF LAKES, STREAMS, AND WETLANDS.

WITH THE SOIL UNTIL 85% VEGETATIVE COVER IS ESTABLISHED. REPAIR AND RESTAPLE

HIGH ON THE UPHILL SIDE AND 2 FEET WIDE. UPSLOPE AREA MUST HAVE A

LANNING BOARD. DT, TOWN PLANNER

- SOIL STOCKPILES GENERAL STOCKPILES MUST BE LOCATED 50 FEET FROM DITCHES AND CULVERT INLETS. PROTECTION OF STOCKPILES
- PROTECT SOIL AND AGGREGATE STOCKPILES WITH TEMPORARY PERIMETER SEDIMENT BARRIER SUCH AS SILT FENCE OR SILT SOCK.
- COVER ACTIVE STOCKPILES WITH ANCHORED PROTECTIVE COVERING PRIOR TO EXPECTED STORM EVENTS
- INACTIVE STOCKPILES SHALL BE COVERED WITH ANCHORED TARPS OR TEMPORARILY SEEDED AND MULCHED PER THE TEMPORARY VEGETATION
- AND MULCHING NOTES ON THIS PAGE. 4. STOCKPILES THAT ARE A SOURCE OF DUST SHALL BE COVERED.


DUST CONTROL A. DUST SHALL BE CONTROLLED ON SITE DURING CONSTRUCTION BY IMPLEMENTING THE FOLLOWING DUST CONTROL MEASURES MULCHING AND VEGETATIVE COVER TO REDUCE DUST.

MECHANICAL SWEEPERS AND FINE WATER SPRAYS. COVER SURFACES WITH CRUSHED STONE OR COARSE GRAVEL.

SEED MIXTURE SELECTION BASED ON SOIL TYPE								
	SOIL DRAINAGE							
USE	SEEDING MIXTURE	DROUGHTY	WELL DRAINED	MODERATELY WELL DRAINED				
STEEP CUTS AND FILLS, BORROW AND DISPOSAL AREAS	A	FAIR	GOOD	GOOD				
	B	POOR	GOOD	FAIR				
	C	POOR	GOOD	EXCELLENT				
	D	FAIR	EXCELLENT	EXCELLENT				
WATERWAYS, EMERGENCY SPILLWAYS, AND OTHER CHANNELS WITH FLOWING WATER.	A	GOOD	GOOD	GOOD				
	C	GOOD	EXCELLENT	EXCELLENT				
LIGHTLY USED PARKING LOTS, ODD AREAS,	A	GOOD	GOOD	GOOD				
UNUSED LANDS, AND LOW INTENSITY USE	B	GOOD	GOOD	FAIR				
RECREATION SITES.	C	GOOD	EXCELLENT	EXCELLENT				
PLAY AREAS AND ATHLETIC FIELDS. (TOPSOIL	E	FAIR	EXCELLENT	EXCELLENT				
IS ESSENTIAL FOR GOOD TURF.)	F	FAIR	EXCELLENT	EXCELLENT				

NOTE: POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREAS AND ATHLETIC FIELDS.

	SEED MIXTURES FOR PERMANENT VEGETATION						
MIXTURE	SPECIES	POUNDS PER ACRE	POUNDS PER 1,000 SF				
A	TALL FESCUE	20	0.45				
	CREEPING RED FESCUE	20	0.45				
	<u>REDTOP</u>	<u>2</u>	<u>0.05</u>				
	TOTAL	42	0.95				
В	TALL FESCUE	15	0.35				
	CREEPING RED FESCUE	10	0.25				
	CROWN VETCH	15	0.35				
	OR	-	-				
	<u>FLATPEA</u>	<u>30</u>	0.75				
	TOTAL	40 OR 55	0.95 OR 1.35				
С	TALL FESCUE	20	0.45				
	CREEPING RED FESCUE	20	0.45				
	<u>BIRDSFOOT_TREFOIL</u>	<u>8</u>	<u>0.20</u>				
	<i>TOTAL</i>	48	1.10				
D	TALL FESCUE	20	0.45				
	<u>FLATPEA</u>	<u>30</u>	<u>0.75</u>				
	TOTAL	50	1.20				
E	CREPPING RED FESCUE	50	1.15				
	<u>KENTUCKY BLUEGRASS</u>	<u>50</u>	<u>1.15</u>				
	TOTAL	100	2.30				
F	TALL FESCUE	150	3.60				



NOTES

- 1. SEDIMENT FILTER TRAP SHALL BE ACF REGULAR FLOW SILTSACK OR APPROVED EQUAL
- 2. FILTERS SHALL BE INSPECTED AFTER EVERY RAIN EVENT OF 0.25" OR GREATER AND SEDIMENTS SHALL BE REMOVED FROM TRAP WHEN SEDIMENT HAS REACHED TWO THIRDS OF THE DEPTH OF THE TRAP, OR IF PONDING OF WATER AT SURFACE BEGINS TO OCCUR. DO NOT PUNCTURE FILTER TRAP TO MITIGATE PONDING.

CATCH BASIN SEDIMENT FILTER DETAIL

FOR SEDIMENT FENCE WOVEN WIRE FENCE, IF REQUIRED, TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES.

2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP, MID SECTION, AND BOTTOM.

CONSTRUCTION NOTES

3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6 INCHES, FOLDED AND STAPLED.

4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SEDIMENT FENCE, OR 50% OF CAPACITY IS USED.


5. 12" DIAMETER FILTREXX SILTSOXX SHALL BE CONSIDERED AN ACCEPTABLE EQUAL TO SEDIMENT FENCE IF INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.


NO FUEL SHALL BE STORED ON SITE DURING CONSTRUCTION.

- SHALL BE REMOVED BY THE CONTRACTOR.
- APPLIED FOR AND RECEIVED.


CONSTRUCTION SEQUENCING:


- OF CONSTRUCTION CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES .. 6. CLEAR/GRUB 7. STOCKPILES A. STOCKPILE LOAM FOR RE-USE AS NEEDED. B. TEMPORARILY STABILIZE LOAM STOCKPILES WITH:
- FACILITIES AS LISTED ABOVE. SEDIMENT TRAP DETAIL.
- TO THEM 10. PARKING LOT CONSTRUCTION A. CUTS AND FILLS:
 - 2. FILLS:
- B. DRAINAGE AND UTILITY STRUCTURES
- EROSION CONTROL NOTES ON THIS SHEET.
















[-504



			AWS	AWS	AWS	INT.
STO	RMTECH CHAMBER SPECIFICATIONS		04/06/21	02/02/21	01/05/21	ATE
	CHAMBERS SHALL BE STORMTECH MC-4500. CHAMBERS SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE		04	02	01	
	COPOLYMERS. CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO					
	INTERNAL SUPPORT PANELS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION. THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE					
	INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.		DATED 02/22/2021			
	CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".		ER DATE			NS
	CHAMBERS SHALL BE DESIGNED AND ALLOWABLE LOADS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".		ENGINEER REVIEW LETTER		SUBMISSION	REVISIONS
	ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. THE CHAMBER MANUFACTURER SHALL SUBMIT THE FOLLOWING UPON REQUEST TO THE SITE DESIGN ENGINEER FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE:		IGINEER RE		ENTRANCE SUB	
	a. A STRUCTURAL EVALUATION SEALED BY A REGISTERED PROFESSIONAL ENGINEER THAT DEMONSTRATES THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY AASHTO FOR THERMOPLASTIC PIPE.		PER TOWN EN	VTES	TERNATE ENTF	
	b. A STRUCTURAL EVALUATION SEALED BY A REGISTERED PROFESSIONAL ENGINEER THAT DEMONSTRATES THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET. THE 50 YEAR CREEP MODULUS DATA		REVISIONS F		INITIAL ALT	
	SPECIFIED IN ASTM F2418 MUST BE USED AS PART OF THE AASHTO STRUCTURAL EVALUATION TO VERIFY LONG-TERM PERFORMANCE.		2.		.0	NO
	c. STRUCTURAL CROSS SECTION DETAIL ON WHICH THE STRUCTURAL EVALUATION IS BASED.					
	CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.					_
IM	PORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF MC-4500 CHAMBER SYSTEM	SEAL				S A.dwg
1.	STORMTECH MC-4500 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS					DETAL
2.	COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS. STORMTECH MC-4500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH	01/05/21	AWS	2 0	,	DRAINAGE
3.	MC-3500/MC-4500 CONSTRUCTION GUIDE". CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR EXCAVATOR SITUATED OVER THE CHAMBERS.	01/	AWS	SLM		
у.	 STORMTECH RECOMMENDS 3 BACKFILL METHODS: STONESHOOTER LOCATED OFF THE CHAMBER BED. BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE. BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR. 	DATE ISSUED:	SLALE: DESIGNED BY: DRAWN RY.	APPROVED BY:		FILE: CIVIL
4.	THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.	DATE I	DESIG	APPF		DMG
5.	JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.					
6.	MAINTAIN MINIMUM 9" (230 mm) SPACING BETWEEN THE CHAMBER ROWS.					03824
7. 8.	INLET AND OUTLET MANIFOLDS MUST BE INSERTED A MINIMUM OF 12" (300 mm) INTO CHAMBER END CAPS. EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE MEETING THE					
9.	AASHTO M43 DESIGNATION OF #3 OR #4. STONE SHALL BE BROUGHT UP EVENLY AROUND CHAMBERS SO AS NOT TO DISTORT THE CHAMBER SHAPE.	AILS			1-10	
	STONE DEPTHS SHOULD NEVER DIFFER BY MORE THAN 12" (300 mm) BETWEEN ADJACENT CHAMBER ROWS.	DETA			AND	URHAM
10.	STONE MUST BE PLACED ON THE TOP CENTER OF THE CHAMBER TO ANCHOR THE CHAMBERS IN PLACE AND PRESERVE ROW SPACING.		for		1-9	
11.	THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIAL BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.	TIOI	prepared	ERFS	_0TS	AINS
12.	ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.	ONSTRUCTION	ргер	TOOMER	Р 5, Г	Σ
NC	DTES FOR CONSTRUCTION EQUIPMENT	VST			<pre>< MAP</pre>	-
1.	STORMTECH MC-4500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".				TAX	
2.	 THE USE OF EQUIPMENT OVER MC-4500 CHAMBERS IS LIMITED: NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS. NO RUBBER TIRED LOADER, DUMP TRUCK, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE". WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH MC-3500/MC-4500 					19 MAIN
3.	FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK					
us	TRAVEL OR DUMPING.					
то	CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY USING THE UMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.		<u> </u>	IENTAL		9-4627
	NTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT		G,	VIRON	ox 359 357	503) 659- PING COM
	FINAL APPROVAL BY DURHAM PLANNING BOARD.		RIN	• E	, P.O. B NH 033	, FAX: (
	CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER		Ш	CTURA	ROAD ST.	5/67-69
	10'-0"		ENGIN	STRU	5 RAIL	(603) 6 F-MAII ·
	3'-0" 2'-0"	1	E	CIVIL		PHONE:
		6 				
	UNLESS OTHERWISE					
N /== -	SPECIFIED					
ERICAN	I GREEN DS 150 NETTING (OR EQUAL) M AND SEED IN BOTTOM OF DITCH	J	OB: 1	8-()41	
	RIVER STONE MULCH LINED DITCH DETAIL	<i>C</i>	_5	• /	ר ר	
					- H (_



	MATERIAL LOCATION	DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / D REQUIREME
D	INAL FILL : FILL MATERIAL FOR LAYER 'D' TARTS FROM THE TOP OF THE 'C' LAYER TO THE OTTOM OF FLEXIBLE PAVEMENT OR UNPAVED INISHED GRADE ABOVE. NOTE THAT PAVEMENT UBBASE MAY BE PART OF THE 'D' LAYER		N/A	PREPARE PER SITE DESIGN E PAVED INSTALLATIONS MAY MATERIAL AND PREPARATION
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 24" (600 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 ¹ A-1, A-2-4, A-3 OR AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10	
В	EMBEDMENT STONE : FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	NO COMPACTION REC
A	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 ¹ 3, 4	PLATE COMPACT OR ROLL TO SURFACE. ^{2,3}
	E NOTE: E LISTED AASHTO DESIGNATIONS ARE FOR GRADATI	ONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSI	HED, ANGULAR. FOR EXAMP	LE, A SPECIFICATION FOR #4