
# SITE PLAN


for

# TOOMERFS, LLC

19 MAIN STREET & 21 MAIN STREET DURHAM, NH

REVISED 30 NOVEMBER, 2021





# TABLE OF CONTENTS

TITLE	SHEET
EXISTING CONDITIONS PLAN	.E1
HISS SOIL MAP	. E2
PROPOSED SITE PLAN	C-101
GRADING, DRAINAGE, UTILITY & EROSION CONTROL PLAN	C-102
DEMOLITION PLAN	C-103
LANDSCAPING PLAN	L-100
AERIAL PLAN	. AE-1
CONSTRUCTION DETAILS	C-501-C-5

# **OWNER**

TOOMERFS, LLC 37 MAIN STREET UNIT O DURHAM, NH 03824

CIVIL ENGINEER





5 RAILROAD STREET NEWMARKET, NEW HAMPSHIRE (603) 659-4979


# LANDSCAPE ARCHITECT

WOODBURN & COMPANY 103 KENT PLACE NEWMARKET, NEW HAMPSHIRE (603) 659-5949 SURVEYOR

NORWAY PLAINS ASSOCIATES, INC. 2 CONTINENTAL BOULEVARD ROCHESTER, NEW HAMPSHIRE 03867 (603) 335-3948










MAPS SOIL

SHEET E2







# LANDSCAPE NOTES:

- 1. Design is based on drawings by MJS Engineering, P.C. dated November 22, 2021, and may require adjustment due to actual
- The conditions.

  The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site from erosion.
- 3. Erosion Control shall be in place prior to construction.
  4. Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water
- bodies, Wetlands and/or drainage ways prior to any construction.

  5. The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any
- discrepancies or changes in layout and/or grade relationships prior to construction.


  6. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation.

  A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is
- incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.


  7. Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line at a minimum and shall include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction
- materials or portalets within the tree protection area.

  8. This plan is for review purposes only, NOT for Construction. Construction Documents will be provided upon request.
- 9. Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the
- The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction.
   Call DIGSAFE at 1-888-344-7233.
- 11. The Contractor shall procure any required permits prior to construction.
- 12. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.
   13. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or
- construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a contractor is aware of a potential issue and does not bring it to the attention of the landscape architect or owner's
- representative immediately, they may be responsible for the labor and materials associated with correcting the problem.

  14. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in ANSI Z60.1 of the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern
- 15. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern.
- 16. All plants shall be legibly tagged with proper botanical name.
- 17. The Contractor shall guarantee all plants for not less than one year from time of acceptance.
  18. Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
- 19. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.20. All landscaping shall be provided with either of the following
- All landscaping shall be provided with either of the following:
   a. An underground sprinkling system
- b. An outside hose attachment within 150 feet
- If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas.
   The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, and watering of plants. Plants shall be appropriately watered prior to, during and after planting. It is the contractor's responsibility to provide water from off site, should it not be available on site.
- 23. All disturbed areas will be dressed with 6" of topsoil and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost.
- 24. Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native bark not longer than 4" in length and ½" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be black.
- 25. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
- 26. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy.
- 27. Snow shall be stored a minimum of 5' from shrubs and trunks of trees.28. Landscape Architect is not responsible for the means and methods of the contractor



# TREE PLANTING DETAIL




noted above.

Plant L	.ist				
TREES					
Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Am	Amelanchier canadensis	Shadblow Serviceberry	1	2.5-3" cal	B&B
Ar	Acer rubrum 'October Glory'	October Glory Red Maple	2	2.5-3" cal	B&B
Ls	Liquidamb ar styraciflua	American Sweetgum	3	2.5-3" cal	B&B
Pa	Picea abies	Norway Spruce	8	7-8' ht.	B&B
Th	Thuja plicata 'Green Giant'	Green Giant Arborvitae	17	10' ht.	B&B
Ua	Ulmus americana 'Princeton'	Princeton American Elm	6	2.5-3" cal	B&B
Z	Zelkova serrata 'Green Vase'	Green Vase Zelkova	4	2.5-3" cal	B&B



103 Kent Place Newmarket, New Hampshire Phone: 603.659.5949



FINAL APPROVAL BY DURHAM PLANNING BOARD.

CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER

CERTIFIED

DATE

ENGINEERING, P.C.
CIVIL • STRUCTURAL • ENVIRONMENTAL
5 RAILROAD ST., P.O. BOX 359
NEWMARKET, NH 03857
PHONE: (603) 659-4979, FAX: (603) 659-4627

ANDSCAP



JOB: 18-041

L-100



FINAL APPROVAL BY DURHAM PLANNING BOARD.

CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER

SCALE: 1" = 30'

SHEET AE-1

**AERIAL PLAN** 

# CONSTRUCTION SEQUENCING AND EROSION CONTROL NOTES:

THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL THE AREA OF UNSTABILIZED SOIL EXCEED 5 ACRES AT ANY ONE TIME BEFORE THE AREA IS STABILIZED

- AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: 1. IN AREAS TO BE PAVED, BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHDOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION, 2016, ITEM
- NO. 304.1 OR 304.2 HAVE BEEN INSTALLED; 2. IN AREAS NOT TO BE PAVED
- 2.A. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; 2.B. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN
- 2.C. EROSION CONTROL BLANKETS HAVE BEEN INSTALLED IN ACCORDANCE WITH ENV-WQ
- DISTURBED AREAS SHALL BE TEMPORARILY STABILIZED WITHIN 45 DAYS AND PERMANENTLY STABILIZED NO LATER THAN 3 DAYS AFTER FINAL GRADING.

## **EROSION CONTROL PRACTICES:**

- A. INSTALLATION: 1. INSTALL ALL EROSION CONTROLS AS SHOWN ON THE GRADING PLAN, TYPICAL DETAILS, AND IN CONFORMANCE WITH THE EROSION AND SEDIMENT CONTROL NOTES ON THIS PAGE. MANUFACTURER'S SPECIFICATIONS SHALL BE FOLLOWED.
- INSPECTION: INSPECT ALL EROSION CONTROLS WEEKLY AND AFTER EVERY RAIN EVENT OF 0.5 INCHES OR GREATER UNLESS OTHERWISE NOTED.
- TEMPORARY STABILIZATION PRACTICES SHALL BE INSPECTED ONCE PER WEEK DURING CONSTRUCTION UNTIL EXPOSED SURFACES ARE STABILIZED.
- ANY SIGNS OF RILL OR GULLY EROSION SHALL BE IMMEDIATELY REPAIRED. MAINTENANCE 1. MAINTAIN EROSION CONTROLS PER THE TYPICAL DETAILS AND IN CONFORMANCE WITH THE
- EROSION AND SEDIMENT CONTROL NOTES ON THIS PAGE. REMOVAL 1. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE 85% VEGETATIVE
- COVER HAS BEEN ESTABLISHED. 2. AFTER REMOVAL, ALL DISTURBED AREAS SHALL BE REGRADED. FERTILIZED. AND RESEEDED. MONITOR TO ENSURE VEGETATIVE GROWTH IS ESTABLISHED AND REPAIR AS NEEDED UNTIL MINIMUM OF 85% VEGETATIVE COVER IS ESTABLISHED.

## COLD WEATHER SITE STABILIZATION

- A. TO ADEQUATELY PROTECT WATER QUALITY DURING COLD WEATHER AND DURING SPRING RUNOFF, THE ADDITIONAL STABILIZATION TECHNIQUES SPECIFIED IN THIS SECTION SHALL BE EMPLOYED DURING THE PERIOD FROM OCTOBER 15 THROUGH MAY 1.
- B. SUBJECT TO (C), BELOW, THE AREA OF EXPOSED, UNSTABILIZED SOIL SHALL BE LIMITED TO ONE ACRE: AND PROTECTED AGAINST EROSION BY THE METHODS DESCRIBED IN THIS SECTION PRIOR TO
- ANY THAW OR SPRING MELT EVENT THE ALLOWABLE AREA OF EXPOSED SOIL MAY BE INCREASED IF A WINTER CONSTRUCTION PLAN IS DEVELOPED BY A QUALIFIED ENGINEER OR A CPESC SPECIALIST AND SUBMITTED TO
- THE DEPARTMENT FOR APPROVAL AS A REQUEST TO WAIVE THE ONE-ACRE LIMIT. SUBJECT TO (F) AND (G), BELOW, ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR THAT ARE DISTURBED AFTER OCTOBER 15, SHALL BE SEEDED AND COVERED WITH 3 TO 4 TONS OF HAY OR STRAW MULCH PER ACRE SECURED WITH ANCHORED NETTING OR TACKIFIER OR WITH AT LEAST 2 INCHES OF EROSION CONTROL MIX MEETING THE CRITERIA OF
- SUBJECT TO (F) AND (G), BELOW, ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF 15% OR GREATER THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR THAT ARE DISTURBED AFTER OCTOBER 15, SHALL BE SEEDED AND COVERED WITH A PROPERLY INSTALLED AND ANCHORED EROSION CONTROL BLANKET OR WITH AT LEAST 4
- INCHES OF EROSION CONTROL MIX MEETING THE CRITERIA OF ENV-WQ 1506.05(B). ANCHORED HAY MULCH OR EROSION CONTROL MIX THAT MEETS THE CRITERIA OF ENV-WQ 1506.05(B) SHALL NOT BE INSTALLED OVER SNOW GREATER THAN ONE INCH IN DEPTH.
- EROSION CONTROL BLANKETS SHALL NOT BE INSTALLED OVER SNOW GREATER THAN ONE INCH IN DEPTH OR ON FROZEN GROUND. H. ALL PROPOSED STABILIZATION IN ACCORDANCE WITH (D) OR (E), ABOVE, SHALL BE
- COMPLETED WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAN 5 DAYS.
- ALL DITCHES OR SWALES THAT DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15, OR THAT ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED 'EMPORARILY WITH STONE OR FROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS, AS DETERMINED BY THE OWNER'S ENGINEERING CONSULTANT.
- AFTER OCTOBER 15, INCOMPLETE ROAD OR PARKING AREAS WHERE ACTIVE CONSTRUCTION OF THE ROAD OR PARKING AREA HAS STOPPED FOR THE WINTER SEASON SHALL BE PROTECTED. WITH A MINIMUM 3-INCH LAYER OF BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHDOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION 2016, TABLE 304-1, ITEM NO. 304.1, 304.2, OR 304.3, AVAILABLE AS NOTED IN APPENDIX B

## TEMPORARY VEGETATION

- INSTALL EROSION AND SEDIMENT CONTROL MEASURES AS SPECIFIED ABOVE. ENSURE RUNOFF IS DIVERTED FROM SEEDED AREA.
- ON SLOPES OF 4:1 OR STEEPER, CREATE HORIZONTAL GROOVES PERPENDICULAR TO THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE RUNOFF. B. SEED BED PREPARATION
- REMOVE STONES AND TRASH FROM AREA TO BE SEEDED. COMPACTED SOIL SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE APPLYING
- APPLY FERTILIZER AT A RATE OF 600 LBS PER ACRE OF 10-10-10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS
- 1. SEED PER THE FOLLOWING RECOMMENDATIONS

SEASON	APPLICATION DATE	MIXTURE TYPE	QUANTITY (lb./Ac.)
EARLY SPRING	NO LATER THAN 5/15	OATS	80
LATE SPRING/ FALL	4/1 TO 6/1 & 8/15 TO 9/15	PERENNIAL RYE	30
EARLY SPRING/ FALL	4/1 TO 5/15 & 8/15 TO 9/15	ANNUAL RYE	40
FALL	8/15 TO 9/15	WINTER RYE	112

- 2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL
- SURFACE. SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING. TEMPORARY SEEDING SHALL OCCUR PRIOR TO SEPTEMBER 15TH IN THE YEAR IN WHICH
- THE AREA BEING SEEDED WAS DISTURBED. 4. AREAS SEEDED BETWEEN MAY 15TH AND AUGUST 15TH SHALL BE COVERED WITH HAY OR STRAW MULCH MEETING THE FOLLOWING CRITERIA: 4.A. HAY AND STRAW MULCHES SHALL BE ANCHORED WITH MULCH NETTING OR TACKIFIER SO THAT THEY ARE NOT BLOWN AWAY BY WIND OR WASHED AWAY BY FLOWING
- 4.B. MULCH MATERIALS SHALL BE SELECTED BASED UPON SOILS, SLOPE, FLOW CONDITIONS. AND TIME OF YEAR:
- 4.C. HAY OR STRAW MULCH SHALL BE APPLIED AT A RATE OF 1.5 TO 2 TONS PER ACRE, EQUIVALENT TO 70 TO 90 POUNDS PER 1,000 SQUARE FEET; IF VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA IS NOT ACHIEVED PRIOR TO OCTOBER 15TH, ONE OR MORE ADDITIONAL EROSION CONTROL
- METHODS SHALL BE IMPLEMENTED. MAINTENANCE 1. TEMPORARY SEEDING SHOULD BE INSPECTED WEEKLY AND AFTER ANY RAINFALL EXCEEDING 1/2 INCH IN 24 HOURS ON ACTIVE CONSTRUCTION SITES. TEMPORARY SEEDING SHOULD ALSO BE INSPECTED JUST PRIOR TO SEPTEMBER 15, TO ASCERTAIN WHETHER ADDITIONAL SEEDING IS REQUIRED TO PROVIDE STABILIZATION OVER THE WINTER PERIOD.
- BASED ON INSPECTION, AREAS SHOULD BE RESEEDED TO ACHIEVE FULL STABILIZATION OF EXPOSED SOILS. IF IT IS TOO LATE IN THE PLANTING SEASON TO APPLY ADDITIONAL SEED, THEN OTHER TEMPORARY STABILIZATION MEASURES SHOULD BE IMPLEMENTED. AT A MINIMUM, 85% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION.
- 4. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHOULD BE MADE AND AREAS SHOULD BE RESEEDED, WITH OTHER TEMPORARY MEASURES (E.G., MULCH) USED TO PROVIDE EROSION PROTECTION DURING THE PERIOD OF VEGETATION ESTABLISHMENT.

## SITE PREPARATION

- REFER TO SITE PREPARATION FOR TEMPORARY SEEDING.
- B. SEED BED PREPARATION REFER TO SEED BED PREPARATION FOR TEMPORARY SEEDING IN CONJUNCTION WITH THESE
- WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OPERATION SHOULD BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM. FINE SEEDBED IS PREPARED. ALL BUT CLAY OR SILTY SOILS AND COARSE SANDS SHOULD BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE.
- REMOVE FROM THE SURFACE ALL STONES 2 INCHES OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, CONCRETE, CLODS, LUMPS, TRASH OR OTHER UNSUITABLE MATERIAL.
- INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED; THE AREA MUST BE TILLED AND FIRMED AS ABOVE. WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A
- DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED. APPLY FERTILIZER AT A RATE OF 600 LBS PER ACRE OF 10-10-10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE.
- C. SEEDING UNLESS OTHERWISE NOTED, GRASS SEED MIXTURE 'C' SHALL BE APPLIED AT THE SPECIFIED
- RATE AS NOTED IN THE 'SEED MIXTURES FOR PERMANENT VEGETATION' TABLE. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM 1/4 TO 1/2 INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE.
- SEEDING OPERATIONS SHOULD BE ON THE CONTOUR. WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS USED, THE SEEDBED SHOULD BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR LIGHT DRAG
- WHEN HYDROSEEDING (HYDRAULIC APPLICATION), PREPARE THE SEEDBED AS SPECIFIED ABOVE OR BY HAND RAKING TO LOOSEN AND SMOOTH THE SOIL AND TO REMOVE SURFACE STONES LARGER THAN 2 INCHES IN DIAMETER. SLOPES MUST BE NO STEEPER THAN 2 TO 1
- LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED. THE USE OF FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). BETTER PROTECTION IS GAINED BY USING STRAW MULCH AND HOLDING IT WITH ADHESIVE MATERIALS OR 500 POUNDS PER ACRE OF WOOD FIBER MULCH.
- SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING TEMPORARY SEEDING SHALL OCCUR PRIOR TO SEPTEMBER 15TH IN THE YEAR IN WHICH THE AREA BEING SEEDED WAS DISTURBED.
- STRAW MULCH MEETING THE FOLLOWING CRITERIA: 9.A. HAY AND STRAW MULCHES SHALL BE ANCHORED WITH MULCH NETTING OR TACKIFIER SO THAT THEY ARE NOT BLOWN AWAY BY WIND OR WASHED AWAY BY FLOWING WATER: 9.A. MULCH MATERIALS SHALL BE SELECTED BASED UPON SOILS, SLOPE, FLOW CONDITIONS, AND TIME OF YEAR;

AREAS SEEDED BETWEEN MAY 15TH AND AUGUST 15TH SHALL BE COVERED WITH HAY OR

- 9.B. HAY OR STRAW MULCH SHALL BE APPLIED AT A RATE OF 1.5 TO 2 TONS PER ACRE, EQUIVALENT TO 70 TO 90 POUNDS PER 1,000 SQUARE FEET; 10. IF VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA IS NOT ACHIEVED PRIOR TO OCTOBER 15TH, ONE OR MORE ADDITIONAL EROSION CONTROL
- METHODS SHALL BE IMPLEMENTED. MAINTENANCE PERMANENTLY SEEDED AREAS SHOULD BE INSPECTED MONTHLY.
  - MOW SEEDED AREAS AS NECESSARY
  - BASED ON INSPECTION, AREAS SHOULD BE REPAIRED AND/OR RESEEDED TO ENSURE 85% OF THE SOIL SURFACE IS COVERED BY VEGETATION.

## MULCHING & EROSION CONTROL MATTING

- 1. APPLY PRIOR TO A STORM EVENT. CLOSELY MONITOR THE WEATHER TO HAVE ADEQUATE WARNING OF SIGNIFICANT STORMS.
- 2. MULCHING WITHIN A SPECIFIED TIME PERIOD FROM ORIGINAL SOIL EXPOSURE 2.A. WITHIN 100 FEET OF WETLANDS THE TIME PERIOD SHOULD BE NO GREATER THAN 7
- 2.B. IN OTHER AREAS IT SHALL BE NO GREATER THAN 14 DAYS. 3. MULCH MATERIALS SHALL BE SELECTED BASED UPON SOILS, FLOW CONDITIONS, AND TIME OF YEAR.
- B. TEMPORARY MULCHING 1. HAY OR STRAW MULCHES
  - 1.A. ORGANIC MULCHES INCLUDING HAY AND STRAW SHALL BE AIR-DRIED, FREE OF UNDESIRABLE SEEDS AND COARSE MATERIALS.
  - 1.B. APPLICATION RATE SHALL BE 2 BALES/1,000 SF (70-90 POUNDS) OR 1.5-2.0 TONS/ACRE TO COVER 75-90% OF THE GROUND.
  - 1.C. ANCHORING SHALL BE ONE OF THE FOLLOWING
  - 1.C.1. NETTING SHALL BE JUTE, WOOD FIBER, OR BIODEGRADABLE PLASTIC NETTING INSTALLED PER MANUFACTURER'S SPECIFICATIONS. 1.C.2. TACKIFIER: APPLY POLYMER OR ORGANIC TACKIFIER TO ANCHOR HAY OR STRAW MULCH APPLY PER MANUFACTURER'S SPECIFICATIONS TYPICAL APPLICATION RATES ARE 40-60 LBS/ACRE FOR POLYMER MATERIAL AND 80-120 LBS/ACRE
  - FOR ORGANIC LIQUID. 1.D. WINTER APPLICATION: APPLY TO A DEPTH OF 4 INCHES OR DOUBLE THE ABOVE LISTED APPLICATION RATE. NOTE THAT IF SEEDING IS NECESSARY, MULCH WILL NEED TO BE REMOVED AND THE AREA SEEDED AND MULCHED IN THE SPRING.
  - 1.E.1. INSPECT PERIODICALLY AND AFTER RAIN STORMS FOR RILLS OR DISPLACEMENT OF MULCH. REPAIR AS NECESSARY. CONTINUE INSPECTIONS UNTIL 85% VEGETATIVE COVER IS ESTABLISHED.
  - 2. EROSION CONTROL BLANKET OR MATTING 2.A. REFER TO PLANS FOR TYPICAL EROSION CONTROL MATTING DETAIL. INSTALL PER MANUFACTURERS SPECIFICATIONS.
  - 2.B. APPLICATION AND TIMING 2.B.1. DURING THE GROWING SEASON (APRIL 15 - SEPTEMBER 15) USE ON THE BASE OF GRASSED WATERWAYS, STEEP SLOPES (15% OR GREATER), ANY
  - DISTURBED SOIL WITHIN 100 FEET OF LAKES, STREAMS, AND WETLANDS. DURING THE LATE FALL AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED ABOVE USE ON SIDE SLOPES OF GRASSED WATERWAYS AND MODERATE SLOPES (GREATER THAN 8%).
- MAINTENANCE 3.A. INSPECT PERIODICALLY AND BEFORE AND AFTER STORM EVENTS TO ENSURE CONTACT WITH THE SOIL UNTIL 85% VEGETATIVE COVER IS ESTABLISHED. REPAIR AND RESTAPLE
- 1. WOOD CHIPS OR GROUND BARK 1.A. APPLY TO A THICKNESS OF 2 TO 6 INCHES. APPLICATION RATES ARE 10-20
- TONS/ACRE OR 460-920 POUNDS/1,000 SF. 1.B. MAINTENANCE: INSPECT ANNUALLY AND AFTER RAIN EVENTS OF 2.5 INCHES OR MORE IN A 24 HOUR PERIOD. REPAIR/REPLACE AS NECESSARY.
- 2. EROSION CONTROL MIX 2.A. SHALL BE PLACED AT A THICKNESS OF 2 INCHES OR MORE FOR MULCHING. 2.B. COMPOSITION OF THE MIX SHALL BE AS FOLLOWS: 2.B.1. ORGANIC MATTER CONTENT SHALL BE BETWEEN 25-65% DRY WEIGHT BASIS.
  - 2.B.2. PARTICLE SIZE BY WEIGHT SHOULD BE 100% PASSING THE 3" SCREEN, 90-100% PASSING THE 1" SCREEN, 70-100% PASSING THE 0.75 INCH SCREEN, AND 30-75% PASSING THE 0.25 INCH SCREEN.
  - 2.B.3. THE ORGANIC PORTION SHALL BE ELONGATED AND FIBROUS SUCH AS FROM SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR EQUIVALENT MANUFACTURED PRODUCTS. IT SHALL NOT CONTAIN WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS.
- THE MIX SHALL NOT CONTAIN SILTS, CLAYS, OR FINE SANDS. 2.B.5. SOLUBLE SALTS CONTENT SHALL BE < 4.0MMHOS/CM AND A pH OF 5.0-8.0, 2.C. PLACEMENT OF BERM 2.C.1. PLACE BERM ALONG A LEVEL CONTOUR. BERM MUST BE A MINIMUM OF 12"
- HIGH ON THE UPHILL SIDE AND 2 FEET WIDE. UPSLOPE AREA MUST HAVE A SLOPE OF LESS THAN 5%. 2.D. MAINTENANCE: INSPECT PERIODICALLY AND AUGMENT AS NEEDED TO MAINTAIN INITIAL THICKNESS. REPLACE IF NO LONGER FUNCTIONING AS INTENDED.

# FINAL APPROVAL BY DURHAM PLANNING BOARD. CERTIFIED BY MICHAEL BEHRENDT. TOWN PLANNER

- GENERAL STOCKPILES MUST BE LOCATED 50 FEET FROM DITCHES AND CULVERT INLETS.
- PROTECTION OF STOCKPILES PROTECT SOIL AND AGGREGATE STOCKPILES WITH TEMPORARY PERIMETER
- SEDIMENT BARRIER SUCH AS SILT FENCE OR SILT SOCK. COVER ACTIVE STOCKPILES WITH ANCHORED PROTECTIVE COVERING PRIOR
- TO EXPECTED STORM EVENTS INACTIVE STOCKPILES SHALL BE COVERED WITH ANCHORED TARPS OR TEMPORARILY SEEDED AND MULCHED PER THE TEMPORARY VEGETATION AND MULCHING NOTES ON THIS PAGE.
- DUST CONTROL


  A. DUST SHALL BE CONTROLLED ON SITE DURING CONSTRUCTION BY IMPLEMENTING THE
- FOLLOWING DUST CONTROL MEASURES MULCHING AND VEGETATIVE COVER TO REDUCE DUST.
- MECHANICAL SWEEPERS AND FINE WATER SPRAYS COVER SURFACES WITH CRUSHED STONE OR COARSE GRAVEL.

4. STOCKPILES THAT ARE A SOURCE OF DUST SHALL BE COVERED.

SEED MIXTURE SELECTION BASED ON SOIL TYPE SOIL DRAINAGE USE MODERATELY SEEDING DROUGHTY MIXTURE WELL DRAINED DRAINED GOOD STEEP CUTS AND FILLS, BORROW AND POOR GOOD FAIR POOR GOOD **EXCELLENT** DISPOSAL AREAS FAIR EXCELLENT **EXCELLENT** WATERWAYS, EMERGENCY SPILLWAYS, AND GOOD GOOD OTHER CHANNELS WITH FLOWING WATER. GOOD EXCELLENT EXCELLENT LIGHTLY USED PARKING LOTS, ODD AREAS, GOOD GOOD GOOD UNUSED LANDS, AND LOW INTENSITY USE GOOD GOOD RECREATION SITES. GOOD EXCELLENT **EXCELLENT** PLAY AREAS AND ATHLETIC FIELDS. (TOPSOIL **EXCELLENT** EXCELLENT FAIR **EXCELLENT EXCELLENT** IS ESSENTIAL FOR GOOD TURF.)

NOTE: POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREAS AND ATHLETIC FIELDS.

SEED MIXTURES FOR PERMANENT VEGETATION						
MIXTURE	SPECIES	POUNDS PER ACRE	POUNDS PER 1,000 SF			
А	TALL FESCUE CREEPING RED FESCUE <u>REDTOP</u> TOTAL	20 20 <u>2</u> 42	0.45 0.45 <u>0.05</u> <i>0.95</i>			
В	TALL FESCUE CREEPING RED FESCUE CROWN VETCH OR FLATPEA TOTAL	15 10 15 - 30 40 <i>OR</i> 55	0.35 0.25 0.35 - 0.75 0.95 OR 1.35			
С	TALL FESCUE CREEPING RED FESCUE BIRDSFOOT TREFOIL TOTAL	20 20 <u>8</u> 48	0.45 0.45 <u>0.20</u> 1.10			
D	TALL FESCUE <u>FLATPEA</u> TOTAL	20 <u>30</u> 50	0.45 <u>0.75</u> 1.20			
E	CREPPING RED FESCUE KENTUCKY BLUEGRASS TOTAL	50 <u>50</u> 100	1.15 <u>1.15</u> 2.30			
F	TALL FESCUE	150	3.60			



- 1. SEDIMENT FILTER TRAP SHALL BE ACF REGULAR FLOW
- SILTSACK OR APPROVED EQUAL. 2. FILTERS SHALL BE INSPECTED AFTER EVERY RAIN EVENT OF 0.25" OR GREATER AND SEDIMENTS SHALL BE REMOVED FROM TRAP WHEN SEDIMENT HAS REACHED TWO THIRDS OF THE DEPTH OF THE TRAP, OR IF PONDING OF WATER AT SURFACE BEGINS TO OCCUR. DO NOT PUNCTURE FILTER

# CATCH BASIN SEDIMENT FILTER DETAIL

TRAP TO MITIGATE PONDING.

## **CONSTRUCTION SEQUENCING:**

- SCHEDULE A PRE-CONSTRUCTION MEETING WITH TOWN OFFICIALS, OWNER, AND CONTRACTORS IF REQUIRED BY THE
- CONDITIONS OF APPROVAL PRIOR TO BEGINNING CONSTRUCTION CONTACT DIG-SAFE, INDIVIDUAL UTILITIES, AND CITY DEPARTMENTS TO GET ALL UTILITIES MARKED PRIOR TO START
- INSTALL PERIMETER CONTROLS PRIOR TO ALL EARTHMOVING WORK. CLEAR/GRUB ONLY WITHIN THE LIMITS OF GRADING AS SHOWN ON THE PLANS. REMOVE ORGANICS ONLY FROM
- THOSÉ AREAS THAT CAN BE WORKED AND STABILIZED WITHIN 45 DAYS OF REMOVAL. THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES..
- 6. CLEAR/GRUB
- A. STUMPS MAY BE DISPOSED ON-SITE IN ACCORDANCE WITH LOCAL AND STATE REGULATIONS. STOCKPILES
- A. STOCKPILE LOAM FOR RE-USE AS NEEDED. B. TEMPORARILY STABILIZE LOAM STOCKPILES WITH:
- WINTER RYE GRASS- PRIOR TO SEPTEMBER 15TH MULCH- FROM SEPTEMBER 15TH TO MAY 1ST
- CONSTRUCT AND STABILIZE ALL TEMPORARY AND PERMANENT SEDIMENT, EROSION, AND STORMWATER CONTROL FACILITIES AS LISTED ABOVE. THESE SHALL BE INSTALLED BEFORE ANY MAJOR EARTH MOVING OPERATIONS.
- RUNOFF MUST BE DIRECTED TO TEMPORARY PRACTICES UNTIL STORMWATER BMPS ARE STABILIZED. REFER TO SEDIMENT TRAP DETAIL.
- C. STORMWATER PONDS, INFILTRATION BASINS, AND SWALES MUST BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM D. REFER TO INDIVIDUAL DETAILS FOR CONSTRUCTION REQUIREMENTS.
- 10. PARKING LOT CONSTRUCTION A. CUTS AND FILLS: . CONSTRUCT IN LOCATIONS AND TO GRADES AS SHOWN ON THE PLANS.
  - 2. FILLS: A. PLACE MAXIMUM 12" LIFTS AND COMPACT TO 95% MAXIMUM DRY DENSITY. B. ALL MATERIAL BASED ON PROCTOR TEST SHALL BE FREE OF DELETERIOUS MATERIALS SUCH AS LOAM, STUMPS, BRUSH, AND ROCKS LARGER THAN 3/4 THE DEPTH OF THE LIFT BEING PLACED.
- LOAM AND SEED SLOPES WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE. B. DRAINAGE AND UTILITY STRUCTURES INSTALL AS SHOWN IN ACCORDANCE WITH DETAILS AND DRY STABILIZE.
- C. BASE MATERIALS: BANK RUN AND CRUSHED GRAVEL SHALL BE PLACED IN 6" LIFTS AND COMPACTED TO 95% MAXIMUM DRY DENSITY TO THE DEPTHS SPECIFIED IN THE PARKING LOTS CROSS-SECTION DETAILS.
- STABILIZE ALL PARKING AREAS WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE. 11. INSPECT, MAINTAIN, AND IF NECESSARY, REPAIR ALL EROSION AND SEDIMENT CONTROL MEASURES AS STATED IN EROSION CONTROL NOTES ON THIS SHEET.
- 12. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES ONCE INITIAL GROWTH IS ESTABLISHED.

CONSTRUCTION NOTES

WOVEN WIRE FENCE. IF REQUIRED

2. FILTER CLOTH TO BE FASTENED

FOLDED AND STAPLED.

RECOMMENDATIONS.

SECURELY TO WOVEN WIRE FENCE


WITH TIES SPACED EVERY 24" AT

TOP, MID SECTION, AND BOTTOM.

FENCE IF INSTALLED PER MANUFACTURER'S

FOR SEDIMENT FENCE

- NO FUEL SHALL BE STORED ON SITE DURING CONSTRUCTION.
- 2. DURING CONSTRUCTION DUST SHALL BE PREVENTED FROM BECOMING A SAFETY OR HEALTH HAZARD BY THE IMPLEMENTATION OF ACCEPTED CONTROL METHODS SUCH AS WATERING. 3. ALL CONSTRUCTION MATERIALS THAT ARE SPILLED OR DEPOSITED ON THE PUBLIC ROADWAYS
- SHALL BE REMOVED BY THE CONTRACTOR. 4. DO NOT BEGIN CONSTRUCTION UNTIL ALL LOCAL, STATE, AND FEDERAL PERMITS HAVE BEEN
- APPLIED FOR AND RECEIVED. 5. THE GENERAL CONTRACTOR IS RESPONSIBLE TO VERIFY ALL DIMENSIONS, ELEVATIONS AND CONDITIONS AT THE SITE. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN ENGINEER BEFORE PROCEEDING WITH THE AFFECTED PART OF THE WORK.



EMBED FILTER CLOTH

MIN. 8" INTO GROUND

SHALL BE CONSIDERED AN ACCEPTABLE EQUAL TO SEDIMENT SEDIMENT FENCE


> -SEDIMENT FENCE **HAYBALES**

SEDIMENT FENCE POCKE

SHEET C501

DETAIL


CONSTRUCTION



- 1. CONSTRUCTION TO BE IN ACCORDANCE WITH PSNH CONSTRUCTION STANDARDS FOR NEW ELECTRICAL SERVICE WORK BY CONTRACTORS, MOST RECENT EDITION.

  2. SELECT SAND BACKFILL SHALL CONSIST OF A FINE GRANULAR MATERIAL OF WHICH 100% SHALL PASS THROUGH A 1/4" SIEVE. EXCEPT NATURALLY OCCURING SMOOTH ROUND PEBBLES NO GREATER THAN 3/8" IN DIAMETER ARE PERMITTED AS LONG AS THEIR TOTAL VOLUME PER CUBIC FOOT OF SAND DOES NOT EXCEED 1%. THE SAND SHALL BE COMPLETELY FREE OF FROZEN LUMPS, ROCKS, STONES, DEBRIS AND RUBBISH. BACKFILL SHALL BE THOROUGHLY COMPACTED IN
- 3. CONDUIT SIZES TO BE 5" 3-PHASE PRIMARY AND 4" 3-PHASE SECONDARY. ALL CONDUIT SIZES TO BE VERIFIED BY PSNH.
- 4. ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND WHERE APPLICABLE THE NATIONAL ELECTRIC CODE.

# TELEPHONE & ELECTRIC TRENCH




- SECTION A-A'
- 1. CONCRETE MINIMUM 5,000 PSI AFTER 28 DAYS. 2. CONDUIT, ANCHOR BOLTS AND TEMPLATE SUPPLIED BY OTHERS.


D = 12"

- LIGHT POLE BASE SIZE IS TO BE SPECIFIED BY A QUALIFIED ENGINEER. 4. TYPICAL BASE DIAMETERS 'D' INCLUDE: 12", 18", 24", AND 30".
- TYPICAL BASE HEIGHTS 'H' RANGE FROM 4' TO 7'.
- OTHER BASE SIZES AVAILABLE UPON REQUEST. 7. BASE SHALL EXTEND 18"-24" ABOVE GRADE.

## LIGHT POLE BASE DETAIL



PARKING LOT END DETAIL



TYPICAL SIGN DETAIL

NOTES:

1. SEE PLANS FOR SIGN PLACEMENT.




# Fixtures 962TCGT (Clow Top)

# LITHONIA DSX0-LED POLE MOUNTED LIGHT FIXTURE


GUARD RAIL DETAIL


NOTE: LIGHT FIXTURE TO BE MOUNTED ON 16' HIGH POLE.

# STERNBERG LIGHTING 962TC-XRLED GLEN ELLYN SERIES POLE MOUNTED LIGHT FIXTURE



1. BACKFILL AROUND BASINS IN 12" LIFTS WITH GRAVEL COMPACTED TO 95% MAXIMUM DRY DENSITY.





1. ALL MATERIAL AND INSTALLATION METHODS SHALL CONFORM W/NHDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, SECTION 606-GUARDRAIL.

REFER TO SHEET C102 FOR LOCATION AND GRADING AROUND GUARD RAIL. 3. FACE OF GUARDRAIL SHOULD BE NO CLOSER THAN 6'-3" FROM THE FACE OF THE INSTALLED RETAINING WALL OR 2'-6" FROM SLOPES GREATER THAN 5%.

TYPICAL END SECTION


FINAL APPROVAL BY DURHAM PLANNING BOARD. CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER

TIMBER BRIDGE DESIGN, CONSTRUCTION, INSPECTION, AND MAINTENANCE PUBLISHED BY THE UNITED STATES DEPARTMENT OF

SHEET C503

CONSTRUCTION DETAILS

REFERENCE: AGRICULTURE FOREST SERVICE.



STORMTECH CHAMBER SPECIFICATIONS

- 1. CHAMBERS SHALL BE STORMTECH MC-4500.
- 2. CHAMBERS SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS.
- 3. CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORT PANELS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- 4. THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
- 5. CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS"
- 6. CHAMBERS SHALL BE DESIGNED AND ALLOWABLE LOADS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- 7. ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. THE CHAMBER MANUFACTURER SHALL SUBMIT THE FOLLOWING UPON REQUEST TO THE SITE DESIGN ENGINEER FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE:
  - A STRUCTURAL EVALUATION SEALED BY A REGISTERED PROFESSIONAL ENGINEER THAT DEMONSTRATES THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY AASHTO FOR THERMOPLASTIC PIPE.
  - A STRUCTURAL EVALUATION SEALED BY A REGISTERED PROFESSIONAL ENGINEER THAT DEMONSTRATES THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET. THE 50 YEAR CREEP MODULUS DATA SPECIFIED IN ASTM F2418 MUST BE USED AS PART OF THE AASHTO STRUCTURAL EVALUATION TO VERIFY LONG-TERM PERFORMANCE.
  - STRUCTURAL CROSS SECTION DETAIL ON WHICH THE STRUCTURAL EVALUATION IS
- 8. CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING

## IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF MC-4500 CHAMBER SYSTEM

- STORMTECH MC-4500 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
- STORMTECH MC-4500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
- CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR EXCAVATOR SITUATED OVER THE CHAMBERS.
- STORMTECH RECOMMENDS 3 BACKFILL METHODS:
- STONESHOOTER LOCATED OFF THE CHAMBER BED. BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
- BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- MAINTAIN MINIMUM 9" (230 mm) SPACING BETWEEN THE CHAMBER ROWS.
- 7. INLET AND OUTLET MANIFOLDS MUST BE INSERTED A MINIMUM OF 12" (300 mm) INTO CHAMBER END CAPS.
- EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE MEETING THE AASHTO M43 DESIGNATION OF #3 OR #4.
- STONE SHALL BE BROUGHT UP EVENLY AROUND CHAMBERS SO AS NOT TO DISTORT THE CHAMBER SHAPE. STONE DEPTHS SHOULD NEVER DIFFER BY MORE THAN 12" (300 mm) BETWEEN ADJACENT CHAMBER ROWS.
- 10. STONE MUST BE PLACED ON THE TOP CENTER OF THE CHAMBER TO ANCHOR THE CHAMBERS IN PLACE AND
- 11. THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIAL BEARING
- CAPACITIES TO THE SITE DESIGN ENGINEER.
- 12. ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.

## NOTES FOR CONSTRUCTION EQUIPMENT

- STORMTECH MC-4500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
- THE USE OF EQUIPMENT OVER MC-4500 CHAMBERS IS LIMITED: NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
  - NO RUBBER TIRED LOADER, DUMP TRUCK, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE". • WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH MC-3500/MC-4500
- FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.

USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY USING THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.

CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT.


> FINAL APPROVAL BY DURHAM PLANNING BOARD. CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER

SHEET C504

DETAIL

CONSTRUCTION

## ENTRY DRIVEWAY CROSS SECTION SCALE: 1"=2'



PARKING ISLAND CROSS SECTION

FINAL APPROVAL BY DURHAM PLANNING BOARD. CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER

CONSTRUCTION DETAILS

