

SITE PLAN

for
TOOMERFS, LLC
19 MAIN STREET & 21 MAIN STREET
DURHAM, NH
REVISED FEBRUARY 02, 2021






TABLE OF CONTENTS

| TITLE | SHEET |
|--|-------------|
| EXISTING CONDITIONS PLAN | E1 |
| PROPOSED SITE PLAN | C-101 |
| GRADING, DRAINAGE, UTILITY & EROSION CONTROL PLAN | C-102 |
| DEMOLITION PLAN | C-103 |
| LANDSCAPING PLAN | L1 |
| LIGHTING PLAN | LT1 |
| CONSTRUCTION DETAILS | C-501-C-505 |

OWNER

TOOMERFS, LLC
37 MAIN STREET
UNIT 0
DURHAM, NH 03824

CIVIL ENGINEER




LANDSCAPE ARCHITECT

WOODBURN & COMPANY
103 KENT PLACE
NEWMARKET, NEW HAMPSHIRE
(603) 659-5949


SURVEYOR

NORWAY PLAINS ASSOCIATES, INC.
2 CONTINENTAL BOULEVARD
ROCHESTER, NEW HAMPSHIRE
03867 (603) 335-3948

| NO. | REVISIONS | DATE | INT. |
|-----|---------------------------------------|----------|------|
| 1 | DRAINAGE UPDATES | 02/02/21 | AW5 |
| 0 | INITIAL ALTERNATE ENTRANCE SUBMISSION | 01/05/21 | AW5 |



reserved registry of deeds




NOTES:

1. Total parcel area: Map 5, Lots 1-9,1-10,1-15,1-16 3.2 acres
2. The parcel is zoned Church Hill Dirstirct. Tax map 5 Lots 1-9 & 1-10 are within the historic overlay district.
3. Minimum lot requirements: lot size = 5000 SF,
4. Building setbacks:
Front = 15' (all Streets)
Side = 5'
Rear = 15'
Maximum building height: 30'
Maximum Impervious Surface Ratio 80%
6. The lots are serviced by the municipal water and sewer system.
7. The proposed lot is not located within the 100 year flood zone as shown on the flood insurance rate map dated 09/30/15 community panel 33017c0318e.



Tax Map & Lot Number
5-1-9,1-10,1-15,1-16
OWNER OF RECORD:
TOOMERFS, LLC
37 MAIN STREET, UNIT 0
DURHAM, NH.

existing features plan
19-21 main street
durham, strafford county, nh
for: Toomerfs, LLC

1"=40' August, 2019




FILE NO.#
PLAN NO.#
DWG. NO.#
F.B. NO. #



LOCATION: 5 MILL ROAD
TM 5-1-1
COLONIAL DURHAM ASSOCIATES
7 MILL ROAD, UNIT 1
DURHAM, NH
SCRD: 3747/822
YEAR BUILT: 1974

LOCUS MAP
NTS



LOCATION: 8 CHESLEY DRIVE
TM 6-7-59
ANDERSON WILLIAMS GROUP, LLC
8 CHESLEY DRIVE
DURHAM, NH
SCRD: 3498/629
YEAR BUILT: 1959

EXISTING SINGLE FAMILY HOME


LOCATION: 5 SMITH PARK LANE
TM 5-1-13
MICHAEL F. URSO & SANDRA A. CEPONIS
421 HILLCREST LANE
LOMBARD, IL
SCRD: 3747/822
YEAR BUILT: 1963

LOCATION: 3 SMITH PARK LANE
TM 5-1-12
WILLIAM F. HALL REV. TRUST
3 SMITH PARK LANE
DURHAM, NH
SCRD: 3635/309
YEAR BUILT: 1895

EXISTING SINGLE FAMILY HOME AND ACCESSORY APARTMENT

LOCATION: 17 MAIN STREET
TM 5-2-8
DURHAM COMMUNITY CHURCH
17 MAIN STREET
DURHAM, NH
SCRD: 999/999
YEAR BUILT: 1900

LOCATION: 1 PARK COURT
TM 4-54-2
ST GEORGE'S EPISCOPAL CHURCH
1 PARK COURT
DURHAM, NH
SCRD: 595/474
YEAR BUILT: 1952
YEAR BUILT: 1850



GENERAL NOTES:

- OWNER OF RECORD:
TOOMERFS, LLC
21 MAIN STREET
DURHAM, NEW HAMPSHIRE 03824
S.C.R.D. BOOK 4486, PAGE 213

OWNER OF RECORD:
TOOMERFS, LLC
19 MAIN STREET
DURHAM, NEW HAMPSHIRE 03824
S.C.R.D. BOOK 4486, PAGE 213

OWNER OF RECORD:
TOOMERFS, LLC
19A/B MAIN STREET
DURHAM, NEW HAMPSHIRE 03824
S.C.R.D. BOOK 4486, PAGE 213

OWNER OF RECORD:
TOOMERFS, LLC
RED TOWER
DURHAM, NEW HAMPSHIRE 03824
S.C.R.D. BOOK 4486, PAGE 213
- LOT AREA: 3.26 ACRES (142,005 S.F.)
- REFERENCE PLANS:
A. EXISTING FEATURES: PLAN MAIN STREET AKA NH ROUTE 108 AND COWELL DRIVE, DURHAM STRAFFORD COUNTY, NH PREPARED FOR TOOMERFS, LLC, PREPARED BY NORWAY PLANS ASSOCIATES, INC. DATED AUGUST, 2018.
- VERTICAL DATUM IS ASSUMED.
- IMPERVIOUS SURFACE RATIO:
EXISTING = 19.3% (27,398 S.F.)
PROPOSED = 52.4% (47,443 S.F.)
- ALL OUTSIDE CONSTRUCTION RELATED ACTIVITY RELATED TO THE DEVELOPMENT OF THIS SITE IS RESTRICTED TO THE HOURS OF 7:00 A.M. TO 6:00 P.M. MONDAY THROUGH FRIDAY AND 8:00 A.M. TO 3:00 P.M. SATURDAY.
- FOR MORE INFORMATION ABOUT THIS SITE PLAN, OR TO SEE THE COMPLETE PLAN SET, CONTACT THE TOWN OF DURHAM PLANNING DEPARTMENT, 8 NEWMARKET ROAD, DURHAM, NH 03824. (603) 868-8064.

- ALL EXTERIOR LIGHTING MUST BE FULLY SHIELDED AND NOT PROJECT GLARE TOWARD ANY ABUTTING PROPERTIES.
- ACCESS INTO THE SITE FOR FIRE APPARATUS SHALL BE MAINTAINED AT ALL TIMES DURING THE CONSTRUCTION PROCESS. PLEASE CONTACT THE FIRE DEPARTMENT AT 868-5531 WITH ANY QUESTIONS ABOUT ACCESS REQUIREMENTS.
- SNOW SHALL NOT BE PUSHED AGAINST TREES OR SHRUBS IN ANY MANNER THAT COULD DAMAGE THEM. SNOW REMOVAL SHALL BE ACCOMPLISHED BY UTILIZING A MELTING MACHINE BROUGHT TO THE SITE AS NEEDED.
- THE GENERAL CONTRACTOR IS RESPONSIBLE TO VERIFY ALL DIMENSIONS, ELEVATIONS AND CONDITIONS AT THE SITE. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER OF RECORD BEFORE PROCEEDING WITH THE AFFECTED PART OF THE WORK. THIS INCLUDES DISCREPANCIES BETWEEN THESE PLANS AND ANY OTHER PLANS OR CONTRACT DOCUMENTS.

SITE DATA BLOCK

PLAN INTENT: THE PROPOSAL IS TO CONSTRUCT A NEW PAVED PARKING LOT ON THE SUBJECT PARCEL

ZONE: CH - CHURCH HILL
OVERLAY DISTRICTS: HISTORIC DISTRICT

| USE: COMMERCIAL | REQUIRED IN CH DISTRICT |
|--|-------------------------|
| MINIMUM LOT SIZE (SQUARE FEET) | 5,000 SF |
| MINIMUM FRONTAGE (FEET) | 50 |
| MINIMUM LOT SETBACKS | |
| FRONT (FEET) | 15' |
| SIDE (FEET) | 5' |
| REAR (FEET) | 15' |
| MAXIMUM ROAD SETBACK (FEET) | NA |
| MAXIMUM HEIGHT (FEET) | 30' |
| MAXIMUM HEIGHT W/ P.B. APPROVAL (FEET) | 35' |
| IMPERVIOUS SURFACES RATIO | 80% |

PARKING CALCULATION

| USE | STANDARD | REQUIRED | PROVIDED |
|------------------------------------|------------------|--------------|------------|
| DWELLING UNITS AND BOARDING HOUSES | 1 SPACE/RESIDENT | 38 RESIDENTS | 38 SPACES |
| | | | 180 SPACES |


NOTE: ADDITIONAL PARKING SPACES FOR RENT BY OTHER PROPERTIES.

FINAL APPROVAL BY DURHAM PLANNING BOARD.
CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER
DATE _____

| NO. | REVISIONS | DATE |
|-----|---------------------------------------|----------|
| 1. | DRAINAGE UPDATES | 02/02/21 |
| 0. | INITIAL ALTERNATE ENTRANCE SUBMISSION | 07/05/21 |




DATE ISSUED: 01/05/21
SCALE: 1" = 30'
DESIGNED BY: AWS
DRAWN BY: MJS
APPROVED BY: MJS
DWG FILE: 18041 CIVIL.DWG

PROPOSED REVISED
ALTERNATE ENTRANCE
prepared for
TOOMERFS, LLC
TAX MAP 5, LOTS 1-9 AND 1-10
19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824




JOB: 18-041

C-101




P- PARKING LOT - CL
STA: 0+00 to STA: 2+64



FINAL APPROVAL BY DURHAM PLANNING BOARD.
 CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER
 DATE _____

| | |
|--|---|
| <p>MJS ENGINEERING, P.C. CIVIL • STRUCTURAL • ENVIRONMENTAL 5 RAILROAD ST., P.O. BOX 359 NEWBURY, NH 03857 PHONE: (603) 659-4979, FAX: (603) 659-4627 E-MAIL: info@mjs-engineering.com</p> | |
| <p>GRADING, DRAINAGE, UTILITY & EROSION CONTROL PLAN prepared for TOOMERFS, LLC TAX MAP 5, LOTS 1-9 AND 1-10 19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824</p> | |
| DATE ISSUED: | 10/28/20 |
| SCALE: | 1" = 30' |
| DESIGNED BY: | AWS |
| DRAWN BY: | AWS |
| APPROVED BY: | MJS |
| DWG FILE: | 18041 CIVI0.Dwg |
| SEAL | |
| NO. | REVISIONS |
| 1. | DRAINAGE UPDATES |
| 0. | INITIAL SUBMISSION FOR SITE PLAN REVIEW |
| DATE | INT. |
| 10/28/20 | AWS |
| 10/28/20 | AWS |




DEMOLITION ITEMS
(REFER TO DEMOLITION NOTE 5)

- ① SAWCUT AND REMOVE PAVEMENT AND ALL MARKINGS OR REMOVE OR GRIND PAVEMENT AS REQUIRED TO RECONSTRUCT AS SHOWN ON SITE PLAN.
- ② SAWCUT AND REMOVE EXISTING PAVEMENT TO THE LIMITS SHOWN.
- ③ REMOVE UTILITY POLE AND CONNECTED CABLES. COORDINATION WITH EVERSOURCE AND INTERNET/TV/PHONE PROVIDER MAY BE REQUIRED.
- ④ REMOVE EXISTING CURBING.
- ⑤ DEMOLISH EXISTING BUILDING, FOUNDATION, AND ALL ASSOCIATED UTILITIES AND STRUCTURES.
- ⑥ EXCAVATE EXISTING CLAY DITCH LINE TO PROJECT EXTENTS.
- ⑦ REMOVE EXISTING SEWER LINE WHERE NECESSARY TO AVOID INTERFERENCE WITH CONSTRUCTION.

DEMOLITION NOTES

1. LOCATIONS OF UTILITIES ARE APPROXIMATE. IT IS THE RESPONSIBILITY OF THE SITE CONTRACTOR TO VERIFY THE LOCATION OF ALL UTILITIES. CONTRACTOR SHALL CALL DISSAFE AT 1-888-DIG-SAFE (1-888-344-7253) PRIOR TO COMMENCING WITH ANY DEMOLITION WORK. ALL UTILITY WORK AND MATERIALS SHALL BE IN CONFORMANCE WITH THE SPECIFIC UTILITY COMPANY. CONSULT WITH THE SPECIFIC UTILITY COMPANY.
2. CONSTRUCTION SEQUENCING SHALL MEET THE REQUIREMENTS OF THE CONSTRUCTION SEQUENCING AND EROSION CONTROL NOTES FOUND ON SHEET D1. TEMPORARY EROSION CONTROL STRUCTURES AND TEMPORARY CHAINLINK FENCE SHALL BE INSTALLED PRIOR TO CONDUCTING EARTHWORK ACTIVITIES.
3. ALL SALVAGED MATERIALS FROM WITHIN THE CITY RIGHT OF WAY SHALL BE TAKEN TO THE DPW FACILITY. ALL DEMOLITION MATERIALS FROM WITHIN THE LOTS SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS SPECIFICALLY INDICATED OTHERWISE ON THIS PLAN. MATERIALS SHALL BE REMOVED FROM THE SITE AS SOON AS POSSIBLE TO PREVENT UNDUE BURDEN ON THE BUILDING CONTRACTOR OF WORKING AROUND STOCKPILED MATERIALS.
4. ALL DEMOLITION MATERIALS SHALL BE PROPERLY DISPOSED OF OFF SITE PER CURRENT LOCAL, STATE, AND FEDERAL REGULATIONS.
5. THE INTENT OF THIS PLAN IS TO SHOW THE DEMOLITION REQUIREMENTS. THE DEMOLITION OR REMOVAL OF ADDITIONAL ITEMS MAY BE REQUIRED AND IT IS THE CONTRACTOR'S RESPONSIBILITY TO PERFORM A SITE VISIT TO VERIFY ALL DEMOLITION REQUIREMENTS FOR THE PROJECT.
6. EXISTING MONUMENTATION THAT IS DISTURBED DURING CONSTRUCTION SHALL BE RESET BY A NH LICENSED LAND SURVEYOR OR PERSONS UNDER THE DIRECT SUPERVISION OF A NH LLS. NORWAY PLAINS & ASSOCIATES INC. (335-3948) IS THE SURVEYOR OF RECORD FOR THIS PROPERTY. COSTS FOR THIS WORK SHALL BE PAID FOR BY THE SITE CONTRACTOR.
7. THE SITE CONTRACTOR SHALL PROVIDE DAILY MAINTENANCE AS NECESSARY, INCLUDING SWEEPING AS NECESSARY, TO REMOVE DEPOSITED MATERIALS, SPILLS, ETC. ASSOCIATED WITH THE SITE CONSTRUCTION ACTIVITIES.
8. ALL WORK SHALL BE CONDUCTED IN A MANNER TO PROTECT EXISTING FEATURES TO REMAIN AS SHOWN. THIS INCLUDES ONSITE FEATURES AND THOSE FEATURES WITHIN THE PUBLIC R.O.W. DAMAGE TO THESE FEATURES SHALL BE REPAIRED/REPLACED IN KIND BY THE SITE CONTRACTOR.
9. IN ANY LOCATION WHERE AN EXISTING PEDESTRIAN TRAVEL WAY LEADS TO THE CONSTRUCTION SITE (CROSSWALK, SIDEWALK, ETC.), ACCESS TO THE CONSTRUCTION SITE SHALL BE BLOCKED AND SIGNAGE SHALL BE PROVIDED AS SHOWN BELOW:

NO ACCESS
CONSTRUCTION SITE
10. UTILITIES: THE SITE CONTRACTOR SHALL COORDINATE WITH EVERSOURCE TO REMOVE AND RELOCATE THE EXISTING TRANSFORMER.



FINAL APPROVAL BY DURHAM PLANNING BOARD.
CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER
CERTIFIED _____
DATE _____

| NO. | REVISIONS | DATE |
|-----|---|----------|
| 1. | DRAINAGE UPDATES | 02/02/21 |
| 0. | INITIAL SUBMISSION FOR SITE PLAN REVIEW | 10/28/20 |

DATE ISSUED: 10/28/20
SCALE: 1" = 30'
DESIGNED BY: AWS
DRAWN BY: AWS
APPROVED BY: MJS
DWF FILE: 18041 CIV.DWG

DEMOLITION PLAN
prepared for
TOOMERFS, LLC
TAX MAP 5, LOTS 1-9 AND 1-10
19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824

MJS ENGINEERING, P.C.
CIVIL • STRUCTURAL • ENVIRONMENTAL
5 RAILROAD ST., P.O. BOX 359
NEWBARKET, NH 03857
PHONE: (603) 659-4070 FAX: (603) 659-4627
E-MAIL: info@mjsengineering.com



LANDSCAPE NOTES:

- Design is based on drawings by MJS Engineering, P.C. dated January 20, 2021, and may require adjustment due to actual field conditions.
- The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site from erosion.
- Erosion Control shall be in place prior to construction.
- Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water bodies, Wetlands and/or drainage ways prior to any construction.
- The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any discrepancies or changes in layout and/or grade relationships prior to construction.
- It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.
- Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line at a minimum and shall include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portalets within the tree protection area.
- This plan is for review purposes only, NOT for Construction. Construction Documents will be provided upon request.
- Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the Contractor.
- The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call DIGSAFE at 1-888-344-7233.
- The Contractor shall procure any required permits prior to construction.
- Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.
- Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a contractor is aware of a potential issue and does not bring it to the attention of the landscape architect or owner's representative immediately, they may be responsible for the labor and materials associated with correcting the problem.
- The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in ANSI Z60.1 of the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
- A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern.
- All plants shall be legibly tagged with proper botanical name.
- The Contractor shall guarantee all plants for not less than one year from time of acceptance.
- Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
- No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.
- All landscaping shall be provided with either of the following
 - An underground sprinkling system
 - An outside hose attachment within 150 feet
- If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas.
- The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, and watering of plants. Plants shall be appropriately watered prior to, during and after planting. It is the contractor's responsibility to provide water from off site, should it not be available on site.
- All disturbed areas will be dressed with 6" of topsoil and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost.
- Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native bark not longer than 4" in length and 1/2" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be black.
- In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
- Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy.
- Snow shall be stored a minimum of 5' from shrubs and trunks of trees.
- Landscape Architect is not responsible for the means and methods of the contractor.

Plant List

| TREES | Symbol | Botanical Name | Common Name | Quantity | Size | Comments |
|-------|--------|-------------------------------------|-------------------------|----------|------------|----------|
| | Am | <i>Amelanchier canadensis</i> | Shadblow Serviceberry | 1 | 2.5-3" cal | B&B |
| | Ar | <i>Acer rubrum 'October Glory'</i> | October Glory Red Maple | 2 | 2.5-3" cal | B&B |
| | Ls | <i>Liquidambar styraciflua</i> | American Sweetgum | 4 | 2.5-3" cal | B&B |
| | Pa | <i>Picea abies</i> | Norway Spruce | 10 | 7-8' ht. | B&B |
| | Pg | <i>Picea glauca</i> | White Spruce | 9 | 7-8' ht. | B&B |
| | Th | <i>Thuja plicata 'Green Giant'</i> | Green Giant Arborvitae | 25 | 10' ht. | B&B |
| | Ua | <i>Ulmus americana 'Princeton'</i> | Princeton American Elm | 10 | 2.5-3" cal | B&B |
| | Z | <i>Zelkova serrata 'Green Vase'</i> | Green Vase Zelkova | 4 | 2.5-3" cal | B&B |

TREE PLANTING DETAIL



woodburn & company
 LANDSCAPE ARCHITECTURE
 103 Kent Place Newmarket, New Hampshire Phone: 603.659.5949

FINAL APPROVAL BY DURHAM PLANNING BOARD.
 CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER
 CERTIFIED _____
 DATE _____

MJS ENGINEERING, P.C.
 CIVIL • STRUCTURAL • ENVIRONMENTAL
 6 FAIRBANKS ST., P.O. BOX 359
 NEWMARKET, NH 03857
 PHONE: (603) 659-4979 FAX: (603) 659-4627
 E-MAIL: info@mjsengineering.com

LANDSCAPE PLAN
 prepared for
 TOOMERS, LLC
 TAX MAP 5, LOTS 1-9 AND 1-10
 19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824

DATE ISSUED: 10/19/20
 SCALE: 1"=30'
 DESIGNED BY: RW
 DRAWN BY: LF
 APPROVED BY: RW
 DWG FILE: _____

1. PER REVISED SITE PLAN
 0. INITIAL SUBMISSION FOR SITE PLAN REVIEW

NO. REVISIONS
 DATE

JOB: 18-041
L-100




VISUAL

19 MAIN ST - DURHAM, NH Site Lighting Layout

| Symbol | Label | Quantity | Manufacturer | Catalog Number | Description | Lamp | Number Lamps | Filename | Lumens Per Lamp | Light Loss Factor | Wattage |
|--------|------------|----------|--------------------|--|---|------|--------------|-----------------------------------|-----------------|-------------------|---------|
| | 2S4 | 3 | Lithonia Lighting | DSX0 LED P3 30K TFTM MVOLT SPA DDBXD with SSS 18 4C DM28AS DDBXD | DSX0 LED Area Fixture; mounted at 18ft | LED | 1 | DSX0_LED_P3_30K_TFTM_MVO LT.ies | 7841 | 0.9 | 142 |
| | EX | 1 | XXXXX | XXXXXX | Existing Lantern-Style Fixture; mounted at 14ft | LED | 1 | 962TC-XRLED-12L45T5-MDL14-SV1.IES | 5166 | 0.9 | 59.1 |
| | G5 | 1 | Sternberg Lighting | 962TC-XRLED-12L45T5-MDL14-SV1 | Glenn Ellen Series; mounted at 14ft | LED | 1 | 962TC-XRLED-12L45T5-MDL14-SV1.IES | 5166 | 0.9 | 59.1 |
| | S2 | 1 | Lithonia Lighting | DSX0 LED P1 30K T3M MVOLT SPA DDBXD with SSS 12 4C DM19AS DDBXD | DSX0 LED Area Fixture; mounted at 12ft | LED | 1 | DSX0_LED_P1_30K_T3M_MVOL T.ies | 4248 | 0.9 | 38 |
| | S4 | 3 | Lithonia Lighting | DSX0 LED P3 30K TFTM MVOLT SPA DDBXD with SSS 18 4C DM19AS DDBXD | DSX0 LED Area Fixture; mounted at 18ft | LED | 1 | DSX0_LED_P3_30K_TFTM_MVO LT.ies | 7841 | 0.9 | 71 |

| Statistics | | | | | | |
|--------------------------|--------|--------|--------|--------|---------|---------|
| Description | Symbol | Avg | Max | Min | Max/Min | Avg/Min |
| Outside of Parking Lot | + | 0.1 fc | 1.3 fc | 0.0 fc | N/A | N/A |
| Parking at Rooming House | + | 0.2 fc | 0.5 fc | 0.1 fc | 5.0:1 | 2.0:1 |
| Parking Lot | + | 1.1 fc | 4.7 fc | 0.1 fc | 47.0:1 | 11.0:1 |



Designer
Heidi G. Connors
Visible Light, Inc.
24 Stickney Terrace
Suite 6
Hampton, NH 03842

Date
10/27/2020

Scale
1"=30'

Drawing No.
Summary

CONSTRUCTION SEQUENCING AND EROSION CONTROL NOTES:

- AREA OF DISTURBANCE/STABILIZATION
A. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION...
B. AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED...
C. DISTURBED AREAS SHALL BE TEMPORARILY STABILIZED WITHIN 45 DAYS...

- EROSION CONTROL PRACTICES:
A. INSTALLATION:
1. INSTALL ALL EROSION CONTROLS AS SHOWN ON THE GRADING PLAN...
B. INSPECTION:
1. INSPECT ALL EROSION CONTROLS WEEKLY AND AFTER EVERY RAIN EVENT...

- COLD WEATHER SITE STABILIZATION
A. TO ADEQUATELY PROTECT WATER QUALITY DURING COLD WEATHER...
B. SUBJECT TO (C), BELOW, THE AREA OF EXPOSED SOIL SHALL BE:
1. LIMITED TO ONE ACRE; AND
2. PROTECTED AGAINST EROSION BY THE METHODS DESCRIBED...

TEMPORARY VEGETATION

- A. SITE PREPARATION
1. INSTALL EROSION AND SEDIMENT CONTROL MEASURES AS SPECIFIED ABOVE.
2. ENSURE RUNOFF IS DIVERTED FROM SEEDING AREA.
B. SEED BED PREPARATION
1. REMOVE STONES AND TRASH FROM AREA TO BE SEEDDED.

Table with columns: SEASON, APPLICATION DATE, MIXTURE TYPE, QUANTITY (lb./Ac.). Rows include Early Spring, Late Spring/Fall, and Early Spring/Fall with specific dates and quantities.

- 2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER...
3. TEMPORARY SEEDING SHALL OCCUR PRIOR TO SEPTEMBER 15TH...
4. AREAS SEEDDED BETWEEN MAY 15TH AND AUGUST 15TH SHALL BE COVERED WITH HAY OR STRAW MULCH...
5. IF VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA IS NOT ACHIEVED...
6. MAINTENANCE
1. TEMPORARY SEEDING SHOULD BE INSPECTED WEEKLY...

- PERMANENT VEGETATION
A. SITE PREPARATION
1. REFER TO SITE PREPARATION FOR TEMPORARY SEEDING.
2. SEED BED PREPARATION FOR TEMPORARY SEEDING IN CONJUNCTION WITH THESE NOTES.
3. REMOVE FROM THE SURFACE ALL STONES 2 INCHES OR LARGER...
4. INSPECT SEEDBED JUST BEFORE SEEDING...
5. WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS...
6. APPLY FERTILIZER AT A RATE OF 600 LBS PER ACRE OF 10-10-10...
C. SEEDING
1. UNLESS OTHERWISE NOTED, GRASS SEED MIXTURE 'C' SHALL BE APPLIED AT THE SPECIFIED RATE...
2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER...
3. WHEN FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS USED...
4. WHEN HYDROSEEDING (HYDRAULIC APPLICATION), PREPARE THE SEEDBED AS SPECIFIED...
5. LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED...
6. FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED...
7. SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING...
8. TEMPORARY SEEDING SHALL OCCUR PRIOR TO SEPTEMBER 15TH...
9. HAY AND STRAW MULCHES SHALL BE ANCHORED WITH MULCH NETTING OR TACKIFIER...
10. IF VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA IS NOT ACHIEVED...
D. MAINTENANCE
1. PERMANENTLY SEEDDED AREAS SHOULD BE INSPECTED MONTHLY.
2. MOW SEEDDED AREAS AS NECESSARY.
3. BASED ON INSPECTION, AREAS SHOULD BE REPAIRED AND/OR RESEEDED TO ENSURE 85% OF THE SOIL SURFACE IS COVERED BY VEGETATION.

MULCHING & EROSION CONTROL MATTING

- A. GENERAL
1. APPLY PRIOR TO A STORM EVENT. CLOSELY MONITOR THE WEATHER TO HAVE ADEQUATE WARNING OF SIGNIFICANT STORMS.
2. MULCHING WITHIN A SPECIFIED TIME PERIOD FROM ORIGINAL SOIL EXPOSURE
2.A. WITHIN 100 FEET OF WETLANDS THE TIME PERIOD SHOULD BE NO GREATER THAN 7 DAYS.
2.B. IN OTHER AREAS IT SHALL BE NO GREATER THAN 14 DAYS.
3. MULCH MATERIALS SHALL BE SELECTED BASED UPON SOILS, FLOW CONDITIONS, AND TIME OF YEAR.
B. TEMPORARY MULCHING
1. HAY OR STRAW MULCHES
1.A. ORGANIC MULCHES INCLUDING HAY AND STRAW SHALL BE AIR-DRIED, FREE OF UNDESIRABLE SEEDS AND COARSE MATERIALS.
1.B. APPLICATION RATE SHALL BE 2 BALES/1,000 SF (70-90 POUNDS) OR 1.5-2.0 TONS/ACRE TO COVER 75-100% OF THE GROUND.
1.C. ANCHORING SHALL BE ONE OF THE FOLLOWING:
1.C.1. NETTING SHALL BE JUTE, WOOD FIBER, OR BIODEGRADABLE PLASTIC NETTING...
1.C.2. TACKIFIER: APPLY POLYMER OR ORGANIC TACKIFIER TO ANCHOR HAY OR STRAW MULCH...
1.D. WINTER APPLICATION: APPLY TO A DEPTH OF 4 INCHES OR DOUBLE THE ABOVE LISTED APPLICATION RATE...
1.E. MAINTENANCE
1.E.1. INSPECT PERIODICALLY AND AFTER RAIN STORMS FOR RILLS OR DISPLACEMENT OF MULCH...
2. EROSION CONTROL BLANKET OR MATTING
2.A. REFER TO PLANS FOR TYPICAL EROSION CONTROL MATTING DETAIL...
2.B. APPLICATION AND TIMING
2.B.1. DURING THE GROWING SEASON (APRIL 15 - SEPTEMBER 15) USE ON THE BASE OF GRASSED WATERWAYS...
2.B.2. DURING THE LATE FALL AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED ABOVE USE ON SIDE SLOPES OF GRASSED WATERWAYS...
3. MAINTENANCE
3.A. INSPECT PERIODICALLY AND BEFORE AND AFTER STORM EVENTS TO ENSURE CONTACT WITH THE SOIL...
C. PERMANENT MULCHING
1. WOOD CHIPS OR GROUND BARK
1.A. APPLY TO A THICKNESS OF 2 TO 6 INCHES...
1.B. MAINTENANCE: INSPECT ANNUALLY AND AFTER RAIN EVENTS...
2. EROSION CONTROL MIX
2.A. SHALL BE PLACED AT A THICKNESS OF 2 INCHES OR MORE...
2.B. COMPOSITION OF THE MIX SHALL BE AS FOLLOWS:
2.B.1. ORGANIC MATTER CONTENT SHALL BE BETWEEN 25-65% DRY WEIGHT BASIS...
2.B.2. PARTICLE SIZE BY WEIGHT SHOULD BE 100% PASSING THE 3" SCREEN...
2.B.3. THE ORGANIC PORTION SHALL BE ELONGATED AND FIBROUS...
2.B.4. THE MIX SHALL NOT CONTAIN SILTS, CLAYS, OR FINE SANDS...
2.B.5. SOLUBLE SALT CONTENT SHALL BE < 4.0MMHOS/CM AND A PH OF 5.0-8.0...
2.C. PLACEMENT OF MIX
2.C.1. PLACE BERM ALONG A LEVEL CONTOUR...
2.D. MAINTENANCE: INSPECT PERIODICALLY AND AUGMENT AS NEEDED TO MAINTAIN INITIAL THICKNESS...

- SOIL STOCKPILES
GENERAL
1. STOCKPILES MUST BE LOCATED 50 FEET FROM DITCHES AND CULVERT INLETS.
2. PROTECT SOIL AND AGGREGATE STOCKPILES WITH TEMPORARY PERIMETER SEDIMENT BARRIER SUCH AS SILT FENCE OR SILT SOCK.
3. COVER ACTIVE STOCKPILES WITH ANCHORED PROTECTIVE COVERING PRIOR TO EXPECTED STORM EVENTS.
4. INACTIVE STOCKPILES SHALL BE COVERED WITH ANCHORED TARPS OR TEMPORARILY SEEDED AND MULCHED PER THE TEMPORARY VEGETATION AND MULCHING NOTES ON THIS PAGE.
5. STOCKPILES THAT ARE A SOURCE OF DUST SHALL BE COVERED.

- DUST CONTROL
A. DUST SHALL BE CONTROLLED ON SITE DURING CONSTRUCTION BY IMPLEMENTING THE FOLLOWING DUST CONTROL MEASURES:
1. MULCHING AND VEGETATIVE COVER TO REDUCE DUST.
2. MECHANICAL SWEEPERS AND FINE WATER SPRAY.
3. COVER SURFACES WITH CRUSHED STONE OR COARSE GRAVEL.

SEED MIXTURE SELECTION BASED ON SOIL TYPE. Table with columns: USE, SEEDING MIXTURE, DROUGHTY, WELL DRAINED, MODERATELY WELL DRAINED. Rows include Steep cuts and fills, waterways, parking lots, play areas.


SEED MIXTURES FOR PERMANENT VEGETATION. Table with columns: MIXTURE, SPECIES, POUNDS PER ACRE, POUNDS PER 1,000 SF. Rows include Tall fescue, creeping red fescue, Kentucky bluegrass.

- CONSTRUCTION SEQUENCING:
1. SCHEDULE A PRE-CONSTRUCTION MEETING WITH TOWN OFFICIALS, OWNER, AND CONTRACTORS...
2. CONTACT DIG-SAFE, INDIVIDUAL UTILITIES, AND CITY DEPARTMENTS TO GET ALL UTILITIES MARKED...
3. INSTALL PERIMETER CONTROLS PRIOR TO ALL EARTHMOVING WORK.
4. CLEAR/GRUB ONLY WITHIN THE LIMITS OF GRADING AS SHOWN ON THE PLANS...
5. THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800...
6. CLEAR/GRUB
A. STUMPS MAY BE DISPOSED ON-SITE IN ACCORDANCE WITH LOCAL AND STATE REGULATIONS.
B. TEMPORARILY STABILIZE LOAM STOCKPILES WITH:
1. WINTER RYE GRASS - PRIOR TO SEPTEMBER 15TH
2. MULCH - FROM SEPTEMBER 15TH TO MAY 1ST
7. CONSTRUCT AND STABILIZE ALL TEMPORARY AND PERMANENT SEDIMENT, EROSION, AND STORMWATER CONTROL FACILITIES AS LISTED ABOVE.
8. THESE SHALL BE INSTALLED BEFORE ANY MAJOR EARTH MOVING OPERATIONS.
9. RUNOFF MUST BE DIRECTED TO TEMPORARY PRACTICES UNTIL STORMWATER BMPs ARE STABILIZED...
10. PARKING LOT CONSTRUCTION
A. CUTS AND FILLS:
1. CONSTRUCT IN LOCATIONS AND TO GRADES AS SHOWN ON THE PLANS.
2. FILLS:
A. PLACE MAXIMUM 12" LIFTS AND COMPACT TO 95% MAXIMUM DRY DENSITY.
B. ALL MATERIAL BASED ON PROCTOR TEST SHALL BE FREE OF DELETERIOUS MATERIALS...
C. LOAM AND SEED SLOPES WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
D. STABILIZE ALL PARKING AREAS WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
11. INSPECT, MAINTAIN, AND IF NECESSARY, REPAIR ALL EROSION AND SEDIMENT CONTROL MEASURES...
12. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES ONCE INITIAL GROWTH IS ESTABLISHED.


- ADDITIONAL NOTES:
1. NO FILLS SHALL BE STORED ON SITE DURING CONSTRUCTION.
2. DURING CONSTRUCTION DUST SHALL BE PREVENTED FROM BECOMING A SAFETY OR HEALTH HAZARD...
3. ALL CONSTRUCTION MATERIALS THAT ARE SPILLED OR DEPOSITED ON THE PUBLIC ROADWAYS SHALL BE REMOVED BY THE CONTRACTOR.
4. DO NOT BEGIN CONSTRUCTION UNTIL ALL LOCAL, STATE, AND FEDERAL PERMITS HAVE BEEN APPLIED FOR AND RECEIVED.
5. THE GENERAL CONTRACTOR IS RESPONSIBLE TO VERIFY ALL DIMENSIONS, ELEVATIONS AND CONDITIONS AT THE SITE. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN ENGINEER BEFORE PROCEEDING WITH THE AFFECTED PART OF THE WORK.

CONSTRUCTION NOTES FOR SEDIMENT FENCE


- 1. WOVEN WIRE FENCE, IF REQUIRED, TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES.
2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP, MID SECTION, AND BOTTOM.
3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6 INCHES, FOLDED AND STAPLED.
4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SEDIMENT FENCE, OR 50% OF CAPACITY IS USED.
5. 12" DIAMETER FILTERX SS SILT/SOXX SHALL BE CONSIDERED AN ACCEPTABLE EQUAL TO SEDIMENT FENCE IF INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.



SEDIMENT FENCE NTS



SEDIMENT FENCE POCKET NTS




- NOTES:
1. SEDIMENT FILTER TRAP SHALL BE ACF REGULAR FLOW SILT/SACK OR APPROVED EQUAL.
2. FILTERS SHALL BE INSPECTED AFTER EVERY RAIN EVENT OF 0.25" OR GREATER AND SEDIMENTS SHALL BE REMOVED FROM TRAP WHEN SEDIMENT HAS REACHED TWO THIRDS OF THE DEPTH OF THE TRAP, OR IF PONDING OF WATER AT SURFACE BEGINS TO OCCUR...
3. DO NOT PUNCTURE FILTER TRAP TO MITIGATE OUNDR.

CATCH BASIN SEDIMENT FILTER DETAIL NTS

FINAL APPROVAL BY DURHAM PLANNING BOARD. CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER. Includes signature lines for Certified and Date.



Table with columns: DATE, REVISIONS. Rows show dates 02/02/21, 07/05/21 and revision numbers 1, 2.



DATE ISSUED: 01/02/21
SCALE: N/A
DESIGNED BY: AWS
DRAWN BY: AWS
APPROVED BY: MJS

CONSTRUCTION DETAILS
prepared for: TOOMERS, LLC
TAX MAP 5, LOTS 1-9 AND 1-10
19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824

MJS ENGINEERING, P.C. CIVIL & STRUCTURAL • ENVIRONMENTAL
5 Railroad St., P.O. Box 359, Newmarket, NH 03857
Phone: (603) 659-6979, Fax: (603) 659-4427, E-mail: mjse@mjse-engineering.com





NOTES:
1. DELETERIOUS MATERIALS ENCOUNTERED BELOW PARKING AREA SHALL BE COMPLETELY REMOVED.
2. COMPACT SUBGRADE TO 95% OF STANDARD PROCTOR.

PAVED PARKING LOT CROSS-SECTION
NTS


- NOTES:
1. SAWCUT THROUGH DEPTH OF PAVEMENT AT LEAST 1 FT. FROM EDGE OR GREATER IF REQUIRED BY NHDOT.
2. INSTALL AND COMPACT CRUSHED GRAVEL TO GRADE.
3. PLACE BINDER COURSE.
4. GRIND EXISTING PAVEMENT 1 FT. WIDE TO A DEPTH NECESSARY TO PROPERLY MATCH NEW WEARING COURSE PAVEMENT.
5. TACK COAT ALL EXISTING PAVEMENT SURFACES WITH EMULSIFIED ASPHALT (MS-1) PRIOR TO PLACING NEW PAVEMENT.

TYPICAL PAVEMENT SAWCUT DETAIL
NTS



- NOTES:
1. LENGTH OF ENTRANCE MAY BE 50' WHERE DIVERSION RIDGE IS PROVIDED.
2. GRADE AND COMPACT ACCESS ROAD ENTRANCE AS NECESSARY. PLACE FILTER FABRIC AND 6\"/>

STABILIZED CONSTRUCTION ENTRANCE DETAIL
NTS




- NOTES:
1. SEE SITE PLAN FOR STRIPING LAYOUT

PAVEMENT MARKINGS:


1. STRIPE PARKING AREAS AND DRIVES AS SHOWN, INCLUDING PARKING SPACES, HANDICAP SYMBOLS, AND PAINTED ISLANDS. ALL TRAFFIC PAINT SHALL MEET THE REQUIREMENTS OF THE NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION (NHDOT) AND AASHTO M248 TYPE "F" MEDIAN ISLANDS AND CENTERLINES TO BE CONSTRUCTED USING YELLOW TRAFFIC PAINT.
2. ALL PAVEMENT MARKINGS AND SIGNS SHALL CONFORM TO THE LATEST EDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", THE "STANDARD ALPHABETS FOR HIGHWAY SIGN AND PAVEMENT MARKINGS", AND THE AMERICANS WITH DISABILITIES ACT REQUIREMENTS.
3. PAINTED ISLANDS SHALL BE 4 INCH WIDE DIAGONAL LINES SPACED AT 3 FT. O.C. BORDERED BY 4 INCH WIDE LINES.
4. MAXIMUM SLOPE OF ADA PARKING IS 2%

ADA STRIPING AND SIGN DETAIL
NTS




- NOTES:
1. MINIMUM LENGTH OF CURB STONES = 3'
2. MAXIMUM LENGTH OF CURB STONES = 10'
3. ADJOINING STONES SHALL HAVE THE SAME OR APPROXIMATELY THE SAME LENGTH.
4. SEE PLAN FOR LOCATION

TYPICAL VERTICAL GRANITE CURB
NTS





- NOTES:
1. REMOVE LOAM TO A MINIMUM DEPTH OF 8\"/>

TYPICAL SLOPED GRANITE CURB
NTS




TYPICAL BIKE RACK DETAIL
NTS


- NOTE:
1. INSTALL IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS
2. ALL STEEL MEMBERS SHALL BE COATED W/ ZINC RICH EPOXY THEN FINISHED W/ POLYESTER POWDER COATING
3. PIPE: ASTM A53 GRADE B STANDARD WEIGHT STEEL PIPE
4. PLATE: ASTM 136 3/8 INCH THICK PLATE WITH THREE 3/4 INCH DIA. HOLES AT 120 DEGREE SPACING.
5. BOLT: DRIVE TYPE ANCHOR BOLT MADE OF ZINC PLATED AISI 1038 HEAT TREATED CARBON STEEL, 1/2 INCH DIA. BY 3 INCHES LONG.
6. CONCRETE STRENGTH TO BE 3,000 PSI AT 28 DAYS.



ANCHOR TRENCH AT TOP OF SLOPE DETAIL B



SHINGLE SPlice DETAIL C



ROLLED EROSION CONTROL DETAIL
NTS

- NOTES:
1. INSTALL STAPLES ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.
2. OVERLAP IN THE DIRECTION OF THE PREVAILING WIND.
3. INSTALL STAPLES ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.
4. PROVIDE CHECK SLOTS ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.
5. ROLL ENDS MAY BE SPLICED IN A CHECK SLOT.
6. TRAPEZOIDAL DITCH SHOWN. SIMILAR DETAILS FOR A V-DITCH.

ANCHOR TRENCH AT TOE OF SLOPE DETAIL D

FINAL APPROVAL BY DURHAM PLANNING BOARD.
CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER
CERTIFIED _____
DATE _____


| NO. | REVISIONS | DATE | INT. |
|-----|---------------------------------------|----------|------|
| 1 | DRAINAGE UPDATES | 02/02/21 | AWS |
| 2 | INITIAL ALTERNATE ENTRANCE SUBMISSION | 07/05/21 | AWS |

| | |
|--------------|----------------|
| DATE ISSUED: | 01/05/21 |
| SCALE: | N/A |
| DESIGNED BY: | AWS |
| DRAWN BY: | AWS |
| APPROVED BY: | MJS |
| DWG FILE: | 18041 DefB.dwg |

CONSTRUCTION DETAILS
prepared for
TOOMERS, LLC
TAX MAP 5, LOTS 1-9 AND 1-10
19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824


MJS ENGINEERING, P.C.
CIVIL • STRUCTURAL • ENVIRONMENTAL
5 Railroad St., P.O. Box 359
Newmarket, NH 03857
Phone: (603) 659-4979 Fax: (603) 659-4427
Email: mjs@engr.com

JOB: 18-041
C-502



- NOTES:**
- CONSTRUCTION TO BE IN ACCORDANCE WITH PSNH CONSTRUCTION STANDARDS FOR NEW ELECTRICAL SERVICE WORK BY CONTRACTORS, MOST RECENT EDITION.
 - SELECT SAND BACKFILL SHALL CONSIST OF A FINE GRANULAR MATERIAL OF WHICH 100% SHALL PASS THROUGH A 1/4" SIEVE, EXCEPT NATURALLY OCCURRING SMOOTH ROUND PEBBLES NO GREATER THAN 3/8" IN DIAMETER ARE PERMITTED AS LONG AS THEIR TOTAL VOLUME PER CUBIC FOOT OF SAND DOES NOT EXCEED 1%. THE SAND SHALL BE COMPLETELY FREE OF FROZEN LUMPS, ROCKS, STONES, DEBRIS AND RUBBISH. BACKFILL SHALL BE THOROUGHLY COMPACTED IN 6" LIFTS.
 - CONDUIT SIZES TO BE 5" 3-PHASE PRIMARY AND 4" 3-PHASE SECONDARY. ALL CONDUIT SIZES TO BE VERIFIED BY PSNH.
 - ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND WHERE APPLICABLE THE NATIONAL ELECTRIC CODE.

TELEPHONE & ELECTRIC TRENCH
N.T.S.




TYPICAL SIGN DETAIL
N.T.S.


- NOTES:**
1. SEE PLANS FOR SIGN PLACEMENT.



LITHONIA DSX0-LED POLE MOUNTED LIGHT FIXTURE
N.T.S.




STERNBERG LIGHTING 962TC-XRLED GLEN ELLYN SERIES POLE MOUNTED LIGHT FIXTURE
N.T.S.




- NOTES:**
- CONCRETE MINIMUM 5,000 PSI AFTER 28 DAYS.
 - CONDUIT, ANCHOR BOLTS AND TEMPLATE SUPPLIED BY OTHERS.
 - LIGHT POLE BASE SIZE IS TO BE SPECIFIED BY A QUALIFIED ENGINEER.
 - TYPICAL BASE DIAMETERS 'D' INCLUDE: 12", 18", 24", AND 30".
 - TYPICAL BASE HEIGHTS 'H' RANGE FROM 4' TO 7'.
 - OTHER BASE SIZES AVAILABLE UPON REQUEST.
 - BASE SHALL EXTEND 18"-24" ABOVE GRADE.

LIGHT POLE BASE DETAIL
N.T.S.




- NOTES:**
1. DELETERIOUS MATERIALS ENCOUNTERED BELOW PARKING AREA SHALL BE COMPLETELY REMOVED.
2. COMPACT SUBGRADE TO 95% OF STANDARD PROCTOR.

RETAINING WALL DETAIL
N.T.S.



ENTRY DRIVEWAY CROSS SECTION
SCALE: 1"=2'




| | |
|--------------|----------------|
| DATE ISSUED: | 01/05/21 |
| SCALE: | N/A |
| DESIGNED BY: | AMS |
| DRAWN BY: | AMS |
| APPROVED BY: | MJS |
| DWG FILE: | 18041 DefB.dwg |

CONSTRUCTION DETAILS
prepared for
TOOMERFS, LLC
TAX MAP 5, LOTS 1-9 AND 1-10
19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824

FINAL APPROVAL BY DURHAM PLANNING BOARD.
CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER
CERTIFIED _____
DATE _____

MJS ENGINEERING, P.C.
CIVIL • STRUCTURAL • ENVIRONMENTAL
5 Railroad St., P.O. Box 359
Newmarket, NH 03857
Phone: (603) 659-4979 Fax: (603) 659-4427
Email: mjs@mjsengineering.com







P:\88918-04\Internal\Drawing Files\CIVIL_DRAINAGE_DETAILS_A.dwg 2023-10-23 09:19 am




NOTES

- ALL DIMENSIONS ARE NOMINAL
- LABEL TYPE OF MANHOLE WITH 3" HIGH LETTERS IN THE CENTER OF THE COVER

DRAIN MANHOLE FRAME AND GRATE
NOT TO SCALE



- STORMTECH CHAMBER SPECIFICATIONS**
- CHAMBERS SHALL BE STORMTECH MC-4500.
 - CHAMBERS SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE COPOLYMERS.
 - CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORT PANELS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
 - THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION FOR IMPACT AND MULTIPLE VEHICLE PRESENCES.
 - CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2418-16, "STANDARD SPECIFICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
 - CHAMBERS SHALL BE DESIGNED AND ALLOWABLE LOADS DETERMINED IN ACCORDANCE WITH ASTM F2787, "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
 - ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. THE CHAMBER MANUFACTURER SHALL SUBMIT THE FOLLOWING UPON REQUEST TO THE SITE DESIGN ENGINEER FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE:
 - A STRUCTURAL EVALUATION SEALED BY A REGISTERED PROFESSIONAL ENGINEER THAT DEMONSTRATES THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY AASHTO FOR THERMOPLASTIC PIPE.
 - A STRUCTURAL EVALUATION SEALED BY A REGISTERED PROFESSIONAL ENGINEER THAT DEMONSTRATES THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET. THE 50 YEAR CREEP MODULUS DATA SPECIFIED IN ASTM F2418 MUST BE USED AS PART OF THE AASHTO STRUCTURAL EVALUATION TO VERIFY LONG-TERM PERFORMANCE.
 - STRUCTURAL CROSS SECTION DETAIL ON WHICH THE STRUCTURAL EVALUATION IS BASED.
 - CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.
- IMPORTANT - NOTES FOR THE BIDDING AND INSTALLATION OF MC-4500 CHAMBER SYSTEM**
- STORMTECH MC-4500 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS.
 - STORMTECH MC-4500 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH MC-3500/MC-4500 CONSTRUCTION GUIDE".
 - CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR EXCAVATOR SITUATED OVER THE CHAMBERS. STORMTECH RECOMMENDS 3 BACKFILL METHODS:
 - STONESHOOTER LOCATED OFF THE CHAMBER BED.
 - BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
 - BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
 - THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
 - JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
 - MAINTAIN MINIMUM 9" (230 mm) SPACING BETWEEN THE CHAMBER ROWS.
 - INLET AND OUTLET MANIFOLDS MUST BE INSERTED A MINIMUM OF 12" (300 mm) INTO CHAMBER END CAPS.
 - EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE MEETING THE AASHTO M43 DESIGNATION OF #3 OR #4.
 - STONE SHALL BE BROUGHT UP EVENLY AROUND CHAMBERS SO AS NOT TO DISTORT THE CHAMBER SHAPE. STONE DEPTHS SHOULD NEVER DIFFER BY MORE THAN 12" (300 mm) BETWEEN ADJACENT CHAMBER ROWS.
 - STONE MUST BE PLACED ON THE TOP CENTER OF THE CHAMBER TO ANCHOR THE CHAMBERS IN PLACE AND PRESERVE ROW SPACING.
 - THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIAL BEARING CAPACITIES TO THE SITE DESIGN ENGINEER.
 - ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.



DATE ISSUED: 01/05/21
SCALE: N/A
DESIGNED BY: AWS
DRAWN BY: MJS
APPROVED BY: MJS
DWG FILE: CIVIL_DRAINAGE_DETAILS_A.dwg

1. DRAINAGE UPDATES
2. INITIAL ALTERNATE ENTRANCE SUBMISSION

NO REVISIONS







DATE INT.

CONSTRUCTION DETAILS

prepared for
TOOMERS, LLC
TAX MAP 5, LOTS 1-9 AND 1-10
19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824

MJS ENGINEERING, P.C.
CIVIL • STRUCTURAL • ENVIRONMENTAL
NEW HAMPSHIRE, NH 03827
6 FAIRBANKS ST. P.O. BOX 359
NEW HAMPSHIRE, NH 03827
PHONE: (603) 659-4479 FAX: (603) 659-4467
E-MAIL: info@mjs-engineering.com

JOB: 18-041
C-504



FINAL APPROVAL BY DURHAM PLANNING BOARD.
CERTIFIED BY MICHAEL BEHRENDT, TOWN PLANNER
CERTIFIED _____
DATE _____

IMPORTANT NOTE
FOUNDATION AND EMBEDMENT STONE SHALL BE **CLEAN, WASHED, ANGULAR CRUSHED STONE**. ENGINEER SHALL INSPECT AND VERIFY MATERIAL PRIOR TO SYSTEM INSTALLATION.

STORMTECH MC-4500 CHAMBER SPECIFICATIONS

100.0\"/>

ROW LENGTH VARIES
 [17 CHAMBERS/ROW x 4.025' LONG] + [2.55' CAP LENGTH x 2] = 73.53' ROW LENGTH
 + [12.0\"/>

[16 CHAMBERS/ROW x 4.025' LONG] + [2.55' CAP LENGTH x 2] = 69.50' ROW LENGTH
 + [12.0\"/>

[14 CHAMBERS/ROW x 4.025' LONG] + [2.55' CAP LENGTH x 2] = 61.45' ROW LENGTH
 + [12.0\"/>

[8 CHAMBERS/ROW x 4.025' LONG] + [2.55' CAP LENGTH x 2] = 37.30' ROW LENGTH
 + [12.0\"/>

[5 ROWS x 100.0\"/>

[12.0\"/>

[81 CHAMBERS x 106.5 CF] + [35.7 CF CAP VOLUME x 2 x 5 ROWS] = 8,984 CF CHAMBER STORAGE
 23,628 CF FIELD - 8,984 CF CHAMBERS = 14,644 CF STONE x 40.0% VOIDS = 5,858 CF STONE STORAGE
 CHAMBER STORAGE + STONE STORAGE = 14,842 CF = 0.340 AF
 OVERALL STORAGE EFFICIENCY = 62.8%

ACCEPTABLE FILL MATERIALS: STORMTECH MC-4500 CHAMBER SYSTEMS

| MATERIAL LOCATION | DESCRIPTION | AASHTO MATERIAL CLASSIFICATIONS | COMPACTION / DENSITY REQUIREMENT | |
|-------------------|---|--|---|---|
| D | FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER | N/A | PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS. | |
| C | INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 24\"/> | GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE. MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER. | AASHTO M145 ¹ A-1, A-2-4, A-3 OR AASHTO M43 ¹ 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9, 10 | BEGIN COMPACTIONS AFTER 24\"/> |
| B | EMBEDMENT STONE: FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE. | CLEAN, CRUSHED, ANGULAR STONE | AASHTO M43 ¹ 3, 4 | NO COMPACTION REQUIRED. |
| A | FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER. | CLEAN, CRUSHED, ANGULAR STONE | AASHTO M43 ¹ 3, 4 | PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. ^{2,3} |

PLEASE NOTE:
 1. THE LISTED AASHTO DESIGNATIONS ARE FOR GRADATIONS ONLY. THE STONE MUST ALSO BE CLEAN, CRUSHED, ANGULAR. FOR EXAMPLE, A SPECIFICATION FOR #4 STONE WOULD STATE: "CLEAN, CRUSHED, ANGULAR NO. 4 (AASHTO M43) STONE".
 2. STORMTECH COMPACTION REQUIREMENTS ARE MET FOR 'A' LOCATION MATERIALS WHEN PLACED AND COMPACTED IN 9\"/>

INSPECTION & MAINTENANCE

- STEP 1) INSPECT ISOLATOR ROW FOR SEDIMENT
 A. INSPECTION PORTS (IF PRESENT)
 A.1. REMOVE/OPEN LID ON NYLOPLAST INLINE DRAIN
 A.2. REMOVE AND CLEAN FLEXSTORM FILTER IF INSTALLED
 A.3. USING A FLASHLIGHT AND STADIA ROD, MEASURE DEPTH OF SEDIMENT AND RECORD ON MAINTENANCE LOG
 A.4. LOWER A CAMERA INTO ISOLATOR ROW FOR VISUAL INSPECTION OF SEDIMENT LEVELS (OPTIONAL)
 A.5. IF SEDIMENT IS AT, OR ABOVE, 3\"/>

B. ALL ISOLATOR ROWS
 B.1. REMOVE COVER FROM STRUCTURE AT UPSTREAM END OF ISOLATOR ROW
 B.2. USING A FLASHLIGHT, INSPECT DOWN THE ISOLATOR ROW THROUGH OUTLET PIPE
 i) MIRRORS OR POLES OR CAMERAS MAY BE USED TO AVOID A CONFINED SPACE ENTRY
 ii) FOLLOW OSHA REGULATIONS FOR CONFINED SPACE ENTRY IF ENTERING MANHOLE
 B.3. IF SEDIMENT IS AT, OR ABOVE, 3\"/>

STEP 2) CLEAN OUT ISOLATOR ROW USING THE JETVAC PROCESS
 A. A FIXED CULVERT CLEANING NOZZLE WITH REAR FACING SPREAD OF 45\"/>

STEP 3) REPLACE ALL COVERS, GRATES, FILTERS, AND LIDS; RECORD OBSERVATIONS AND ACTIONS.

STEP 4) INSPECT AND CLEAN BASINS AND MANHOLES UPSTREAM OF THE STORMTECH SYSTEM.

NOTES

1. INSPECT EVERY 6 MONTHS DURING THE FIRST YEAR OF OPERATION. ADJUST THE INSPECTION INTERVAL BASED ON PREVIOUS OBSERVATIONS OF SEDIMENT ACCUMULATION AND HIGH WATER ELEVATIONS.
 2. CONDUCT JETTING AND VACTORING ANNUALLY OR WHEN INSPECTION SHOWS THAT MAINTENANCE IS NECESSARY.

| | | | |
|----------|------------------------|-------------|-----|
| DATE | 01/05/21 | ISSUED | N/A |
| SCALE | N/A | DESIGNED BY | AMS |
| | | DRAWN BY | AMS |
| | | APPROVED BY | MJS |
| DWG FILE | CIVIL\DRAINAGE DETAILS | | |

| | | |
|-----|---------------------------------------|----------|
| NO. | REVISIONS | DATE |
| 1 | DRAINAGE UPDATES | 02/02/21 |
| 2 | INITIAL ALTERNATE ENTRANCE SUBMISSION | 07/05/21 |
| | | AMS |
| | | INT. |

SEALED AND STAMPED BY: MICHAEL BEHRENDT, TOWN PLANNER, LICENSE NO. 1887

DATE: 01/05/21

SCALE: N/A

DESIGNED BY: AMS

DRAWN BY: AMS

APPROVED BY: MJS

DWG FILE: CIVIL\DRAINAGE DETAILS

CONSTRUCTION DETAILS

prepared for
TOOMERS, LLC

TAX MAP 5, LOTS 1-9 AND 1-10
19 MAIN ST AND 21 MAIN ST, DURHAM, NH 03824

MJS ENGINEERING, P.C.
 CIVIL • STRUCTURAL • ENVIRONMENTAL
 5 RAILROAD ST., P.O. BOX 359
 NEWBARK, NH 03857
 PHONE: (603) 659-4979, FAX: (603) 659-4627
 E-MAIL: info@mjs-engineering.com

JOB: 18-041

C-505